Proposal:270030 **Let Date:**January 21, 2027 **Call Order:**600
J/P Num:36319(04) **Proj. Num:**STP-210C(137)AD
Counties:CARTER
Description:PEDESTRIAN IMPROVEMENTS AND SIDEWALKS
SH-76: FROM THE INTERSECTION OF CITY STREET (1ST STREET),
EXTEND EAST IN THE CITY OF HEALDTON.
PROJECT LENGTH = 0.303 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	221(G)2800	TEMPORARY FIBER LOG	66.000	LF
0020	303(A)1200	AGGREGATE BASE TYPE A	269.000	CY
0030	509(B)0300	CLASS A CONCRETE	9.000	CY
0040	511(B)2300	EPOXY COATED REINFORCING STEEL	640.000	LB
0050	609(B)4375	2'-8" COMB.CRB.& GUT.(8" BARRIER)	1,481.000	LF
0060	610(A)5200	4" CONCRETE SIDEWALK	876.000	SY
0070	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	404.000	SY
0080	610(I)6000	TACTILE WARNING DEVICE-NEW	170.000	SF
0090	610(J)6100	(PL) STAMPED CONCRETE FINISH	158.000	SY
0100	612(A)3200	MANHOLES ADJUST TO GRADE	2.000	EA
0110	619(B)6356	REMOVAL OF CURB AND GUTTER	1,209.000	LF
0120	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	358.000	SY
0130	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	257.000	SY
0140	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	250.000	SY
0150	619(B)6404	REMOVAL OF SIDEWALK	882.000	SY
0160	619(C)6600	SAWING PAVEMENT	343.000	LF
0170	622(A)0200	PIPE RAILING	103.000	LF
0002	TRAFFIC CONTROL			
0180	880(A)6220	ARROW DISPLAY(TYPE C)	120.000	SD
0190	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,080.000	SD
0200	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,800.000	SD
0210	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,520.000	SD
0220	880(E)6600	WARNING LIGHTS(TYPE A)	1,560.000	SD
0230	880(G)6805	CHANNELIZER CONES	9,000.000	SD
0240	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	134.000	SD
0003	SIGNING AND STRIPING			
0250	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0260	850(A)1200	SHEET ALUMINUM SIGNS	5.000	SF
0270	851(C)2415	2" SQUARE TUBE POST	30.000	LF
0280	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	1,221.000	LF
0290	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	420.000	LF
0300	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	3.000	EA
0310	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	570.000	LF
0004	STAKING			
0320	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0330	641 2110	MOBILIZATION	1.000	LSUM