Proposal:270031 **Let Date:**January 21, 2027 **Call Order:**605
J/P Num:35788(04) **Proj. Num:**SBR-213B(040)SB
Counties:CIMARRON
Description:BRIDGE REHABILITATION
US-56: OVER UNNAMED CREEK, 2.14 MILES WEST OF
THE SH-171 JUNCTION NEAR KEYES.
PROJECT LENGTH = 0.086 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	200.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	200.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	800.000	LF
0040	230(A)7200	SOLID SLAB SODDING	1,000.000	SY
0050	303(A)1200	AGGREGATE BASE TYPE A	250.000	CY
0060	310(B)5300	SUBGRADE, METHOD B	915.000	SY
0070	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	90.000	TON
0080	407(B)7300	TACK COAT	230.000	GAL
0090	408 8100	PRIME COAT	320.000	GAL
0100	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	306.000	TON
0110	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	240.000	TON
0120	412 3100	COLD MILLING PAVEMENT	1,225.000	SY
0130	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	887.500	LF
0140	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0150	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	160.000	LF
0002	BRIDGE "A"			
0160	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	250.000	CY
0170	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0180	509(A)0210	CLASS AA CONCRETE	420.000	CY
0190	509(G)0800	PNEUMATICALLY PLACED MALP CONCRETE	61.000	SY
0200	511(B)2310	EPOXY COATED REINFORCING STEEL	64,410.000	LB
0210	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	47.000	LF
0220	520(C)1400	EPOXY RESIN, ABOVE WATER	5.000	GAL
0230	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	TRAFFIC TEMPORARY			
0240	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	360.000	SD
0250	857(C)9410	REMOVABLE PAVEMENT MARKING TAPE(8" WIDE)	820.000	LF
0260	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	500.000	LF
0270	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,000.000	SD
0280	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,000.000	SD
0290	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,500.000	SD
0300	880(C)6420	WING BARRICADES	360.000	SD
0310	880(E)6600	WARNING LIGHTS(TYPE A)	5,040.000	SD
0320	880(E)6607	WARNING LIGHTS(TYPE B)	2,880.000	SD
0330	880(E)6610	WARNING LIGHTS(TYPE C)	1,620.000	SD
0340	880(F)6700	DRUMS	3,240.000	SD
0350	880(G)6805	CHANNELIZER CONES	3,600.000	SD
0360	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	360.000	SD
0004	TRAFFIC PERMANENT			
0370	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	1,840.000	LF
0005	CONSTRUCTION			
0380	641 2100	MOBILIZATION	1.000	LSUM