Proposal:270047 **Let Date:**January 14, 2027 **Call Order:**504
J/P Num:34937(04) **Proj. Num:**STP-206D(085)CI
Counties:BLAINE
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW 0650): OVER SPRING CREEK,
3.37 MILES WEST OF THE SH- 8 JUNCTION NEAR OKEENE.
PROJECT LENGTH = 0.151 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(H)2900	EARTHWORK	1.000	LSUM
0020	221(B)2300	TEMPORARY SILT FENCE	350.000	LF
0030	221(E)2600	TEMPORARY SILT DIKE	250.000	LF
0040	230(A)7200	SOLID SLAB SODDING	5,500.000	SY
0050	233(A)0200	VEGETATIVE MULCHING	1.140	AC
0060	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	408.000	TON
0070	509(D)0500	CLASS C CONCRETE	10.000	CY
0080	853 5100	DELINEATORS(TYPE 1, CODE 1)	4.000	EA
0002	BRIDGE			
0090	202(A)2210	UNCLASSIFIED EXCAVATION	3,555.000	CY
0100	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	304.000	CY
0110	509(A)0210	CLASS AA CONCRETE	638.300	CY
0120	511(A)2210	REINFORCING STEEL	146,493.000	LB
0130	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	1,056.000	TON
0140	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC			
0150	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	360.000	SD
0160	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	540.000	SD
0170	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	900.000	SD
0180	880(E)6600	WARNING LIGHTS(TYPE A)	1,980.000	SD
0004	STAKING			
0190	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0200	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0210	641 2100	MOBILIZATION	1.000	LSUM