Letting Date: January 28, 2010, 10:30 A.M.
Call Order: 045 **Contract ID:** 100001
J/P No.: 23059(04) **Project No.:** BRO-105D(121)CO **Contract Time:**
County: BECKHAM
Description: BRIDGE AND APPROACHES COUNTY ROAD (NS-181): OVER TURKEY CREEK, 1.5 MILES SOUTH OF I-40 PROJECT LENGTH = 0.227 MILES

	VENDORNAME	PROPOSALITEMTO		
1	K & R BUILDERS, INC.	565,958.74	78.14	100.00
2	D. M. DOZERS, INC.	586,871.07	81.03	103.70
3	Cimarron Construction Company, LLC	664,415.02	91.73	117.40
4	OBC, INC.	667,794.87	92.20	117.99
	Engineer's Estimate	724,280.20		
5	EARTH BUILDERS, L.P.	725,816.70	100.21	128.25
6	Reece Construction Co, Inc.	955,056.05	131.86	168.75

Letting Date: January 28, 2010, 10:30 A.M.
Call Order: 045 **Contract ID:** 100001

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	202(A) 0183	UNCLASSIFIED EXCAVATION	2,585.000	CY	
	Engineer's Estimate		**5.50**		**14,217.50**
1	K & R BUILDERS, INC.		3.75		9,693.75
2	D. M. DOZERS, INC.		4.00		10,340.00
3	Cimarron Construction Company, LLC		10.00		25,850.00
4	OBC, INC.		6.50		16,802.50
5	EARTH BUILDERS, L.P.		8.00		20,680.00
6	Reece Construction Co, Inc.		9.71		25,100.35
0002	202(G) 0185	EARTHWORK	1.000	LSUM	
	Engineer's Estimate		**20,000.00**		**20,000.00**
1	K & R BUILDERS, INC.		21,500.00		21,500.00
2	D. M. DOZERS, INC.		30,000.00		30,000.00
3	Cimarron Construction Company, LLC		39,000.00		39,000.00
4	OBC, INC.		75,900.00		75,900.00
5	EARTH BUILDERS, L.P.		38,000.00		38,000.00
6	Reece Construction Co, Inc.		65,366.04		65,366.04
0003	223 2801	TEMPORARY SILT FENCE	1,500.000	LF	
	Engineer's Estimate		**2.50**		**3,750.00**
1	K & R BUILDERS, INC.		1.40		2,100.00
2	D. M. DOZERS, INC.		2.00		3,000.00
3	Cimarron Construction Company, LLC		2.00		3,000.00
4	OBC, INC.		2.00		3,000.00
5	EARTH BUILDERS, L.P.		1.80		2,700.00
6	Reece Construction Co, Inc.		1.30		1,950.00
0004	230(A) 2806	SOLID SLAB SODDING	11,500.000	SY	
	Engineer's Estimate		**2.50**		**28,750.00**
1	K & R BUILDERS, INC.		1.30		14,950.00
2	D. M. DOZERS, INC.		1.45		16,675.00
3	Cimarron Construction Company, LLC		1.55		17,825.00
4	OBC, INC.		1.35		15,525.00
5	EARTH BUILDERS, L.P.		1.80		20,700.00
6	Reece Construction Co, Inc.		1.29		14,835.00
0005	233(A) 2817	VEGETATIVE MULCHING	2.690	AC	
	Engineer's Estimate		**800.00**		**2,152.00**
1	K & R BUILDERS, INC.		250.00		672.50
2	D. M. DOZERS, INC.		200.00		538.00
3	Cimarron Construction Company, LLC		200.00		538.00
4	OBC, INC.		500.00		1,345.00
5	EARTH BUILDERS, L.P.		500.00		1,345.00
6	Reece Construction Co, Inc.		350.00		941.50
0006	303 5912	AGGREGATE BASE	1,159.000	TON	
	Engineer's Estimate		**28.00**		**32,452.00**
1	K & R BUILDERS, INC.		21.50		24,918.50
2	D. M. DOZERS, INC.		24.00		27,816.00
3	Cimarron Construction Company, LLC		24.00		27,816.00
4	OBC, INC.		30.60		35,465.40
5	EARTH BUILDERS, L.P.		25.00		28,975.00
6	Reece Construction Co, Inc.		32.04		37,134.36

Letting Date: January 28, 2010, 10:30 A.M.
Call Order: 045 **Contract ID:** 100001

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0001**	**ROADWAY**	
0007	509(D) 0325	CLASS C CONCRETE	81.400 CY
	Engineer's Estimate	**250.00**	**20,350.00**
1	K & R BUILDERS, INC.	255.00	20,757.00
2	D. M. DOZERS, INC.	200.00	16,280.00
3	Cimarron Construction Company, LLC	275.00	22,385.00
4	OBC, INC.	350.00	28,490.00
5	EARTH BUILDERS, L.P.	320.00	26,048.00
6	Reece Construction Co, Inc.	359.00	29,222.60
0008	613(CC) 7189	TYPE D4 CULVERT END TREATMENT	2.000 EA
	Engineer's Estimate	**1,800.00**	**3,600.00**
1	K & R BUILDERS, INC.	1,500.00	3,000.00
2	D. M. DOZERS, INC.	850.00	1,700.00
3	Cimarron Construction Company, LLC	1,600.00	3,200.00
4	OBC, INC.	1,680.00	3,360.00
5	EARTH BUILDERS, L.P.	1,400.00	2,800.00
6	Reece Construction Co, Inc.	1,950.00	3,900.00
0009	613(D) 0692	36" CORR. GALV. STEEL PIPE	46.000 LF
	Engineer's Estimate	**35.00**	**1,610.00**
1	K & R BUILDERS, INC.	31.00	1,426.00
2	D. M. DOZERS, INC.	30.00	1,380.00
3	Cimarron Construction Company, LLC	41.00	1,886.00
4	OBC, INC.	44.62	2,052.52
5	EARTH BUILDERS, L.P.	55.00	2,530.00
6	Reece Construction Co, Inc.	43.71	2,010.66

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0002**	**BRIDGE 'A'**	
0010	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	96.000 CY
	Engineer's Estimate	**20.00**	**1,920.00**
1	K & R BUILDERS, INC.	6.50	624.00
2	D. M. DOZERS, INC.	8.00	768.00
3	Cimarron Construction Company, LLC	8.00	768.00
4	OBC, INC.	22.00	2,112.00
5	EARTH BUILDERS, L.P.	8.00	768.00
6	Reece Construction Co, Inc.	26.00	2,496.00
0011	501(D) 6353	UNCLASSIFIED BACKFILL	114.000 CY
	Engineer's Estimate	**20.00**	**2,280.00**
1	K & R BUILDERS, INC.	8.50	969.00
2	D. M. DOZERS, INC.	10.00	1,140.00
3	Cimarron Construction Company, LLC	12.00	1,368.00
4	OBC, INC.	22.00	2,508.00
5	EARTH BUILDERS, L.P.	12.00	1,368.00
6	Reece Construction Co, Inc.	26.00	2,964.00

Letting Date: January 28, 2010, 10:30 A.M.
Call Order: 045 **Contract ID:** 100001

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A'					
0012	503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	416.170	LF	
	Engineer's Estimate		**200.00**		**83,234.00**
1	K & R BUILDERS, INC.		156.50		65,130.61
2	D. M. DOZERS, INC.		155.00		64,506.35
3	Cimarron Construction Company, LLC		159.50		66,379.12
4	OBC, INC.		183.00		76,159.11
5	EARTH BUILDERS, L.P.		180.00		74,910.60
6	Reece Construction Co, Inc.		237.00		98,632.29
0013	504(E) 1380	CONCRETE RAIL (TR1)	283.160	LF	
	Engineer's Estimate		**60.00**		**16,989.60**
1	K & R BUILDERS, INC.		55.00		15,573.80
2	D. M. DOZERS, INC.		45.00		12,742.20
3	Cimarron Construction Company, LLC		60.00		16,989.60
4	OBC, INC.		48.00		13,591.68
5	EARTH BUILDERS, L.P.		65.00		18,405.40
6	Reece Construction Co, Inc.		73.00		20,670.68
0014	506(A) 1322	STRUCTURAL STEEL	2,020.000	LB	
	Engineer's Estimate		**3.50**		**7,070.00**
1	K & R BUILDERS, INC.		2.90		5,858.00
2	D. M. DOZERS, INC.		3.00		6,060.00
3	Cimarron Construction Company, LLC		2.50		5,050.00
4	OBC, INC.		4.65		9,393.00
5	EARTH BUILDERS, L.P.		3.50		7,070.00
6	Reece Construction Co, Inc.		5.00		10,100.00
0015	509(A) 1326	CLASS AA CONCRETE	80.900	CY	
	Engineer's Estimate		**500.00**		**40,450.00**
1	K & R BUILDERS, INC.		425.00		34,382.50
2	D. M. DOZERS, INC.		500.00		40,450.00
3	Cimarron Construction Company, LLC		500.00		40,450.00
4	OBC, INC.		500.00		40,450.00
5	EARTH BUILDERS, L.P.		425.00		34,382.50
6	Reece Construction Co, Inc.		765.00		61,888.50
0016	509(B) 1328	CLASS A CONCRETE	63.800	CY	
	Engineer's Estimate		**525.00**		**33,495.00**
1	K & R BUILDERS, INC.		445.00		28,391.00
2	D. M. DOZERS, INC.		450.00		28,710.00
3	Cimarron Construction Company, LLC		500.00		31,900.00
4	OBC, INC.		485.00		30,943.00
5	EARTH BUILDERS, L.P.		400.00		25,520.00
6	Reece Construction Co, Inc.		751.00		47,913.80
0017	511(A) 1332	REINFORCING STEEL	26,889.000	LB	
	Engineer's Estimate		**0.90**		**24,200.10**
1	K & R BUILDERS, INC.		0.72		19,360.08
2	D. M. DOZERS, INC.		0.68		18,284.52
3	Cimarron Construction Company, LLC		0.70		18,822.30
4	OBC, INC.		0.89		23,931.21
5	EARTH BUILDERS, L.P.		0.80		21,511.20
6	Reece Construction Co, Inc.		0.60		16,133.40

Letting Date: January 28, 2010, 10:30 A.M.
Call Order: 045 **Contract ID:** 100001

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A'					
0018	514(A) 6010	PILES, FURNISHED (HP 10X42)	220.000	LF	
	Engineer's Estimate		**40.00**		**8,800.00**
1	K & R BUILDERS, INC.		20.00		4,400.00
2	D. M. DOZERS, INC.		20.00		4,400.00
3	Cimarron Construction Company, LLC		26.60		5,852.00
4	OBC, INC.		24.25		5,335.00
5	EARTH BUILDERS, L.P.		25.00		5,500.00
6	Reece Construction Co, Inc.		32.00		7,040.00
0019	514(A) 6011	PILES, FURNISHED (HP 12X53)	700.000	LF	
	Engineer's Estimate		**50.00**		**35,000.00**
1	K & R BUILDERS, INC.		27.00		18,900.00
2	D. M. DOZERS, INC.		24.00		16,800.00
3	Cimarron Construction Company, LLC		31.40		21,980.00
4	OBC, INC.		30.60		21,420.00
5	EARTH BUILDERS, L.P.		28.00		19,600.00
6	Reece Construction Co, Inc.		39.00		27,300.00
0020	514(B) 6292	PILES, DRIVEN (HP 10X42)	220.000	LF	
	Engineer's Estimate		**15.00**		**3,300.00**
1	K & R BUILDERS, INC.		5.00		1,100.00
2	D. M. DOZERS, INC.		6.00		1,320.00
3	Cimarron Construction Company, LLC		12.00		2,640.00
4	OBC, INC.		11.00		2,420.00
5	EARTH BUILDERS, L.P.		20.00		4,400.00
6	Reece Construction Co, Inc.		8.00		1,760.00
0021	514(B) 6294	PILES, DRIVEN (HP 12X53)	700.000	LF	
	Engineer's Estimate		**15.00**		**10,500.00**
1	K & R BUILDERS, INC.		6.00		4,200.00
2	D. M. DOZERS, INC.		6.00		4,200.00
3	Cimarron Construction Company, LLC		14.10		9,870.00
4	OBC, INC.		11.00		7,700.00
5	EARTH BUILDERS, L.P.		20.00		14,000.00
6	Reece Construction Co, Inc.		8.00		5,600.00
0022	601(A-1)1353	TYPE I-A PLAIN RIPRAP	5,972.000	TON	
	Engineer's Estimate		**35.00**		**209,020.00**
1	K & R BUILDERS, INC.		31.00		185,132.00
2	D. M. DOZERS, INC.		33.00		197,076.00
3	Cimarron Construction Company, LLC		35.50		212,006.00
4	OBC, INC.		25.60		152,883.20
5	EARTH BUILDERS, L.P.		39.00		232,908.00
6	Reece Construction Co, Inc.		45.26		270,292.72
0023	601(A-2)1355	TYPE I-A FILTER BLANKET	1,755.000	TON	
	Engineer's Estimate		**28.00**		**49,140.00**
1	K & R BUILDERS, INC.		24.00		42,120.00
2	D. M. DOZERS, INC.		27.00		47,385.00
3	Cimarron Construction Company, LLC		28.00		49,140.00
4	OBC, INC.		22.15		38,873.25
5	EARTH BUILDERS, L.P.		29.00		50,895.00
6	Reece Construction Co, Inc.		35.73		62,706.15

Letting Date: January 28, 2010, 10:30 A.M.
Call Order: 045 **Contract ID:** 100001

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A'**			
0024	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM	
	Engineer's Estimate		**10,000.00**	**10,000.00**
1	K & R BUILDERS, INC.		5,000.00	5,000.00
2	D. M. DOZERS, INC.		9,500.00	9,500.00
3	Cimarron Construction Company, LLC		10,000.00	10,000.00
4	OBC, INC.		15,000.00	15,000.00
5	EARTH BUILDERS, L.P.		6,500.00	6,500.00
6	Reece Construction Co, Inc.		33,708.00	33,708.00
0025	623(A) 1418	BEAM GUARD RAIL-W-BEAM-SINGLE	300.000 LF	
	Engineer's Estimate		**25.00**	**7,500.00**
1	K & R BUILDERS, INC.		15.00	4,500.00
2	D. M. DOZERS, INC.		15.00	4,500.00
3	Cimarron Construction Company, LLC		15.00	4,500.00
4	OBC, INC.		16.50	4,950.00
5	EARTH BUILDERS, L.P.		15.00	4,500.00
6	Reece Construction Co, Inc.		14.00	4,200.00
0026	623(F) 6032	GUARD RAIL ANCHOR UNIT (TYPE I)	1.000 EA	
	Engineer's Estimate		**3,000.00**	**3,000.00**
1	K & R BUILDERS, INC.		1,550.00	1,550.00
2	D. M. DOZERS, INC.		1,750.00	1,750.00
3	Cimarron Construction Company, LLC		1,550.00	1,550.00
4	OBC, INC.		1,925.00	1,925.00
5	EARTH BUILDERS, L.P.		1,800.00	1,800.00
6	Reece Construction Co, Inc.		1,450.00	1,450.00
0027	623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	3.000 EA	
	Engineer's Estimate		**3,000.00**	**9,000.00**
1	K & R BUILDERS, INC.		1,950.00	5,850.00
2	D. M. DOZERS, INC.		1,850.00	5,550.00
3	Cimarron Construction Company, LLC		1,950.00	5,850.00
4	OBC, INC.		2,000.00	6,000.00
5	EARTH BUILDERS, L.P.		2,500.00	7,500.00
6	Reece Construction Co, Inc.		1,800.00	5,400.00
0028	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	K & R BUILDERS, INC.		3,100.00	3,100.00
2	D. M. DOZERS, INC.		2,600.00	2,600.00
3	Cimarron Construction Company, LLC		3,000.00	3,000.00
4	OBC, INC.		2,860.00	2,860.00
5	EARTH BUILDERS, L.P.		4,500.00	4,500.00
6	Reece Construction Co, Inc.		2,540.00	2,540.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003	**STAKING**			

Letting Date: January 28, 2010, 10:30 A.M.

Call Order: 045 **Contract ID:** 100001

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0003**	**STAKING**	
0029	642 0098	STAKING	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	K & R BUILDERS, INC.	3,800.00	3,800.00
2	D. M. DOZERS, INC.	4,900.00	4,900.00
3	Cimarron Construction Company, LLC	3,400.00	3,400.00
4	OBC, INC.	5,400.00	5,400.00
5	EARTH BUILDERS, L.P.	6,000.00	6,000.00
6	Reece Construction Co, Inc.	4,200.00	4,200.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0004**	**CONSTRUCTION**	
0030	220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**7,500.00**	**7,500.00**
1	K & R BUILDERS, INC.	2,500.00	2,500.00
2	D. M. DOZERS, INC.	2,000.00	2,000.00
3	Cimarron Construction Company, LLC	4,200.00	4,200.00
4	OBC, INC.	2,000.00	2,000.00
5	EARTH BUILDERS, L.P.	2,000.00	2,000.00
6	Reece Construction Co, Inc.	2,000.00	2,000.00
0031	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**25,000.00**	**25,000.00**
1	K & R BUILDERS, INC.	14,500.00	14,500.00
2	D. M. DOZERS, INC.	4,500.00	4,500.00
3	Cimarron Construction Company, LLC	7,200.00	7,200.00
4	OBC, INC.	20,000.00	20,000.00
5	EARTH BUILDERS, L.P.	38,000.00	38,000.00
6	Reece Construction Co, Inc.	85,600.00	85,600.00