Letting Date: October 21, 2010, 10:30 A.M.
Call Order: 590 **Contract ID:** 100588
J/P No.: 14971(13) **Project No.:** NHY-008N(019) **Contract Time:**
County: TEXAS
Description: GRADE, DRAIN, AND SURFACE US-54: FROM 5.5 MILES SOUTHWEST OF THE SH-94 JUNCTION, EXTEND NORTHEAST. PROJECT LENGTH = 5.284

	VENDORNAME	PROPOSALITEMTO		
1	DOBSON BROTHERS CONSTRUCTION CO.	9,958,921.28	91.17	100.00
2	J & R SAND COMPANY, INC.	10,376,291.47	94.99	104.19
	Engineer's Estimate	10,923,661.75		
3	R. K. Hall, LLC	10,999,346.79	100.69	110.45

Letting Date: October 21, 2010, 10:30 A.M.
Call Order: 590 **Contract ID:** 100588

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	201 0102	CLEARING AND GRUBBING	1.000	LSUM
	Engineer's Estimate		**15,000.00**	**15,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		8,800.00	8,800.00
2	J & R SAND COMPANY, INC.		10,000.00	10,000.00
3	R. K. Hall, LLC		15,729.13	15,729.13
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	20,704.000	CY
	Engineer's Estimate		**5.00**	**103,520.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		3.25	67,288.00
2	J & R SAND COMPANY, INC.		7.50	155,280.00
3	R. K. Hall, LLC		5.19	107,453.76
0003	202(C) 0184	UNCLASSIFIED BORROW	5,000.000	CY
	Engineer's Estimate		**8.00**	**40,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		11.25	56,250.00
2	J & R SAND COMPANY, INC.		7.50	37,500.00
3	R. K. Hall, LLC		9.18	45,900.00
0004	205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
	Engineer's Estimate		**25,000.00**	**25,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		19,450.00	19,450.00
2	J & R SAND COMPANY, INC.		10,000.00	10,000.00
3	R. K. Hall, LLC		85,335.29	85,335.29
0005	223 2801	TEMPORARY SILT FENCE	48,585.000	LF
	Engineer's Estimate		**3.00**	**145,755.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		1.52	73,849.20
2	J & R SAND COMPANY, INC.		1.60	77,736.00
3	R. K. Hall, LLC		1.48	71,905.80
0006	227 0100	TEMPORARY SILT DIKE	310.000	LF
	Engineer's Estimate		**7.00**	**2,170.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		7.36	2,281.60
2	J & R SAND COMPANY, INC.		9.80	3,038.00
3	R. K. Hall, LLC		7.14	2,213.40
0007	230(A) 2806	SOLID SLAB SODDING	76,966.000	SY
	Engineer's Estimate		**2.50**	**192,415.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		1.79	137,769.14
2	J & R SAND COMPANY, INC.		1.55	119,297.30
3	R. K. Hall, LLC		1.73	133,151.18
0008	230(F) 2812	WATERING	3,080.000	MGAL
	Engineer's Estimate		**40.00**	**123,200.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		10.52	32,401.60
2	J & R SAND COMPANY, INC.		11.00	33,880.00
3	R. K. Hall, LLC		18.85	58,058.00
0009	233(A) 2817	VEGETATIVE MULCHING	15.900	AC
	Engineer's Estimate		**500.00**	**7,950.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		473.20	7,523.88
2	J & R SAND COMPANY, INC.		200.00	3,180.00
3	R. K. Hall, LLC		459.00	7,298.10

Letting Date: October 21, 2010, 10:30 A.M.
Call Order: 590 **Contract ID:** 100588

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0010	241 2832	MOWING	15.900	AC
	Engineer's Estimate		**125.00**	**1,987.50**
1	DOBSON BROTHERS CONSTRUCTION CO.		52.58	836.02
2	J & R SAND COMPANY, INC.		100.00	1,590.00
3	R. K. Hall, LLC		51.00	810.90
0011	327(A) 4200	(SP)FLY ASH	8,819.000	TON
	Engineer's Estimate		**65.00**	**573,235.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		75.00	661,425.00
2	J & R SAND COMPANY, INC.		77.00	679,063.00
3	R. K. Hall, LLC		67.18	592,460.42
0012	327(D) 4230	(SP)LIME	869.000	TON
	Engineer's Estimate		**130.00**	**112,970.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		150.00	130,350.00
2	J & R SAND COMPANY, INC.		178.00	154,682.00
3	R. K. Hall, LLC		174.03	151,232.07
0013	327(E) 4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	164,112.000	SY
	Engineer's Estimate		**5.00**	**820,560.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		1.35	221,551.20
2	J & R SAND COMPANY, INC.		2.50	410,280.00
3	R. K. Hall, LLC		1.95	320,018.40
0014	327(G) 4260	(SP)LIME PRETREATMENT	48,009.000	SY
	Engineer's Estimate		**4.00**	**192,036.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		0.40	19,203.60
2	J & R SAND COMPANY, INC.		1.25	60,011.25
3	R. K. Hall, LLC		1.44	69,132.96
0015	403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1,691.000	TON
	Engineer's Estimate		**35.00**	**59,185.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		47.32	80,018.12
2	J & R SAND COMPANY, INC.		35.00	59,185.00
3	R. K. Hall, LLC		30.84	52,150.44
0016	407 0250	TACK COAT	30,925.000	GAL
	Engineer's Estimate		**2.50**	**77,312.50**
1	DOBSON BROTHERS CONSTRUCTION CO.		2.53	78,240.25
2	J & R SAND COMPANY, INC.		2.15	66,488.75
3	R. K. Hall, LLC		3.01	93,084.25
0017	408 5774	PRIME COAT	27,001.000	GAL
	Engineer's Estimate		**2.50**	**67,502.50**
1	DOBSON BROTHERS CONSTRUCTION CO.		4.06	109,624.06
2	J & R SAND COMPANY, INC.		4.25	114,754.25
3	R. K. Hall, LLC		3.83	103,413.83
0018	411(S3) 5935	(SP)ASPHALT CONCRETE TYPE S3(PG 76-28 OK)	18,623.000	TON
	Engineer's Estimate		**60.00**	**1,117,380.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		62.60	1,165,799.80
2	J & R SAND COMPANY, INC.		67.00	1,247,741.00
3	R. K. Hall, LLC		72.04	1,341,600.92

Letting Date: October 21, 2010, 10:30 A.M.
Call Order: 590 **Contract ID:** 100588

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0019	411(S3) 5945	(SP)ASPHALT CONCRETE TYPE S3(PG 64-22 OK)	93,531.000	TON
	Engineer's Estimate		**54.00**	**5,050,674.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		54.85	5,130,175.35
2	J & R SAND COMPANY, INC.		54.00	5,050,674.00
3	R. K. Hall, LLC		60.70	5,677,331.70
0020	411(S4) 5950	(SP)ASPHALT CONCRETE TYPE S4(PG 76-28 OK)	12,098.000	TON
	Engineer's Estimate		**67.00**	**810,566.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		72.60	878,314.80
2	J & R SAND COMPANY, INC.		77.00	931,546.00
3	R. K. Hall, LLC		82.31	995,786.38
0021	411(S4) 5960	(SP)ASPHALT CONCRETE TYPE S4(PG 64-22 OK)	3,733.000	TON
	Engineer's Estimate		**61.00**	**227,713.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		58.75	219,313.75
2	J & R SAND COMPANY, INC.		58.00	216,514.00
3	R. K. Hall, LLC		64.33	240,143.89
0022	413(A) 4861	RUMBLE STRIP-METHOD AC-CON	55,800.000	LF
	Engineer's Estimate		**0.50**	**27,900.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		0.11	6,138.00
2	J & R SAND COMPANY, INC.		0.05	2,790.00
3	R. K. Hall, LLC		0.20	11,160.00
0023	417 4267	COLD MILLING BITUMINOUS PAVEMENT	32,900.000	SY
	Engineer's Estimate		**5.00**	**164,500.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		3.26	107,254.00
2	J & R SAND COMPANY, INC.		4.50	148,050.00
3	R. K. Hall, LLC		1.60	52,640.00
0024	509(D) 0325	CLASS C CONCRETE	50.000	CY
	Engineer's Estimate		**290.00**	**14,500.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		304.95	15,247.50
2	J & R SAND COMPANY, INC.		320.00	16,000.00
3	R. K. Hall, LLC		410.98	20,549.00
0025	609(B) 1514	1'-8" COMB. CURB & GUTTER (8" BARRIER)	3,400.000	LF
	Engineer's Estimate		**20.00**	**68,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		21.03	71,502.00
2	J & R SAND COMPANY, INC.		25.00	85,000.00
3	R. K. Hall, LLC		15.12	51,408.00
0026	613(CC) 7198	TYPE C6 CULVERT END TREATMENT	2.000	EA
	Engineer's Estimate		**1,340.00**	**2,680.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		1,577.34	3,154.68
2	J & R SAND COMPANY, INC.		2,800.00	5,600.00
3	R. K. Hall, LLC		2,739.67	5,479.34
0027	613(D) 0692	36" CORR. GALV. STEEL PIPE	86.000	LF
	Engineer's Estimate		**56.00**	**4,816.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		58.89	5,064.54
2	J & R SAND COMPANY, INC.		50.00	4,300.00
3	R. K. Hall, LLC		35.01	3,010.86

Letting Date: October 21, 2010, 10:30 A.M.
Call Order: 590 **Contract ID:** 100588

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0001	**ROADWAY**		
0028	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000 LSUM
	Engineer's Estimate	**10,000.00**	**10,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	8,496.28	8,496.28
2	J & R SAND COMPANY, INC.	7,500.00	7,500.00
3	R. K. Hall, LLC	5,681.97	5,681.97
0029	619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	4,084.000 SY
	Engineer's Estimate	**4.25**	**17,357.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	3.26	13,313.84
2	J & R SAND COMPANY, INC.	4.50	18,378.00
3	R. K. Hall, LLC	4.59	18,745.56
0030	619(C) 0924	SAWING PAVEMENT	900.000 LF
	Engineer's Estimate	**5.00**	**4,500.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	4.21	3,789.00
2	J & R SAND COMPANY, INC.	4.50	4,050.00
3	R. K. Hall, LLC	2.78	2,502.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002	**TRAFFIC SIGNING AND STRIPING**		
0031	850(A) 8110	SHEET ALUMINUM SIGNS	180.000 SF
	Engineer's Estimate	**13.00**	**2,340.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	11.68	2,102.40
2	J & R SAND COMPANY, INC.	15.00	2,700.00
3	R. K. Hall, LLC	15.51	2,791.80
0032	851(C) 8327	2 1/4" SQUARE TUBE POST	120.000 LF
	Engineer's Estimate	**7.50**	**900.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	21.24	2,548.80
2	J & R SAND COMPANY, INC.	10.00	1,200.00
3	R. K. Hall, LLC	10.34	1,240.80
0033	855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	144,099.000 LF
	Engineer's Estimate	**0.50**	**72,049.50**
1	DOBSON BROTHERS CONSTRUCTION CO.	0.69	99,428.31
2	J & R SAND COMPANY, INC.	0.33	47,552.67
3	R. K. Hall, LLC	0.36	51,875.64
0034	855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	74.000 EA
	Engineer's Estimate	**100.00**	**7,400.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	90.29	6,681.46
2	J & R SAND COMPANY, INC.	114.00	8,436.00
3	R. K. Hall, LLC	117.86	8,721.64

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003	**TEMPORARY TRAFFIC CONTROL**		

Letting Date: October 21, 2010, 10:30 A.M.
Call Order: 590 **Contract ID:** 100588

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0003	**TEMPORARY TRAFFIC CONTROL**				
0035	856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	71,600.000	LF	
	Engineer's Estimate		**0.50**		**35,800.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		0.53		37,948.00
2	J & R SAND COMPANY, INC.		0.70		50,120.00
3	R. K. Hall, LLC		0.72		51,552.00
0036	856(G) 8890	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS(FLEX TAB)TYF	14,320.000	EA	
	Engineer's Estimate		**0.50**		**7,160.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		0.53		7,589.60
2	J & R SAND COMPANY, INC.		0.50		7,160.00
3	R. K. Hall, LLC		0.52		7,446.40
0037	880(A) 8815	ARROW DISPLAY(TYPE C)	2.000	EA	
	Engineer's Estimate		**5,000.00**		**10,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		4,248.72		8,497.44
2	J & R SAND COMPANY, INC.		3,000.00		6,000.00
3	R. K. Hall, LLC		3,101.68		6,203.36
0038	880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	10,780.000	SD	
	Engineer's Estimate		**0.50**		**5,390.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		0.27		2,910.60
2	J & R SAND COMPANY, INC.		0.25		2,695.00
3	R. K. Hall, LLC		0.26		2,802.80
0039	880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,920.000	SD	
	Engineer's Estimate		**0.60**		**2,352.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		2.12		8,310.40
2	J & R SAND COMPANY, INC.		0.75		2,940.00
3	R. K. Hall, LLC		0.78		3,057.60
0040	880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,595.000	SD	
	Engineer's Estimate		**1.60**		**12,152.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		2.12		16,101.40
2	J & R SAND COMPANY, INC.		1.50		11,392.50
3	R. K. Hall, LLC		1.55		11,772.25
0041	880(C) 8842	BARRICADES(TYPE III)	2,205.000	SD	
	Engineer's Estimate		**1.15**		**2,535.75**
1	DOBSON BROTHERS CONSTRUCTION CO.		2.12		4,674.60
2	J & R SAND COMPANY, INC.		1.00		2,205.00
3	R. K. Hall, LLC		1.03		2,271.15
0042	880(C) 8848	WING BARRICADES	1,960.000	SD	
	Engineer's Estimate		**0.35**		**686.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		0.27		529.20
2	J & R SAND COMPANY, INC.		1.00		1,960.00
3	R. K. Hall, LLC		1.03		2,018.80
0043	880(E) 8860	WARNING LIGHTS(TYPE A)	4,410.000	SD	
	Engineer's Estimate		**0.20**		**882.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		0.53		2,337.30
2	J & R SAND COMPANY, INC.		0.20		882.00
3	R. K. Hall, LLC		0.21		926.10

Letting Date: October 21, 2010, 10:30 A.M.
Call Order: 590 **Contract ID:** 100588

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003	**TEMPORARY TRAFFIC CONTROL**		
0044	880(E) 8872	WARNING LIGHTS(TYPE C)	45,325.000 SD
	Engineer's Estimate	**0.05**	**2,266.25**
1	DOBSON BROTHERS CONSTRUCTION CO.	0.16	7,252.00
2	J & R SAND COMPANY, INC.	0.08	3,626.00
3	R. K. Hall, LLC	0.08	3,626.00
0045	880(F) 8878	DRUMS	45,325.000 SD
	Engineer's Estimate	**0.20**	**9,065.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	0.16	7,252.00
2	J & R SAND COMPANY, INC.	0.20	9,065.00
3	R. K. Hall, LLC	0.21	9,518.25
0046	880(G) 8890	CHANNELIZER CONES	45,325.000 SD
	Engineer's Estimate	**0.15**	**6,798.75**
1	DOBSON BROTHERS CONSTRUCTION CO.	0.16	7,252.00
2	J & R SAND COMPANY, INC.	0.15	6,798.75
3	R. K. Hall, LLC	0.16	7,252.00
0047	882(A) 8303	PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA
	Engineer's Estimate	**20,000.00**	**80,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	16,145.14	64,580.56
2	J & R SAND COMPANY, INC.	15,000.00	60,000.00
3	R. K. Hall, LLC	15,508.38	62,033.52

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004	**STAKING**		
0048	642 0098	STAKING	1.000 LSUM
	Engineer's Estimate	**25,000.00**	**25,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	95,000.00	95,000.00
2	J & R SAND COMPANY, INC.	31,450.00	31,450.00
3	R. K. Hall, LLC	39,942.03	39,942.03

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0005	**CONSTRUCTION**		
0049	220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**8,000.00**	**8,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	3,500.00	3,500.00
2	J & R SAND COMPANY, INC.	6,000.00	6,000.00
3	R. K. Hall, LLC	8,907.10	8,907.10
0050	641 1552	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**510,000.00**	**510,000.00**
1	DOBSON BROTHERS CONSTRUCTION CO.	200,000.00	200,000.00
2	J & R SAND COMPANY, INC.	320,000.00	320,000.00
3	R. K. Hall, LLC	345,000.00	345,000.00

Letting Date: October 21, 2010, 10:30 A.M.

Call Order: 590 **Contract ID:** 100588

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0005	**CONSTRUCTION**			
0051	643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000 LSUM	
	Engineer's Estimate		**42,500.00**	**42,500.00**
1	DOBSON BROTHERS CONSTRUCTION CO.		40,000.00	40,000.00
2	J & R SAND COMPANY, INC.		60,000.00	60,000.00
3	R. K. Hall, LLC		35,000.00	35,000.00