Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 420 **Contract ID:** 110011
J/P No.: 25639(04) **Project No.:** BRO-NBIL(129)CO **Contract Time:**
County: MAYES
Description: BRIDGE AND APPROACHES COUNTY ROAD (NS-433): OVER SALT CREEK, 1.50 MILES NORTH OF THE SH-20 JUNCTION. PROJECT LENGTH = 0.190 MILES

	VENDORNAME	PROPOSALITEMTO		
1	BECCO CONTRACTORS, INC.	533,112.80	99.02	100.00
	Engineer's Estimate	538,399.05		
2	BEACHNER CONSTRUCTION CO., INC.	547,342.68	101.66	102.67
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	593,754.75	110.28	111.38
4	C-GAWF CONSTRUCTION, INC.	647,998.00	120.36	121.55
5	K & R BUILDERS, INC.	699,592.62	129.94	131.23

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 420 **Contract ID:** 110011

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0001	201(A) 0102	CLEARING AND GRUBBING	1.000 LSUM	
	Engineer's Estimate		**2,500.00**	**2,500.00**
1	BECCO CONTRACTORS, INC.		7,000.00	7,000.00
2	BEACHNER CONSTRUCTION CO., INC.		3,000.00	3,000.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		12,000.00	12,000.00
4	C-GAWF CONSTRUCTION, INC.		7,500.00	7,500.00
5	K & R BUILDERS, INC.		4,500.00	4,500.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	2,481.000 CY	
	Engineer's Estimate		**5.00**	**12,405.00**
1	BECCO CONTRACTORS, INC.		6.00	14,886.00
2	BEACHNER CONSTRUCTION CO., INC.		4.00	9,924.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		7.00	17,367.00
4	C-GAWF CONSTRUCTION, INC.		7.50	18,607.50
5	K & R BUILDERS, INC.		7.00	17,367.00
0003	202(D) 0184	UNCLASSIFIED BORROW	2,966.000 CY	
	Engineer's Estimate		**6.50**	**19,279.00**
1	BECCO CONTRACTORS, INC.		9.00	26,694.00
2	BEACHNER CONSTRUCTION CO., INC.		6.00	17,796.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		12.00	35,592.00
4	C-GAWF CONSTRUCTION, INC.		8.50	25,211.00
5	K & R BUILDERS, INC.		10.00	29,660.00
0004	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000 LSUM	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	BECCO CONTRACTORS, INC.		10,000.00	10,000.00
2	BEACHNER CONSTRUCTION CO., INC.		4,000.00	4,000.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		4,000.00	4,000.00
4	C-GAWF CONSTRUCTION, INC.		7,500.00	7,500.00
5	K & R BUILDERS, INC.		4,500.00	4,500.00
0005	221(C) 2801	TEMPORARY SILT FENCE	1,745.000 LF	
	Engineer's Estimate		**2.00**	**3,490.00**
1	BECCO CONTRACTORS, INC.		2.00	3,490.00
2	BEACHNER CONSTRUCTION CO., INC.		2.00	3,490.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		2.50	4,362.50
4	C-GAWF CONSTRUCTION, INC.		2.00	3,490.00
5	K & R BUILDERS, INC.		2.00	3,490.00
0006	221(F) 0100	TEMPORARY SILT DIKE	160.000 LF	
	Engineer's Estimate		**6.50**	**1,040.00**
1	BECCO CONTRACTORS, INC.		7.00	1,120.00
2	BEACHNER CONSTRUCTION CO., INC.		10.00	1,600.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		8.00	1,280.00
4	C-GAWF CONSTRUCTION, INC.		7.00	1,120.00
5	K & R BUILDERS, INC.		9.00	1,440.00
0007	229 4318	DITCH LINER PROTECTION	517.000 LF	
	Engineer's Estimate		**10.00**	**5,170.00**
1	BECCO CONTRACTORS, INC.		2.00	1,034.00
2	BEACHNER CONSTRUCTION CO., INC.		1.99	1,028.83
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		2.50	1,292.50
4	C-GAWF CONSTRUCTION, INC.		3.00	1,551.00
5	K & R BUILDERS, INC.		2.36	1,220.12

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 420 **Contract ID:** 110011

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0008	230(A) 2806	SOLID SLAB SODDING	2,960.000	SY	
	Engineer's Estimate		**1.70**		**5,032.00**
1	BECCO CONTRACTORS, INC.		2.00		5,920.00
2	BEACHNER CONSTRUCTION CO., INC.		1.59		4,706.40
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		2.00		5,920.00
4	C-GAWF CONSTRUCTION, INC.		3.00		8,880.00
5	K & R BUILDERS, INC.		1.88		5,564.80
0009	233(A) 2817	VEGETATIVE MULCHING	0.810	AC	
	Engineer's Estimate		**300.00**		**243.00**
1	BECCO CONTRACTORS, INC.		100.00		81.00
2	BEACHNER CONSTRUCTION CO., INC.		85.00		68.85
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		150.00		121.50
4	C-GAWF CONSTRUCTION, INC.		500.00		405.00
5	K & R BUILDERS, INC.		85.00		68.85
0010	303(A) 2100	AGGREGATE BASE TYPE A	589.000	CY	
	Engineer's Estimate		**42.00**		**24,738.00**
1	BECCO CONTRACTORS, INC.		40.00		23,560.00
2	BEACHNER CONSTRUCTION CO., INC.		35.00		20,615.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		42.00		24,738.00
4	C-GAWF CONSTRUCTION, INC.		38.00		22,382.00
5	K & R BUILDERS, INC.		58.00		34,162.00
0011	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	103.000	TON	
	Engineer's Estimate		**24.00**		**2,472.00**
1	BECCO CONTRACTORS, INC.		20.00		2,060.00
2	BEACHNER CONSTRUCTION CO., INC.		20.00		2,060.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		25.00		2,575.00
4	C-GAWF CONSTRUCTION, INC.		20.00		2,060.00
5	K & R BUILDERS, INC.		40.00		4,120.00
0012	407(B) 0250	TACK COAT	144.000	GAL	
	Engineer's Estimate		**3.00**		**432.00**
1	BECCO CONTRACTORS, INC.		3.00		432.00
2	BEACHNER CONSTRUCTION CO., INC.		3.90		561.60
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		2.00		288.00
4	C-GAWF CONSTRUCTION, INC.		6.50		936.00
5	K & R BUILDERS, INC.		3.10		446.40
0013	408 5774	PRIME COAT	847.000	GAL	
	Engineer's Estimate		**6.00**		**5,082.00**
1	BECCO CONTRACTORS, INC.		3.00		2,541.00
2	BEACHNER CONSTRUCTION CO., INC.		4.00		3,388.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		2.00		1,694.00
4	C-GAWF CONSTRUCTION, INC.		5.00		4,235.00
5	K & R BUILDERS, INC.		9.30		7,877.10
0014	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	487.000	TON	
	Engineer's Estimate		**65.00**		**31,655.00**
1	BECCO CONTRACTORS, INC.		50.00		24,350.00
2	BEACHNER CONSTRUCTION CO., INC.		67.00		32,629.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		60.00		29,220.00
4	C-GAWF CONSTRUCTION, INC.		89.00		43,343.00
5	K & R BUILDERS, INC.		90.00		43,830.00

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 420 **Contract ID:** 110011

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0015	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	372.000	TON	
	Engineer's Estimate		**70.00**		**26,040.00**
1	BECCO CONTRACTORS, INC.		65.00		24,180.00
2	BEACHNER CONSTRUCTION CO., INC.		85.75		31,899.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		72.00		26,784.00
4	C-GAWF CONSTRUCTION, INC.		94.00		34,968.00
5	K & R BUILDERS, INC.		110.00		40,920.00
0016	509(D) 0325	CLASS C CONCRETE	38.000	CY	
	Engineer's Estimate		**300.00**		**11,400.00**
1	BECCO CONTRACTORS, INC.		300.00		11,400.00
2	BEACHNER CONSTRUCTION CO., INC.		400.00		15,200.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		200.00		7,600.00
4	C-GAWF CONSTRUCTION, INC.		250.00		9,500.00
5	K & R BUILDERS, INC.		350.00		13,300.00
0017	611(G) 5705	INLET CDI RCP DES. 2	1.000	EA	
	Engineer's Estimate		**1,500.00**		**1,500.00**
1	BECCO CONTRACTORS, INC.		3,500.00		3,500.00
2	BEACHNER CONSTRUCTION CO., INC.		1,250.00		1,250.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		1,500.00		1,500.00
4	C-GAWF CONSTRUCTION, INC.		3,500.00		3,500.00
5	K & R BUILDERS, INC.		3,000.00		3,000.00
0018	613(A) 0492	24" R.C.PIPE CLASS III	56.000	LF	
	Engineer's Estimate		**38.00**		**2,128.00**
1	BECCO CONTRACTORS, INC.		55.00		3,080.00
2	BEACHNER CONSTRUCTION CO., INC.		42.00		2,352.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		60.00		3,360.00
4	C-GAWF CONSTRUCTION, INC.		53.00		2,968.00
5	K & R BUILDERS, INC.		80.00		4,480.00
0019	613(L) 5730	24" PREFAB. CULVERT END SECTION, ROUND	1.000	EA	
	Engineer's Estimate		**740.00**		**740.00**
1	BECCO CONTRACTORS, INC.		900.00		900.00
2	BEACHNER CONSTRUCTION CO., INC.		710.00		710.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		650.00		650.00
4	C-GAWF CONSTRUCTION, INC.		850.00		850.00
5	K & R BUILDERS, INC.		1,000.00		1,000.00
0020	613(T) 1187	STANDARD BEDDING MATERIAL, CLASS C	15.000	CY	
	Engineer's Estimate		**33.00**		**495.00**
1	BECCO CONTRACTORS, INC.		40.00		600.00
2	BEACHNER CONSTRUCTION CO., INC.		62.00		930.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		22.00		330.00
4	C-GAWF CONSTRUCTION, INC.		65.00		975.00
5	K & R BUILDERS, INC.		61.00		915.00
0021	613(V) 1180	TRENCH EXCAVATION	24.000	CY	
	Engineer's Estimate		**20.00**		**480.00**
1	BECCO CONTRACTORS, INC.		20.00		480.00
2	BEACHNER CONSTRUCTION CO., INC.		6.00		144.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		25.00		600.00
4	C-GAWF CONSTRUCTION, INC.		15.00		360.00
5	K & R BUILDERS, INC.		15.00		360.00

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 420 **Contract ID:** 110011

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0001	**ROADWAY**		
0022	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000 LSUM
	Engineer's Estimate	**2,500.00**	**2,500.00**
1	BECCO CONTRACTORS, INC.	2,000.00	2,000.00
2	BEACHNER CONSTRUCTION CO., INC.	1,500.00	1,500.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	4,000.00	4,000.00
4	C-GAWF CONSTRUCTION, INC.	5,500.00	5,500.00
5	K & R BUILDERS, INC.	3,500.00	3,500.00
0023	619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	1,925.000 SY
	Engineer's Estimate	**2.00**	**3,850.00**
1	BECCO CONTRACTORS, INC.	3.00	5,775.00
2	BEACHNER CONSTRUCTION CO., INC.	3.00	5,775.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	5.00	9,625.00
4	C-GAWF CONSTRUCTION, INC.	2.00	3,850.00
5	K & R BUILDERS, INC.	4.00	7,700.00
0024	619(C) 0924	SAWING PAVEMENT	38.000 LF
	Engineer's Estimate	**5.00**	**190.00**
1	BECCO CONTRACTORS, INC.	5.00	190.00
2	BEACHNER CONSTRUCTION CO., INC.	5.00	190.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	4.00	152.00
4	C-GAWF CONSTRUCTION, INC.	6.00	228.00
5	K & R BUILDERS, INC.	16.00	608.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A'**		
0025	501(F) 6352	GRANULAR BACKFILL	18.000 CY
	Engineer's Estimate	**40.00**	**720.00**
1	BECCO CONTRACTORS, INC.	35.00	630.00
2	BEACHNER CONSTRUCTION CO., INC.	85.00	1,530.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	65.00	1,170.00
4	C-GAWF CONSTRUCTION, INC.	65.00	1,170.00
5	K & R BUILDERS, INC.	70.00	1,260.00
0026	503(A) 6123	PRESTRESSED CONCRETE BEAMS	733.250 LF
	Engineer's Estimate	**225.00**	**164,981.25**
1	BECCO CONTRACTORS, INC.	180.00	131,985.00
2	BEACHNER CONSTRUCTION CO., INC.	220.00	161,315.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	225.00	164,981.25
4	C-GAWF CONSTRUCTION, INC.	290.00	212,642.50
5	K & R BUILDERS, INC.	275.00	201,643.75
0027	504(A) 1304	APPROACH SLAB	102.000 SY
	Engineer's Estimate	**150.00**	**15,300.00**
1	BECCO CONTRACTORS, INC.	160.00	16,320.00
2	BEACHNER CONSTRUCTION CO., INC.	195.00	19,890.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	170.00	17,340.00
4	C-GAWF CONSTRUCTION, INC.	175.00	17,850.00
5	K & R BUILDERS, INC.	225.00	22,950.00

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 420 **Contract ID:** 110011

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A'					
0028	504(D) 6239	CONCRETE RAIL (TR3)	274.000	LF	
	Engineer's Estimate		**60.00**		**16,440.00**
1	BECCO CONTRACTORS, INC.		70.00		19,180.00
2	BEACHNER CONSTRUCTION CO., INC.		55.00		15,070.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		68.00		18,632.00
4	C-GAWF CONSTRUCTION, INC.		75.00		20,550.00
5	K & R BUILDERS, INC.		72.00		19,728.00
0029	509(B) 1328	CLASS A CONCRETE	42.000	CY	
	Engineer's Estimate		**420.00**		**17,640.00**
1	BECCO CONTRACTORS, INC.		500.00		21,000.00
2	BEACHNER CONSTRUCTION CO., INC.		450.00		18,900.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		550.00		23,100.00
4	C-GAWF CONSTRUCTION, INC.		550.00		23,100.00
5	K & R BUILDERS, INC.		750.00		31,500.00
0030	511(A) 1332	REINFORCING STEEL	6,984.000	LB	
	Engineer's Estimate		**0.95**		**6,634.80**
1	BECCO CONTRACTORS, INC.		1.20		8,380.80
2	BEACHNER CONSTRUCTION CO., INC.		1.00		6,984.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		1.00		6,984.00
4	C-GAWF CONSTRUCTION, INC.		2.00		13,968.00
5	K & R BUILDERS, INC.		1.15		8,031.60
0031	516(A) 6092	DRILLED SHAFTS 36" DIAMETER	100.000	LF	
	Engineer's Estimate		**420.00**		**42,000.00**
1	BECCO CONTRACTORS, INC.		350.00		35,000.00
2	BEACHNER CONSTRUCTION CO., INC.		520.00		52,000.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		450.00		45,000.00
4	C-GAWF CONSTRUCTION, INC.		450.00		45,000.00
5	K & R BUILDERS, INC.		560.00		56,000.00
0032	601(B) 1353	TYPE I-A PLAIN RIPRAP	1,027.000	TON	
	Engineer's Estimate		**30.00**		**30,810.00**
1	BECCO CONTRACTORS, INC.		30.00		30,810.00
2	BEACHNER CONSTRUCTION CO., INC.		26.00		26,702.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		30.00		30,810.00
4	C-GAWF CONSTRUCTION, INC.		30.00		30,810.00
5	K & R BUILDERS, INC.		32.00		32,864.00
0033	601(C) 1355	TYPE I-A FILTER BLANKET	226.000	TON	
	Engineer's Estimate		**25.00**		**5,650.00**
1	BECCO CONTRACTORS, INC.		28.00		6,328.00
2	BEACHNER CONSTRUCTION CO., INC.		25.00		5,650.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		24.00		5,424.00
4	C-GAWF CONSTRUCTION, INC.		30.00		6,780.00
5	K & R BUILDERS, INC.		28.00		6,328.00
0034	601(I) 6312	FILTER FABRIC (RIPRAP)	894.000	SY	
	Engineer's Estimate		**2.00**		**1,788.00**
1	BECCO CONTRACTORS, INC.		2.00		1,788.00
2	BEACHNER CONSTRUCTION CO., INC.		2.00		1,788.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		3.00		2,682.00
4	C-GAWF CONSTRUCTION, INC.		4.00		3,576.00
5	K & R BUILDERS, INC.		4.00		3,576.00

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 420 **Contract ID:** 110011

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE 'A'				
0035	613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000 LF	
	Engineer's Estimate		**20.00**	**1,200.00**
1	BECCO CONTRACTORS, INC.		20.00	1,200.00
2	BEACHNER CONSTRUCTION CO., INC.		25.00	1,500.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		25.00	1,500.00
4	C-GAWF CONSTRUCTION, INC.		8.00	480.00
5	K & R BUILDERS, INC.		35.00	2,100.00
0036	613(I) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	64.000 LF	
	Engineer's Estimate		**18.00**	**1,152.00**
1	BECCO CONTRACTORS, INC.		20.00	1,280.00
2	BEACHNER CONSTRUCTION CO., INC.		25.00	1,600.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		10.00	640.00
4	C-GAWF CONSTRUCTION, INC.		8.00	512.00
5	K & R BUILDERS, INC.		35.00	2,240.00
0037	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM	
	Engineer's Estimate		**2,500.00**	**2,500.00**
1	BECCO CONTRACTORS, INC.		5,000.00	5,000.00
2	BEACHNER CONSTRUCTION CO., INC.		2,000.00	2,000.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		15,000.00	15,000.00
4	C-GAWF CONSTRUCTION, INC.		3,500.00	3,500.00
5	K & R BUILDERS, INC.		7,500.00	7,500.00
0038	623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000 EA	
	Engineer's Estimate		**1,600.00**	**6,400.00**
1	BECCO CONTRACTORS, INC.		1,500.00	6,000.00
2	BEACHNER CONSTRUCTION CO., INC.		1,594.00	6,376.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		1,600.00	6,400.00
4	C-GAWF CONSTRUCTION, INC.		1,500.00	6,000.00
5	K & R BUILDERS, INC.		1,800.00	7,200.00
0039	623(G) 8571	GUARDRAIL END TREATMENT (GET)	4.000 EA	
	Engineer's Estimate		**2,200.00**	**8,800.00**
1	BECCO CONTRACTORS, INC.		2,400.00	9,600.00
2	BEACHNER CONSTRUCTION CO., INC.		1,909.00	7,636.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		2,500.00	10,000.00
4	C-GAWF CONSTRUCTION, INC.		2,400.00	9,600.00
5	K & R BUILDERS, INC.		2,350.00	9,400.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003 TRAFFIC				
0040	855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	4,040.000 LF	
	Engineer's Estimate		**0.55**	**2,222.00**
1	BECCO CONTRACTORS, INC.		0.95	3,838.00
2	BEACHNER CONSTRUCTION CO., INC.		0.85	3,434.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC		1.00	4,040.00
4	C-GAWF CONSTRUCTION, INC.		1.00	4,040.00
5	K & R BUILDERS, INC.		1.05	4,242.00

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 420 **Contract ID:** 110011

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 TRAFFIC			
0041	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**3,500.00**	**3,500.00**
1	BECCO CONTRACTORS, INC.	2,500.00	2,500.00
2	BEACHNER CONSTRUCTION CO., INC.	2,400.00	2,400.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	4,000.00	4,000.00
4	C-GAWF CONSTRUCTION, INC.	3,500.00	3,500.00
5	K & R BUILDERS, INC.	3,000.00	3,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004 STAKING			
0042	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	BECCO CONTRACTORS, INC.	1,000.00	1,000.00
2	BEACHNER CONSTRUCTION CO., INC.	9,750.00	9,750.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	5,500.00	5,500.00
4	C-GAWF CONSTRUCTION, INC.	5,000.00	5,000.00
5	K & R BUILDERS, INC.	7,000.00	7,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0005 CONSTRUCTION			
0043	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**5,800.00**	**5,800.00**
1	BECCO CONTRACTORS, INC.	3,000.00	3,000.00
2	BEACHNER CONSTRUCTION CO., INC.	4,000.00	4,000.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	3,000.00	3,000.00
4	C-GAWF CONSTRUCTION, INC.	2,500.00	2,500.00
5	K & R BUILDERS, INC.	3,500.00	3,500.00
0044	640(A) 1398	FIELD OFFICE	1.000 EA
	Engineer's Estimate	**4,000.00**	**4,000.00**
1	BECCO CONTRACTORS, INC.	3,000.00	3,000.00
2	BEACHNER CONSTRUCTION CO., INC.	4,000.00	4,000.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	4,000.00	4,000.00
4	C-GAWF CONSTRUCTION, INC.	5,000.00	5,000.00
5	K & R BUILDERS, INC.	5,500.00	5,500.00
0045	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**28,000.00**	**28,000.00**
1	BECCO CONTRACTORS, INC.	50,000.00	50,000.00
2	BEACHNER CONSTRUCTION CO., INC.	30,000.00	30,000.00
3	PARADIGM CONSTRUCTION & ENGINEERING, INC	28,500.00	28,500.00
4	C-GAWF CONSTRUCTION, INC.	22,500.00	22,500.00
5	K & R BUILDERS, INC.	30,000.00	30,000.00