Letting Date: February 17, 2011, 10:30 A.M.
Call Order: 410 **Contract ID:** 110117
J/P No.: 24628(04) **Project No.:** SSR-156N(143)SR **Contract Time:**
County: OKMULGEE
Description: RESURFACE (ASPHALT) I-40: FROM MILE MARKER 237 EXTEND EAST TO MILE MARKER 239.3. PROJECT LENGTH = 2.33 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	698,968.16		
1	HASKELL LEMON CONSTRUCTION CO.	719,136.76	102.89	100.00
2	APAC-CENTRAL, INC.	791,051.48	113.17	110.00
3	GLOVER & ASSOCIATES, INC.	821,620.26	117.55	114.25

Letting Date: February 17, 2011, 10:30 A.M.

Call Order: 410 **Contract ID:** 110117

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	407(A) 4659	FOG SEAL	550.000	GAL
	Engineer's Estimate		**2.40**	**1,320.00**
1	HASKELL LEMON CONSTRUCTION CO.		8.00	4,400.00
2	APAC-CENTRAL, INC.		4.03	2,216.50
3	GLOVER & ASSOCIATES, INC.		2.63	1,446.50
0002	407(C) 0300	POLYMER MODIFIED CATIONIC RAPID SET - 1	19,200.000	GAL
	Engineer's Estimate		**3.00**	**57,600.00**
1	HASKELL LEMON CONSTRUCTION CO.		2.50	48,000.00
2	APAC-CENTRAL, INC.		3.12	59,904.00
3	GLOVER & ASSOCIATES, INC.		3.00	57,600.00
0003	411(D) 5965	SUPERPAVE, TYPE S5(PG 76-28 OK)	6,450.000	TON
	Engineer's Estimate		**70.00**	**451,500.00**
1	HASKELL LEMON CONSTRUCTION CO.		84.50	545,025.00
2	APAC-CENTRAL, INC.		88.92	573,534.00
3	GLOVER & ASSOCIATES, INC.		98.00	632,100.00
0004	411(I) 6310	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	75.000	TON
	Engineer's Estimate		**200.00**	**15,000.00**
1	HASKELL LEMON CONSTRUCTION CO.		160.00	12,000.00
2	APAC-CENTRAL, INC.		188.95	14,171.25
3	GLOVER & ASSOCIATES, INC.		150.00	11,250.00
0005	412 5267	COLD MILLING PAVEMENT	76,600.000	SY
	Engineer's Estimate		**1.70**	**130,220.00**
1	HASKELL LEMON CONSTRUCTION CO.		1.00	76,600.00
2	APAC-CENTRAL, INC.		1.27	97,282.00
3	GLOVER & ASSOCIATES, INC.		1.00	76,600.00
0006	855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	49,400.000	LF
	Engineer's Estimate		**0.40**	**19,760.00**
1	HASKELL LEMON CONSTRUCTION CO.		0.44	21,736.00
2	APAC-CENTRAL, INC.		0.44	21,736.00
3	GLOVER & ASSOCIATES, INC.		0.42	20,748.00
0007	855(A) 8813	TRAFFIC STRIPE(PLASTIC)(6" WIDE)	6,152.000	LF
	Engineer's Estimate		**0.58**	**3,568.16**
1	HASKELL LEMON CONSTRUCTION CO.		0.63	3,875.76
2	APAC-CENTRAL, INC.		0.62	3,814.24
3	GLOVER & ASSOCIATES, INC.		0.63	3,875.76
0008	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
	Engineer's Estimate		**20,000.00**	**20,000.00**
1	HASKELL LEMON CONSTRUCTION CO.		7,500.00	7,500.00
2	APAC-CENTRAL, INC.		18,393.49	18,393.49
3	GLOVER & ASSOCIATES, INC.		18,000.00	18,000.00