Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 640 **Contract ID:** 110253
J/P No.: 26558(04) **Project No.:** STP-171C(132)CI **Contract Time:**
County: TILLMAN
Description: GRADE, DRAIN, AND SURFACE COUNTY ROAD (EW-180/NS-223): ON EW-180 FROM US-183, EXTEND EAST, THEN SOUTH ON NS-223. PROJECT LENGTH = 4.247 MILES

	VENDORNAME	PROPOSALITEMTO		
1	T & G CONSTRUCTION, INC.	1,499,337.30	94.01	100.00
	Engineer's Estimate	1,594,918.20		
2	APAC-CENTRAL, INC.	1,671,711.75	104.81	111.50
3	DOBSON BROTHERS CONSTRUCTION CO.	1,779,741.18	111.59	118.70

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 640 **Contract ID:** 110253

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	202(G) 0185	EARTHWORK	1.000	LSUM
	Engineer's Estimate		**20,000.00**	**20,000.00**
1	T & G CONSTRUCTION, INC.		20,000.00	20,000.00
2	APAC-CENTRAL, INC.		65,000.00	65,000.00
3	DOBSON BROTHERS CONSTRUCTION CO.		40,000.00	40,000.00
0002	223 2801	TEMPORARY SILT FENCE	1,120.000	LF
	Engineer's Estimate		**1.50**	**1,680.00**
1	T & G CONSTRUCTION, INC.		1.80	2,016.00
2	APAC-CENTRAL, INC.		2.25	2,520.00
3	DOBSON BROTHERS CONSTRUCTION CO.		2.07	2,318.40
0003	230(A) 2806	SOLID SLAB SODDING	20,000.000	SY
	Engineer's Estimate		**1.50**	**30,000.00**
1	T & G CONSTRUCTION, INC.		1.28	25,600.00
2	APAC-CENTRAL, INC.		1.25	25,000.00
3	DOBSON BROTHERS CONSTRUCTION CO.		1.04	20,800.00
0004	233(A) 2817	VEGETATIVE MULCHING	2.800	AC
	Engineer's Estimate		**400.00**	**1,120.00**
1	T & G CONSTRUCTION, INC.		300.00	840.00
2	APAC-CENTRAL, INC.		375.00	1,050.00
3	DOBSON BROTHERS CONSTRUCTION CO.		357.55	1,001.14
0005	303 5912	AGGREGATE BASE	5,303.000	TON
	Engineer's Estimate		**26.00**	**137,878.00**
1	T & G CONSTRUCTION, INC.		26.80	142,120.40
2	APAC-CENTRAL, INC.		24.00	127,272.00
3	DOBSON BROTHERS CONSTRUCTION CO.		40.00	212,120.00
0006	311(D) 0154	PROCESSING EXISTING BASE & SURFACE, METHOD D	126.180	STA
	Engineer's Estimate		**600.00**	**75,708.00**
1	T & G CONSTRUCTION, INC.		575.00	72,553.50
2	APAC-CENTRAL, INC.		250.00	31,545.00
3	DOBSON BROTHERS CONSTRUCTION CO.		475.00	59,935.50
0007	327(E) 4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	32,776.000	SY
	Engineer's Estimate		**3.00**	**98,328.00**
1	T & G CONSTRUCTION, INC.		2.40	78,662.40
2	APAC-CENTRAL, INC.		3.42	112,093.92
3	DOBSON BROTHERS CONSTRUCTION CO.		1.45	47,525.20
0008	403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	449.000	TON
	Engineer's Estimate		**28.00**	**12,572.00**
1	T & G CONSTRUCTION, INC.		25.00	11,225.00
2	APAC-CENTRAL, INC.		23.50	10,551.50
3	DOBSON BROTHERS CONSTRUCTION CO.		32.50	14,592.50
0009	407 0250	TACK COAT	3,850.000	GAL
	Engineer's Estimate		**2.50**	**9,625.00**
1	T & G CONSTRUCTION, INC.		3.00	11,550.00
2	APAC-CENTRAL, INC.		2.25	8,662.50
3	DOBSON BROTHERS CONSTRUCTION CO.		4.00	15,400.00

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 640 **Contract ID:** 110253

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001	**ROADWAY**				
0010	411(S3) 5945	(SP)ASPHALT CONCRETE TYPE S3(PG 64-22 OK)	10,228.000	TON	
	Engineer's Estimate		**65.00**		**664,820.00**
1	T & G CONSTRUCTION, INC.		61.05		624,419.40
2	APAC-CENTRAL, INC.		68.00		695,504.00
3	DOBSON BROTHERS CONSTRUCTION CO.		65.75		672,491.00
0011	411(S4) 5960	(SP)ASPHALT CONCRETE TYPE S4(PG 64-22 OK)	3,830.000	TON	
	Engineer's Estimate		**69.00**		**264,270.00**
1	T & G CONSTRUCTION, INC.		63.50		243,205.00
2	APAC-CENTRAL, INC.		72.00		275,760.00
3	DOBSON BROTHERS CONSTRUCTION CO.		67.25		257,567.50
0012	426(C) 5097	FLY ASH	1,660.000	TON	
	Engineer's Estimate		**60.00**		**99,600.00**
1	T & G CONSTRUCTION, INC.		55.00		91,300.00
2	APAC-CENTRAL, INC.		75.00		124,500.00
3	DOBSON BROTHERS CONSTRUCTION CO.		95.00		157,700.00
0013	509(B) 0321	CLASS A CONCRETE	10.000	CY	
	Engineer's Estimate		**350.00**		**3,500.00**
1	T & G CONSTRUCTION, INC.		550.00		5,500.00
2	APAC-CENTRAL, INC.		175.00		1,750.00
3	DOBSON BROTHERS CONSTRUCTION CO.		275.00		2,750.00
0014	609(B) 1514	1'-8" COMB. CURB & GUTTER (8" BARRIER)	1,650.000	LF	
	Engineer's Estimate		**22.00**		**36,300.00**
1	T & G CONSTRUCTION, INC.		18.00		29,700.00
2	APAC-CENTRAL, INC.		25.43		41,959.50
3	DOBSON BROTHERS CONSTRUCTION CO.		27.25		44,962.50
0015	613(D) 0690	24" CORR. GALV. STEEL PIPE	743.000	LF	
	Engineer's Estimate		**30.00**		**22,290.00**
1	T & G CONSTRUCTION, INC.		30.00		22,290.00
2	APAC-CENTRAL, INC.		27.82		20,670.26
3	DOBSON BROTHERS CONSTRUCTION CO.		59.75		44,394.25
0016	613(D) 0691	30" CORR. GALV. STEEL PIPE	72.000	LF	
	Engineer's Estimate		**35.00**		**2,520.00**
1	T & G CONSTRUCTION, INC.		37.00		2,664.00
2	APAC-CENTRAL, INC.		65.87		4,742.64
3	DOBSON BROTHERS CONSTRUCTION CO.		75.00		5,400.00
0017	613(D) 0692	36" CORR. GALV. STEEL PIPE	24.000	LF	
	Engineer's Estimate		**45.00**		**1,080.00**
1	T & G CONSTRUCTION, INC.		45.00		1,080.00
2	APAC-CENTRAL, INC.		59.64		1,431.36
3	DOBSON BROTHERS CONSTRUCTION CO.		89.75		2,154.00
0018	613(D) 0694	48" CORR. GALV. STEEL PIPE	50.000	LF	
	Engineer's Estimate		**55.00**		**2,750.00**
1	T & G CONSTRUCTION, INC.		71.00		3,550.00
2	APAC-CENTRAL, INC.		78.42		3,921.00
3	DOBSON BROTHERS CONSTRUCTION CO.		135.00		6,750.00

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 640 **Contract ID:** 110253

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001	**ROADWAY**				
0019	613(M) 5730	24" PREFAB. CULVERT END SECTION, ROUND	34.000	EA	
	Engineer's Estimate		**400.00**		**13,600.00**
1	T & G CONSTRUCTION, INC.		425.00		14,450.00
2	APAC-CENTRAL, INC.		118.16		4,017.44
3	DOBSON BROTHERS CONSTRUCTION CO.		215.00		7,310.00
0020	613(M) 5732	30" PREFAB. CULVERT END SECTION, ROUND	4.000	EA	
	Engineer's Estimate		**450.00**		**1,800.00**
1	T & G CONSTRUCTION, INC.		525.00		2,100.00
2	APAC-CENTRAL, INC.		258.47		1,033.88
3	DOBSON BROTHERS CONSTRUCTION CO.		415.00		1,660.00
0021	613(M) 5734	36" PREFAB. CULVERT END SECTION, ROUND	2.000	EA	
	Engineer's Estimate		**500.00**		**1,000.00**
1	T & G CONSTRUCTION, INC.		595.00		1,190.00
2	APAC-CENTRAL, INC.		332.32		664.64
3	DOBSON BROTHERS CONSTRUCTION CO.		550.00		1,100.00
0022	613(M) 5738	48" PREFAB. CULVERT END SECTION, ROUND	2.000	EA	
	Engineer's Estimate		**600.00**		**1,200.00**
1	T & G CONSTRUCTION, INC.		950.00		1,900.00
2	APAC-CENTRAL, INC.		706.85		1,413.70
3	DOBSON BROTHERS CONSTRUCTION CO.		1,100.00		2,200.00
0023	619(B) 4726	REMOVAL OF CURB AND GUTTER	1,650.000	LF	
	Engineer's Estimate		**4.50**		**7,425.00**
1	T & G CONSTRUCTION, INC.		5.00		8,250.00
2	APAC-CENTRAL, INC.		6.55		10,807.50
3	DOBSON BROTHERS CONSTRUCTION CO.		6.75		11,137.50
0024	629(E) 5048	REMOVE AND RESET MAILBOX	11.000	EA	
	Engineer's Estimate		**200.00**		**2,200.00**
1	T & G CONSTRUCTION, INC.		150.00		1,650.00
2	APAC-CENTRAL, INC.		140.69		1,547.59
3	DOBSON BROTHERS CONSTRUCTION CO.		76.62		842.82
0025	850(A) 8110	SHEET ALUMINUM SIGNS	166.680	SF	
	Engineer's Estimate		**15.00**		**2,500.20**
1	T & G CONSTRUCTION, INC.		20.00		3,333.60
2	APAC-CENTRAL, INC.		21.89		3,648.63
3	DOBSON BROTHERS CONSTRUCTION CO.		20.43		3,405.27
0026	851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	336.000	LF	
	Engineer's Estimate		**7.00**		**2,352.00**
1	T & G CONSTRUCTION, INC.		4.50		1,512.00
2	APAC-CENTRAL, INC.		4.92		1,653.12
3	DOBSON BROTHERS CONSTRUCTION CO.		4.60		1,545.60
0027	855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	12,600.000	LF	
	Engineer's Estimate		**0.50**		**6,300.00**
1	T & G CONSTRUCTION, INC.		0.76		9,576.00
2	APAC-CENTRAL, INC.		0.83		10,458.00
3	DOBSON BROTHERS CONSTRUCTION CO.		0.78		9,828.00

Letting Date: April 14, 2011, 10:30 A.M.
Call Order: 640 **Contract ID:** 110253

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0001 ROADWAY			
0028	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**10,000.00**	**10,000.00**
1	T & G CONSTRUCTION, INC.	4,600.00	4,600.00
2	APAC-CENTRAL, INC.	5,033.57	5,033.57
3	DOBSON BROTHERS CONSTRUCTION CO.	4,850.00	4,850.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002 STAKING			
0029	642 0098	STAKING	1.000 LSUM
	Engineer's Estimate	**10,000.00**	**10,000.00**
1	T & G CONSTRUCTION, INC.	42,500.00	42,500.00
2	APAC-CENTRAL, INC.	37,000.00	37,000.00
3	DOBSON BROTHERS CONSTRUCTION CO.	25,000.00	25,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 CONSTRUCTION			
0030	220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**7,500.00**	**7,500.00**
1	T & G CONSTRUCTION, INC.	10,000.00	10,000.00
2	APAC-CENTRAL, INC.	5,500.00	5,500.00
3	DOBSON BROTHERS CONSTRUCTION CO.	3,000.00	3,000.00
0031	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**45,000.00**	**45,000.00**
1	T & G CONSTRUCTION, INC.	10,000.00	10,000.00
2	APAC-CENTRAL, INC.	35,000.00	35,000.00
3	DOBSON BROTHERS CONSTRUCTION CO.	100,000.00	100,000.00