Letting Date: June 16, 2011, 10:30 A.M.
Call Order: 680 **Contract ID:** 110311
J/P No.: 28553(04) **Project No.:** SEC117-167B(189)SG **Contract Time:**
County: SEMINOLE
Description: INTERSECTION MODIFICATION US-270: FROM 4.5 MILES EAST OF THE SH-99 JUNCTION, EXTEND EAST. PROJECT LENGTH = 0.85 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	954,413.00		
1	THE CUMMINS CONSTRUCTION CO., INC.	997,641.45	104.53	100.00
2	HASKELL LEMON CONSTRUCTION CO.	1,138,411.00	119.28	114.11

Letting Date: June 16, 2011, 10:30 A.M.
Call Order: 680 **Contract ID:** 110311

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM	
	Engineer's Estimate		**12,000.00**		**12,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		10,150.00		10,150.00
2	HASKELL LEMON CONSTRUCTION CO.		25,000.00		25,000.00
0002	202(H) 0185	EARTHWORK	1.000	LSUM	
	Engineer's Estimate		**83,208.00**		**83,208.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		137,400.00		137,400.00
2	HASKELL LEMON CONSTRUCTION CO.		295,000.00		295,000.00
0003	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM	
	Engineer's Estimate		**15,950.00**		**15,950.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		5,585.00		5,585.00
2	HASKELL LEMON CONSTRUCTION CO.		30,000.00		30,000.00
0004	221(C) 2801	TEMPORARY SILT FENCE	600.000	LF	
	Engineer's Estimate		**5.00**		**3,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		10.90		6,540.00
2	HASKELL LEMON CONSTRUCTION CO.		4.00		2,400.00
0005	221(F) 0100	TEMPORARY SILT DIKE	120.000	LF	
	Engineer's Estimate		**5.00**		**600.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		11.95		1,434.00
2	HASKELL LEMON CONSTRUCTION CO.		21.00		2,520.00
0006	230(A) 2806	SOLID SLAB SODDING	2,000.000	SY	
	Engineer's Estimate		**4.00**		**8,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		2.30		4,600.00
2	HASKELL LEMON CONSTRUCTION CO.		2.00		4,000.00
0007	303(A) 2100	AGGREGATE BASE TYPE A	1,851.000	CY	
	Engineer's Estimate		**25.00**		**46,275.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		51.50		95,326.50
2	HASKELL LEMON CONSTRUCTION CO.		46.00		85,146.00
0008	307(E) 4240	CEMENTITIOUS STABILIZED SUBGRADE	7,550.000	SY	
	Engineer's Estimate		**3.50**		**26,425.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		3.45		26,047.50
2	HASKELL LEMON CONSTRUCTION CO.		3.50		26,425.00
0009	407(B) 0250	TACK COAT	2,062.000	GAL	
	Engineer's Estimate		**3.00**		**6,186.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		2.70		5,567.40
2	HASKELL LEMON CONSTRUCTION CO.		2.00		4,124.00
0010	408 5774	PRIME COAT	833.000	GAL	
	Engineer's Estimate		**4.50**		**3,748.50**
1	THE CUMMINS CONSTRUCTION CO., INC.		4.85		4,040.05
2	HASKELL LEMON CONSTRUCTION CO.		7.00		5,831.00
0011	409(A) 4242	FABRIC REINFORCEMENT	7,900.000	SY	
	Engineer's Estimate		**3.00**		**23,700.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		3.05		24,095.00
2	HASKELL LEMON CONSTRUCTION CO.		2.50		19,750.00

Letting Date: June 16, 2011, 10:30 A.M.
Call Order: 680 **Contract ID:** 110311

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0012	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	3,732.000	TON	
	Engineer's Estimate		**68.00**		**253,776.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		65.10		242,953.20
2	HASKELL LEMON CONSTRUCTION CO.		68.00		253,776.00
0013	411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	2,872.000	TON	
	Engineer's Estimate		**74.00**		**212,528.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		80.05		229,903.60
2	HASKELL LEMON CONSTRUCTION CO.		85.00		244,120.00
0014	412 5267	COLD MILLING PAVEMENT	538.000	SY	
	Engineer's Estimate		**11.25**		**6,052.50**
1	THE CUMMINS CONSTRUCTION CO., INC.		12.75		6,859.50
2	HASKELL LEMON CONSTRUCTION CO.		12.00		6,456.00
0015	426(C) 5097	FLY ASH	468.000	TON	
	Engineer's Estimate		**50.00**		**23,400.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		60.50		28,314.00
2	HASKELL LEMON CONSTRUCTION CO.		60.00		28,080.00
0016	613(C) 5206	21" X 15" PRECOATED CORR. STL. PIPE ARCH	184.000	LF	
	Engineer's Estimate		**29.00**		**5,336.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		28.65		5,271.60
2	HASKELL LEMON CONSTRUCTION CO.		37.00		6,808.00
0017	613(L) 4504	21" X 15" PREFAB. CULVERT END SECTION, ARCH	6.000	EA	
	Engineer's Estimate		**413.00**		**2,478.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		210.00		1,260.00
2	HASKELL LEMON CONSTRUCTION CO.		400.00		2,400.00
0018	619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	4,400.000	SY	
	Engineer's Estimate		**5.50**		**24,200.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		4.70		20,680.00
2	HASKELL LEMON CONSTRUCTION CO.		4.00		17,600.00
0019	641 1552	MOBILIZATION	1.000	LSUM	
	Engineer's Estimate		**85,000.00**		**85,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		70,035.00		70,035.00
2	HASKELL LEMON CONSTRUCTION CO.		15,000.00		15,000.00
0020	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000	LSUM	
	Engineer's Estimate		**20,000.00**		**20,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		4,400.00		4,400.00
2	HASKELL LEMON CONSTRUCTION CO.		5,000.00		5,000.00
0021	855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	7,875.000	LF	
	Engineer's Estimate		**0.40**		**3,150.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		0.62		4,882.50
2	HASKELL LEMON CONSTRUCTION CO.		1.00		7,875.00
0022	855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	4.000	EA	
	Engineer's Estimate		**150.00**		**600.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		76.15		304.60
2	HASKELL LEMON CONSTRUCTION CO.		200.00		800.00

Letting Date: June 16, 2011, 10:30 A.M.
Call Order: 680 **Contract ID:** 110311

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0023	877(A) 8483	PORTABLE LONGITUDINAL BARRIER	1,500.000	LF	
	Engineer's Estimate		**25.00**		**37,500.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		37.50		56,250.00
2	HASKELL LEMON CONSTRUCTION CO.		25.00		37,500.00
0024	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM	
	Engineer's Estimate		**45,000.00**		**45,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		765.00		765.00
2	HASKELL LEMON CONSTRUCTION CO.		10,000.00		10,000.00
0025	882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	140.000	SD	
	Engineer's Estimate		**45.00**		**6,300.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		35.55		4,977.00
2	HASKELL LEMON CONSTRUCTION CO.		20.00		2,800.00