Letting Date: February 16, 2012, 10:30 A.M.
Call Order: 040 **Contract ID:** 120080
J/P No.: 27576(04) **Project No.:** STPY-104B(073)3P **Contract Time:**
County: BEAVER
Description: RESURFACE (ASPHALT) US-64: FROM 5.0 MILES EAST OF US-83, EXTEND EAST. PROJECT LENGTH = 7.00 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	1,280,124.50		
1	J & R SAND COMPANY, INC.	1,363,940.80	106.55	100.00
2	DOBSON BROTHERS CONSTRUCTION CO.	1,455,656.13	113.71	106.72
3	HIGHWAY CONTRACTORS, INC.	1,457,377.05	113.85	106.85

Letting Date: February 16, 2012, 10:30 A.M.
Call Order: 040 **Contract ID:** 120080

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0001	202(D) 0184	UNCLASSIFIED BORROW	1,200.000	CY
	Engineer's Estimate		**5.00**	**6,000.00**
1	J & R SAND COMPANY, INC.		6.00	7,200.00
2	DOBSON BROTHERS CONSTRUCTION CO.		7.80	9,360.00
3	HIGHWAY CONTRACTORS, INC.		8.00	9,600.00
0002	202(H) 0185	EARTHWORK	1.000	LSUM
	Engineer's Estimate		**20,000.00**	**20,000.00**
1	J & R SAND COMPANY, INC.		20,000.00	20,000.00
2	DOBSON BROTHERS CONSTRUCTION CO.		15,291.71	15,291.71
3	HIGHWAY CONTRACTORS, INC.		25,000.00	25,000.00
0003	230(A) 2806	SOLID SLAB SODDING	28,750.000	SY
	Engineer's Estimate		**2.25**	**64,687.50**
1	J & R SAND COMPANY, INC.		2.00	57,500.00
2	DOBSON BROTHERS CONSTRUCTION CO.		2.37	68,137.50
3	HIGHWAY CONTRACTORS, INC.		2.00	57,500.00
0004	407(B) 0250	TACK COAT	7,060.000	GAL
	Engineer's Estimate		**2.25**	**15,885.00**
1	J & R SAND COMPANY, INC.		2.00	14,120.00
2	DOBSON BROTHERS CONSTRUCTION CO.		3.00	21,180.00
3	HIGHWAY CONTRACTORS, INC.		3.65	25,769.00
0005	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	13,200.000	TON
	Engineer's Estimate		**75.00**	**990,000.00**
1	J & R SAND COMPANY, INC.		86.00	1,135,200.00
2	DOBSON BROTHERS CONSTRUCTION CO.		89.50	1,181,400.00
3	HIGHWAY CONTRACTORS, INC.		89.79	1,185,228.00
0006	411(I) 6310	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	500.000	TON
	Engineer's Estimate		**100.00**	**50,000.00**
1	J & R SAND COMPANY, INC.		115.00	57,500.00
2	DOBSON BROTHERS CONSTRUCTION CO.		100.00	50,000.00
3	HIGHWAY CONTRACTORS, INC.		120.00	60,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 TRAFFIC				
0007	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	129,360.000	LF
	Engineer's Estimate		**0.70**	**90,552.00**
1	J & R SAND COMPANY, INC.		0.28	36,220.80
2	DOBSON BROTHERS CONSTRUCTION CO.		0.58	75,028.80
3	HIGHWAY CONTRACTORS, INC.		0.34	43,982.40
0008	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
	Engineer's Estimate		**8,000.00**	**8,000.00**
1	J & R SAND COMPANY, INC.		9,000.00	9,000.00
2	DOBSON BROTHERS CONSTRUCTION CO.		15,258.12	15,258.12
3	HIGHWAY CONTRACTORS, INC.		6,500.00	6,500.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount

Letting Date: February 16, 2012, 10:30 A.M.

Call Order: 040 **Contract ID:** 120080

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0003**	**CONSTRUCTION**	
0009	641 1552	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**35,000.00**	**35,000.00**
1	J & R SAND COMPANY, INC.	27,200.00	27,200.00
2	DOBSON BROTHERS CONSTRUCTION CO.	20,000.00	20,000.00
3	HIGHWAY CONTRACTORS, INC.	43,797.65	43,797.65