Letting Date: February 16, 2012, 10:30 A.M.
Call Order: 720 **Contract ID:** 120113
J/P No.: 27577(04) **Project No.:** NHY-017N(237)3P **Contract Time:**
County: WOODWARD
Description: RESURFACE (UTWBC) US-183: FROM 8.3 MILES NORTH OF SH-15, EXTEND NORTH. PROJECT LENGTH = 5.40 MILES

	VENDORNAME	PROPOSALITEMTO		
1	THE CUMMINS CONSTRUCTION CO., INC.	890,525.22	85.95	100.00
2	J & R SAND COMPANY, INC.	1,013,243.60	97.79	113.78

Letting Date: February 16, 2012, 10:30 A.M.
Call Order: 720 **Contract ID:** 120113

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	404(G) 4845	ULTRA-THIN BONDED WEARING COURSE, TYPE C	5,917.000	TON	
	Engineer's Estimate		**135.25**		**800,274.25**
1	THE CUMMINS CONSTRUCTION CO., INC.		121.90		721,282.30
2	J & R SAND COMPANY, INC.		137.00		810,629.00
0002	407(A) 4659	FOG SEAL	1,990.000	GAL	
	Engineer's Estimate		**5.00**		**9,950.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		4.25		8,457.50
2	J & R SAND COMPANY, INC.		5.50		10,945.00
0003	407(B) 0250	TACK COAT	322.000	GAL	
	Engineer's Estimate		**3.50**		**1,127.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		4.20		1,352.40
2	J & R SAND COMPANY, INC.		2.00		644.00
0004	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	450.000	TON	
	Engineer's Estimate		**110.00**		**49,500.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		94.00		42,300.00
2	J & R SAND COMPANY, INC.		112.00		50,400.00
0005	412 5267	COLD MILLING PAVEMENT	934.000	SY	
	Engineer's Estimate		**3.75**		**3,502.50**
1	THE CUMMINS CONSTRUCTION CO., INC.		7.55		7,051.70
2	J & R SAND COMPANY, INC.		3.50		3,269.00
0006	413(A) 4861	RUMBLE STRIP-METHOD HMA-CON	7,000.000	LF	
	Engineer's Estimate		**0.25**		**1,750.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		0.40		2,800.00
2	J & R SAND COMPANY, INC.		0.20		1,400.00
0007	619(B) 4780	REMOVAL OF GUARDRAIL	600.000	LF	
	Engineer's Estimate		**2.50**		**1,500.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		1.30		780.00
2	J & R SAND COMPANY, INC.		2.00		1,200.00
0008	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	250.000	LF	
	Engineer's Estimate		**18.00**		**4,500.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		16.50		4,125.00
2	J & R SAND COMPANY, INC.		17.50		4,375.00
0009	623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA	
	Engineer's Estimate		**1,600.00**		**6,400.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		1,597.00		6,388.00
2	J & R SAND COMPANY, INC.		1,235.00		4,940.00
0010	623(G) 8571	GUARDRAIL END TREATMENT (GET)	4.000	EA	
	Engineer's Estimate		**2,300.00**		**9,200.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		2,214.50		8,858.00
2	J & R SAND COMPANY, INC.		2,100.00		8,400.00

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 TRAFFIC					

Letting Date: February 16, 2012, 10:30 A.M.
Call Order: 720 **Contract ID:** 120113

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 TRAFFIC					
0011	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	117,674.000	LF	
	Engineer's Estimate		**0.70**		**82,371.80**
1	THE CUMMINS CONSTRUCTION CO., INC.		0.28		32,948.72
2	J & R SAND COMPANY, INC.		0.40		47,069.60
0012	856(A) 8540	TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	3,368.000	LF	
	Engineer's Estimate		**1.60**		**5,388.80**
1	THE CUMMINS CONSTRUCTION CO., INC.		1.75		5,894.00
2	J & R SAND COMPANY, INC.		1.50		5,052.00
0013	856(A) 8555	TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	14.000	LF	
	Engineer's Estimate		**11.00**		**154.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		10.30		144.20
2	J & R SAND COMPANY, INC.		10.00		140.00
0014	856(B) 8860	TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	12.000	EA	
	Engineer's Estimate		**100.00**		**1,200.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		154.50		1,854.00
2	J & R SAND COMPANY, INC.		125.00		1,500.00
0015	876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	20.000	SD	
	Engineer's Estimate		**40.00**		**800.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		8.25		165.00
2	J & R SAND COMPANY, INC.		10.00		200.00
0016	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM	
	Engineer's Estimate		**8,500.00**		**8,500.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		7,086.40		7,086.40
2	J & R SAND COMPANY, INC.		3,080.00		3,080.00

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0003 CONSTRUCTION					
0017	641 1552	MOBILIZATION	1.000	LSUM	
	Engineer's Estimate		**50,000.00**		**50,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		39,038.00		39,038.00
2	J & R SAND COMPANY, INC.		60,000.00		60,000.00