Letting Date: June 21, 2012, 10:30 A.M.
Call Order: 540 **Contract ID:** 120219
J/P No.: 21913(04) **Project No.:** HSIPY-157C(061) **Contract Time:**
County: OSAGE
Description: BRIDGE AND APPROACHES SH-18: OVER LOST MAN CREEK, 2.0 MILES NORTH OF SH-60.
PROJECT LENGTH = 0.037 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	763,681.25		
1	APAC-CENTRAL, INC.	813,914.87	106.58	100.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	916,063.10	119.95	112.55

Letting Date: June 21, 2012, 10:30 A.M.
Call Order: 540 **Contract ID:** 120219

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM	
	Engineer's Estimate		**8,000.00**		**8,000.00**
1	APAC-CENTRAL, INC.		6,096.83		6,096.83
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		25,000.00		25,000.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	2,844.000	CY	
	Engineer's Estimate		**8.00**		**22,752.00**
1	APAC-CENTRAL, INC.		8.49		24,145.56
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		6.50		18,486.00
0003	202(D) 0184	UNCLASSIFIED BORROW	3,355.000	CY	
	Engineer's Estimate		**12.00**		**40,260.00**
1	APAC-CENTRAL, INC.		15.60		52,338.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		12.50		41,937.50
0004	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM	
	Engineer's Estimate		**8,000.00**		**8,000.00**
1	APAC-CENTRAL, INC.		14,304.84		14,304.84
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		12,000.00		12,000.00
0005	221(C) 2801	TEMPORARY SILT FENCE	2,485.000	LF	
	Engineer's Estimate		**3.00**		**7,455.00**
1	APAC-CENTRAL, INC.		2.44		6,063.40
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		3.00		7,455.00
0006	221(D) 2803	TEMPORARY SEDIMENT FILTER	1.000	EA	
	Engineer's Estimate		**300.00**		**300.00**
1	APAC-CENTRAL, INC.		434.62		434.62
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		500.00		500.00
0007	221(F) 0100	TEMPORARY SILT DIKE	168.000	LF	
	Engineer's Estimate		**10.50**		**1,764.00**
1	APAC-CENTRAL, INC.		8.64		1,451.52
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		8.50		1,428.00
0008	221(G) 0152	TEMPORARY ROCK FILTER DAM TYPE 3	160.000	CY	
	Engineer's Estimate		**100.00**		**16,000.00**
1	APAC-CENTRAL, INC.		91.81		14,689.60
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		125.00		20,000.00
0009	229 4318	DITCH LINER PROTECTION	300.000	LF	
	Engineer's Estimate		**2.00**		**600.00**
1	APAC-CENTRAL, INC.		2.17		651.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		2.50		750.00
0010	230(A) 2806	SOLID SLAB SODDING	8,196.000	SY	
	Engineer's Estimate		**1.75**		**14,343.00**
1	APAC-CENTRAL, INC.		2.12		17,375.52
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		2.00		16,392.00
0011	232(A) 2813	SEEDING METHOD A	1.000	AC	
	Engineer's Estimate		**300.00**		**300.00**
1	APAC-CENTRAL, INC.		869.22		869.22
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		865.00		865.00

Letting Date: June 21, 2012, 10:30 A.M.
Call Order: 540 **Contract ID:** 120219

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0012	233(A) 2817	VEGETATIVE MULCHING	1.000	AC	
	Engineer's Estimate		**300.00**		**300.00**
1	APAC-CENTRAL, INC.		869.22		869.22
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		865.00		865.00
0013	303(B) 2110	AGGREGATE BASE TYPE B	329.000	CY	
	Engineer's Estimate		**50.00**		**16,450.00**
1	APAC-CENTRAL, INC.		47.23		15,538.67
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		50.00		16,450.00
0014	307(D) 4230	LIME	88.000	TON	
	Engineer's Estimate		**175.00**		**15,400.00**
1	APAC-CENTRAL, INC.		181.52		15,973.76
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		165.00		14,520.00
0015	307(H) 4270	LIME STABILIZED SUBGRADE	4,910.000	SY	
	Engineer's Estimate		**4.00**		**19,640.00**
1	APAC-CENTRAL, INC.		3.39		16,644.90
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		4.00		19,640.00
0016	325 5271	SEPARATOR FABRIC	2,108.000	SY	
	Engineer's Estimate		**2.00**		**4,216.00**
1	APAC-CENTRAL, INC.		1.42		2,993.36
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		3.50		7,378.00
0017	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	150.000	TON	
	Engineer's Estimate		**40.00**		**6,000.00**
1	APAC-CENTRAL, INC.		26.36		3,954.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		30.00		4,500.00
0018	407(B) 0250	TACK COAT	310.000	GAL	
	Engineer's Estimate		**4.00**		**1,240.00**
1	APAC-CENTRAL, INC.		2.53		784.30
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		2.75		852.50
0019	408 5774	PRIME COAT	1,382.000	GAL	
	Engineer's Estimate		**7.00**		**9,674.00**
1	APAC-CENTRAL, INC.		7.83		10,821.06
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		8.50		11,747.00
0020	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	693.000	TON	
	Engineer's Estimate		**80.00**		**55,440.00**
1	APAC-CENTRAL, INC.		89.36		61,926.48
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		99.00		68,607.00
0021	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	462.000	TON	
	Engineer's Estimate		**95.00**		**43,890.00**
1	APAC-CENTRAL, INC.		112.56		52,002.72
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		125.00		57,750.00
0022	509(D) 0325	CLASS C CONCRETE	28.000	CY	
	Engineer's Estimate		**350.00**		**9,800.00**
1	APAC-CENTRAL, INC.		543.26		15,211.28
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		350.00		9,800.00

Letting Date: June 21, 2012, 10:30 A.M.
Call Order: 540 **Contract ID:** 120219

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0023	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000 LSUM	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	APAC-CENTRAL, INC.		3,401.54	3,401.54
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		17,000.00	17,000.00
0024	619(B) 4725	REMOVAL OF FENCE	3,045.000 LF	
	Engineer's Estimate		**1.50**	**4,567.50**
1	APAC-CENTRAL, INC.		2.17	6,607.65
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		2.50	7,612.50
0025	619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	3,462.000 SY	
	Engineer's Estimate		**3.25**	**11,251.50**
1	APAC-CENTRAL, INC.		3.18	11,009.16
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		7.50	25,965.00
0026	619(B) 4780	REMOVAL OF GUARDRAIL	162.000 LF	
	Engineer's Estimate		**5.00**	**810.00**
1	APAC-CENTRAL, INC.		2.88	466.56
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		4.00	648.00
0027	619(C) 0924	SAWING PAVEMENT	1,000.000 LF	
	Engineer's Estimate		**3.00**	**3,000.00**
1	APAC-CENTRAL, INC.		2.34	2,340.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		3.00	3,000.00
0028	624(C) 4459	FENCE-STYLE SWF (5 BARBED WIRE)	3,200.000 LF	
	Engineer's Estimate		**4.00**	**12,800.00**
1	APAC-CENTRAL, INC.		6.46	20,672.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		6.00	19,200.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE 'A'				
0029	202(A) 1301	UNCLASSIFIED EXCAVATION	2,175.000 CY	
	Engineer's Estimate		**8.00**	**17,400.00**
1	APAC-CENTRAL, INC.		7.94	17,269.50
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		6.50	14,137.50
0030	501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	135.000 CY	
	Engineer's Estimate		**30.00**	**4,050.00**
1	APAC-CENTRAL, INC.		32.60	4,401.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		40.00	5,400.00
0031	509(A) 1326	CLASS AA CONCRETE	519.900 CY	
	Engineer's Estimate		**350.00**	**181,965.00**
1	APAC-CENTRAL, INC.		455.94	237,043.21
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		450.00	233,955.00
0032	511(A) 1332	REINFORCING STEEL	97,088.000 LB	
	Engineer's Estimate		**1.00**	**97,088.00**
1	APAC-CENTRAL, INC.		0.71	68,932.48
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		0.90	87,379.20

Letting Date: June 21, 2012, 10:30 A.M.
Call Order: 540 **Contract ID:** 120219

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002 BRIDGE 'A'			
0033	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	APAC-CENTRAL, INC.	10,596.91	10,596.91
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	15,000.00	15,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 TRAFFIC			
0034	805(D) 8756	(PL)REMOVE & RESET EXISTING SIGNS	2.000 EA
	Engineer's Estimate	**100.00**	**200.00**
1	APAC-CENTRAL, INC.	108.65	217.30
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	110.00	220.00
0035	853 9030	DELINEATORS(TYPE 1, CODE 3)	4.000 EA
	Engineer's Estimate	**15.00**	**60.00**
1	APAC-CENTRAL, INC.	15.21	60.84
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	21.00	84.00
0036	854(A) 8800	TRAFFIC STRIPE(PAINT)(4" WIDE)	2,715.000 LF
	Engineer's Estimate	**0.35**	**950.25**
1	APAC-CENTRAL, INC.	0.27	733.05
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	0.30	814.50
0037	857(A) 8839	CONSTRUCTION TRAFFIC STRIPE(PAINT)(4" WIDE)	6,400.000 LF
	Engineer's Estimate	**0.25**	**1,600.00**
1	APAC-CENTRAL, INC.	0.16	1,024.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	0.18	1,152.00
0038	857(F) 8006	PAVEMENT MARKING REMOVAL(TRAFFIC STRIPE)	4,000.000 LF
	Engineer's Estimate	**0.30**	**1,200.00**
1	APAC-CENTRAL, INC.	0.27	1,080.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	0.30	1,200.00
0039	871(B) 8705	(SP)CONST.ZONE IMPACT ATTEN.	160.000 SD
	Engineer's Estimate	**30.00**	**4,800.00**
1	APAC-CENTRAL, INC.	10.87	1,739.20
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	12.00	1,920.00
0040	877(B) 8484	DELIVER PORTABLE LONGITUDINAL BARRIER	800.000 LF
	Engineer's Estimate	**25.00**	**20,000.00**
1	APAC-CENTRAL, INC.	23.36	18,688.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	35.00	28,000.00
0041	880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	900.000 SD
	Engineer's Estimate	**0.60**	**540.00**
1	APAC-CENTRAL, INC.	1.09	981.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	1.10	990.00
0042	880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	540.000 SD
	Engineer's Estimate	**0.80**	**432.00**
1	APAC-CENTRAL, INC.	4.35	2,349.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC	4.40	2,376.00

Letting Date: June 21, 2012, 10:30 A.M.
Call Order: 540 **Contract ID:** 120219

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003 TRAFFIC				
0043	880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,040.000 SD	
	Engineer's Estimate		**1.00**	**1,040.00**
1	APAC-CENTRAL, INC.		3.26	3,390.40
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		3.30	3,432.00
0044	880(C) 8842	CONSTRUCTION BARRICADES(TYPE III)	80.000 SD	
	Engineer's Estimate		**2.00**	**160.00**
1	APAC-CENTRAL, INC.		4.35	348.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		4.40	352.00
0045	880(E) 8860	WARNING LIGHTS(TYPE A)	880.000 SD	
	Engineer's Estimate		**0.50**	**440.00**
1	APAC-CENTRAL, INC.		0.11	96.80
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		0.11	96.80
0046	880(F) 8878	DRUMS	6,260.000 SD	
	Engineer's Estimate		**0.30**	**1,878.00**
1	APAC-CENTRAL, INC.		0.05	313.00
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		0.06	375.60

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0004 STAKING				
0047	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM	
	Engineer's Estimate		**6,500.00**	**6,500.00**
1	APAC-CENTRAL, INC.		10,539.33	10,539.33
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		9,500.00	9,500.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0005 CONSTRUCTION				
0048	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM	
	Engineer's Estimate		**3,125.00**	**3,125.00**
1	APAC-CENTRAL, INC.		710.59	710.59
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		2,900.00	2,900.00
0049	640(A) 1426	FIELD OFFICE	1.000 EA	
	Engineer's Estimate		**6,000.00**	**6,000.00**
1	APAC-CENTRAL, INC.		3,552.95	3,552.95
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		6,430.00	6,430.00
0050	641 1552	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**70,000.00**	**70,000.00**
1	APAC-CENTRAL, INC.		50,211.54	50,211.54
2	MANHATTAN ROAD & BRIDGE COMPANY, LLC		70,000.00	70,000.00