Letting Date: February 21, 2013, 10:30 A.M.
Call Order: 860 **Contract ID:** 130117
J/P No.: 27578(04) **Project No.:** STPY-176C(180)3P **Contract Time:**
County: WOODS
Description: RESURFACE (ASPHALT) SH-14: BEGIN 7.5 MILES NORTH OF US-281 IN WAYNOKA, EXTEND NORTH. PROJECT LENGTH = 7.10 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	1,319,290.00		
1	Venture Corporation dba VCO Paving	1,411,530.00	106.99	100.00
2	THE CUMMINS CONSTRUCTION CO., INC.	1,478,755.00	112.09	104.76

Letting Date: February 21, 2013, 10:30 A.M.
Call Order: 860 **Contract ID:** 130117

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	202(D) 0184	UNCLASSIFIED BORROW	1,500.000 CY	
	Engineer's Estimate		**5.00**	**7,500.00**
1	Venture Corporation dba VCO Paving		1.00	1,500.00
2	THE CUMMINS CONSTRUCTION CO., INC.		23.60	35,400.00
0002	202(H) 0185	EARTHWORK	1.000 LSUM	
	Engineer's Estimate		**20,000.00**	**20,000.00**
1	Venture Corporation dba VCO Paving		20,000.00	20,000.00
2	THE CUMMINS CONSTRUCTION CO., INC.		13,850.00	13,850.00
0003	230(A) 2806	SOLID SLAB SODDING	31,000.000 SY	
	Engineer's Estimate		**2.00**	**62,000.00**
1	Venture Corporation dba VCO Paving		2.00	62,000.00
2	THE CUMMINS CONSTRUCTION CO., INC.		1.45	44,950.00
0004	407(B) 0250	TACK COAT	6,200.000 GAL	
	Engineer's Estimate		**2.70**	**16,740.00**
1	Venture Corporation dba VCO Paving		2.00	12,400.00
2	THE CUMMINS CONSTRUCTION CO., INC.		4.10	25,420.00
0005	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	11,500.000 TON	
	Engineer's Estimate		**80.00**	**920,000.00**
1	Venture Corporation dba VCO Paving		85.00	977,500.00
2	THE CUMMINS CONSTRUCTION CO., INC.		94.70	1,089,050.00
0006	411(I) 6310	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	500.000 TON	
	Engineer's Estimate		**125.00**	**62,500.00**
1	Venture Corporation dba VCO Paving		170.00	85,000.00
2	THE CUMMINS CONSTRUCTION CO., INC.		129.25	64,625.00
0007	412 5267	COLD MILLING PAVEMENT	3,200.000 SY	
	Engineer's Estimate		**6.00**	**19,200.00**
1	Venture Corporation dba VCO Paving		10.00	32,000.00
2	THE CUMMINS CONSTRUCTION CO., INC.		7.05	22,560.00
0008	619(B) 4780	REMOVAL OF GUARDRAIL	400.000 LF	
	Engineer's Estimate		**12.50**	**5,000.00**
1	Venture Corporation dba VCO Paving		25.00	10,000.00
2	THE CUMMINS CONSTRUCTION CO., INC.		25.00	10,000.00
0009	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	1,650.000 LF	
	Engineer's Estimate		**25.00**	**41,250.00**
1	Venture Corporation dba VCO Paving		30.00	49,500.00
2	THE CUMMINS CONSTRUCTION CO., INC.		30.00	49,500.00
0010	623(G) 8571	GUARDRAIL END TREATMENT (GET)	16.000 EA	
	Engineer's Estimate		**2,200.00**	**35,200.00**
1	Venture Corporation dba VCO Paving		2,250.00	36,000.00
2	THE CUMMINS CONSTRUCTION CO., INC.		2,250.00	36,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**TRAFFIC**			

Letting Date: February 21, 2013, 10:30 A.M.

Call Order: 860 **Contract ID:** 130117

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**TRAFFIC**		
0011	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	117,000.000	LF
	Engineer's Estimate		**0.70**	**81,900.00**
1	Venture Corporation dba VCO Paving		0.39	45,630.00
2	THE CUMMINS CONSTRUCTION CO., INC.		0.43	50,310.00
0012	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
	Engineer's Estimate		**8,000.00**	**8,000.00**
1	Venture Corporation dba VCO Paving		30,000.00	30,000.00
2	THE CUMMINS CONSTRUCTION CO., INC.		3,690.00	3,690.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0003**	**CONSTRUCTION**		
0013	641 1552	MOBILIZATION	1.000	LSUM
	Engineer's Estimate		**40,000.00**	**40,000.00**
1	Venture Corporation dba VCO Paving		50,000.00	50,000.00
2	THE CUMMINS CONSTRUCTION CO., INC.		33,400.00	33,400.00