Letting Date: October 17, 2013, 10:30 A.M.
Call Order: 060 **Contract ID:** 130357
J/P No.: 22488(04) **Project No.:** STP-107D(098)CI **Contract Time:**
County: BRYAN
Description: BRIDGE AND APPROACHES COUNTY ROAD (NS-382.5): OVER ISLAND BAYOU CREEK 3.2 MILES NORTH OF THE TOWN OF YUBA. PROJECT LENGTH = 0.236 MILE

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	522,208.98		
1	HUB Construction, Inc.	549,043.55	105.14	100.00
2	K & R BUILDERS, INC.	592,428.28	113.45	107.90
3	L & N BRIDGE, LLC	615,396.81	117.84	112.09
4	EARTH BUILDERS, L.P.	721,427.45	138.15	131.40

Letting Date: October 17, 2013, 10:30 A.M.
Call Order: 060 **Contract ID:** 130357

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	201(A) 0102	CLEARING AND GRUBBING	1.000 LSUM	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	HUB Construction, Inc.		9,000.00	9,000.00
2	K & R BUILDERS, INC.		14,170.00	14,170.00
3	L & N BRIDGE, LLC		10,000.00	10,000.00
4	EARTH BUILDERS, L.P.		10,000.00	10,000.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	4,530.000 CY	
	Engineer's Estimate		**4.00**	**18,120.00**
1	HUB Construction, Inc.		6.00	27,180.00
2	K & R BUILDERS, INC.		7.50	33,975.00
3	L & N BRIDGE, LLC		4.25	19,252.50
4	EARTH BUILDERS, L.P.		10.00	45,300.00
0003	202(D) 0184	UNCLASSIFIED BORROW	5,240.000 CY	
	Engineer's Estimate		**5.00**	**26,200.00**
1	HUB Construction, Inc.		7.00	36,680.00
2	K & R BUILDERS, INC.		9.65	50,566.00
3	L & N BRIDGE, LLC		12.25	64,190.00
4	EARTH BUILDERS, L.P.		10.00	52,400.00
0004	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000 LSUM	
	Engineer's Estimate		**12,227.78**	**12,227.78**
1	HUB Construction, Inc.		3,500.00	3,500.00
2	K & R BUILDERS, INC.		8,000.00	8,000.00
3	L & N BRIDGE, LLC		10,000.00	10,000.00
4	EARTH BUILDERS, L.P.		5,000.00	5,000.00
0005	221(C) 2801	TEMPORARY SILT FENCE	2,293.000 LF	
	Engineer's Estimate		**3.00**	**6,879.00**
1	HUB Construction, Inc.		3.00	6,879.00
2	K & R BUILDERS, INC.		1.60	3,668.80
3	L & N BRIDGE, LLC		1.39	3,187.27
4	EARTH BUILDERS, L.P.		1.50	3,439.50
0006	221(F) 0100	TEMPORARY SILT DIKE	182.000 LF	
	Engineer's Estimate		**8.00**	**1,456.00**
1	HUB Construction, Inc.		6.00	1,092.00
2	K & R BUILDERS, INC.		10.00	1,820.00
3	L & N BRIDGE, LLC		8.66	1,576.12
4	EARTH BUILDERS, L.P.		10.00	1,820.00
0007	230(A) 2806	SOLID SLAB SODDING	17,608.000 SY	
	Engineer's Estimate		**1.00**	**17,608.00**
1	HUB Construction, Inc.		2.00	35,216.00
2	K & R BUILDERS, INC.		1.72	30,285.76
3	L & N BRIDGE, LLC		1.54	27,116.32
4	EARTH BUILDERS, L.P.		2.00	35,216.00
0008	233(A) 2817	VEGETATIVE MULCHING	3.640 AC	
	Engineer's Estimate		**500.00**	**1,820.00**
1	HUB Construction, Inc.		350.00	1,274.00
2	K & R BUILDERS, INC.		537.50	1,956.50
3	L & N BRIDGE, LLC		644.00	2,344.16
4	EARTH BUILDERS, L.P.		1,000.00	3,640.00

Letting Date: October 17, 2013, 10:30 A.M.
Call Order: 060 **Contract ID:** 130357

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0001	**ROADWAY**		
0009	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1,062.000 TON
	Engineer's Estimate	**30.00**	**31,860.00**
1	HUB Construction, Inc.	28.00	29,736.00
2	K & R BUILDERS, INC.	26.57	28,217.34
3	L & N BRIDGE, LLC	25.00	26,550.00
4	EARTH BUILDERS, L.P.	30.00	31,860.00
0010	509(D) 0325	CLASS C CONCRETE	10.000 CY
	Engineer's Estimate	**250.00**	**2,500.00**
1	HUB Construction, Inc.	300.00	3,000.00
2	K & R BUILDERS, INC.	275.00	2,750.00
3	L & N BRIDGE, LLC	275.00	2,750.00
4	EARTH BUILDERS, L.P.	300.00	3,000.00
0011	613(B) 4530	42" X 29" CORR. GALV. STEEL PIPE ARCH	54.000 LF
	Engineer's Estimate	**50.00**	**2,700.00**
1	HUB Construction, Inc.	50.00	2,700.00
2	K & R BUILDERS, INC.	47.00	2,538.00
3	L & N BRIDGE, LLC	50.00	2,700.00
4	EARTH BUILDERS, L.P.	75.00	4,050.00
0012	613(P) 4573	42" X 29" GALV. STEEL CULVERT END SECTION ARCH	2.000 EA
	Engineer's Estimate	**500.00**	**1,000.00**
1	HUB Construction, Inc.	500.00	1,000.00
2	K & R BUILDERS, INC.	532.00	1,064.00
3	L & N BRIDGE, LLC	500.00	1,000.00
4	EARTH BUILDERS, L.P.	600.00	1,200.00
0013	624(C) 4459	FENCE-STYLE SWF (5 BARBED WIRE)	1,059.000 LF
	Engineer's Estimate	**4.00**	**4,236.00**
1	HUB Construction, Inc.	5.00	5,295.00
2	K & R BUILDERS, INC.	4.70	4,977.30
3	L & N BRIDGE, LLC	5.00	5,295.00
4	EARTH BUILDERS, L.P.	9.00	9,531.00
0014	624(D) 4470	GATE, GALVANIZED STEEL	1.000 EA
	Engineer's Estimate	**500.00**	**500.00**
1	HUB Construction, Inc.	150.00	150.00
2	K & R BUILDERS, INC.	896.00	896.00
3	L & N BRIDGE, LLC	700.00	700.00
4	EARTH BUILDERS, L.P.	2,500.00	2,500.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A'**		
0015	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	84.000 CY
	Engineer's Estimate	**25.00**	**2,100.00**
1	HUB Construction, Inc.	12.00	1,008.00
2	K & R BUILDERS, INC.	10.50	882.00
3	L & N BRIDGE, LLC	35.00	2,940.00
4	EARTH BUILDERS, L.P.	20.00	1,680.00

Letting Date: October 17, 2013, 10:30 A.M.
Call Order: 060 **Contract ID:** 130357

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A'					
0016	501(G) 6309	CLSM BACKFILL	82.000	CY	
	Engineer's Estimate		**100.00**		**8,200.00**
1	HUB Construction, Inc.		140.00		11,480.00
2	K & R BUILDERS, INC.		170.00		13,940.00
3	L & N BRIDGE, LLC		175.00		14,350.00
4	EARTH BUILDERS, L.P.		150.00		12,300.00
0017	503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	416.670	LF	
	Engineer's Estimate		**200.00**		**83,334.00**
1	HUB Construction, Inc.		205.00		85,417.35
2	K & R BUILDERS, INC.		186.75		77,813.12
3	L & N BRIDGE, LLC		232.00		96,667.44
4	EARTH BUILDERS, L.P.		225.00		93,750.75
0018	504(B) 1305	SAW-CUT GROOVING	319.600	SY	
	Engineer's Estimate		**4.50**		**1,438.20**
1	HUB Construction, Inc.		7.00		2,237.20
2	K & R BUILDERS, INC.		7.00		2,237.20
3	L & N BRIDGE, LLC		6.25		1,997.50
4	EARTH BUILDERS, L.P.		7.00		2,237.20
0019	504(D) 6239	CONCRETE RAIL (TR3)	275.000	LF	
	Engineer's Estimate		**75.00**		**20,625.00**
1	HUB Construction, Inc.		75.00		20,625.00
2	K & R BUILDERS, INC.		73.00		20,075.00
3	L & N BRIDGE, LLC		95.00		26,125.00
4	EARTH BUILDERS, L.P.		90.00		24,750.00
0020	506(A) 1322	STRUCTURAL STEEL	1,810.000	LB	
	Engineer's Estimate		**3.50**		**6,335.00**
1	HUB Construction, Inc.		2.50		4,525.00
2	K & R BUILDERS, INC.		2.70		4,887.00
3	L & N BRIDGE, LLC		2.25		4,072.50
4	EARTH BUILDERS, L.P.		5.00		9,050.00
0021	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	4.000	EA	
	Engineer's Estimate		**750.00**		**3,000.00**
1	HUB Construction, Inc.		750.00		3,000.00
2	K & R BUILDERS, INC.		800.00		3,200.00
3	L & N BRIDGE, LLC		500.00		2,000.00
4	EARTH BUILDERS, L.P.		1,000.00		4,000.00
0022	507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	4.000	EA	
	Engineer's Estimate		**750.00**		**3,000.00**
1	HUB Construction, Inc.		750.00		3,000.00
2	K & R BUILDERS, INC.		800.00		3,200.00
3	L & N BRIDGE, LLC		500.00		2,000.00
4	EARTH BUILDERS, L.P.		1,000.00		4,000.00
0023	509(A) 1326	CLASS AA CONCRETE	80.600	CY	
	Engineer's Estimate		**450.00**		**36,270.00**
1	HUB Construction, Inc.		600.00		48,360.00
2	K & R BUILDERS, INC.		585.00		47,151.00
3	L & N BRIDGE, LLC		650.00		52,390.00
4	EARTH BUILDERS, L.P.		600.00		48,360.00

Letting Date: October 17, 2013, 10:30 A.M.
Call Order: 060 **Contract ID:** 130357

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE 'A'				
0024	509(B) 1328	CLASS A CONCRETE	60.100 CY	
	Engineer's Estimate		**400.00**	**24,040.00**
1	HUB Construction, Inc.		650.00	39,065.00
2	K & R BUILDERS, INC.		615.00	36,961.50
3	L & N BRIDGE, LLC		650.00	39,065.00
4	EARTH BUILDERS, L.P.		600.00	36,060.00
0025	511(A) 1332	REINFORCING STEEL	26,558.000 LB	
	Engineer's Estimate		**1.00**	**26,558.00**
1	HUB Construction, Inc.		1.00	26,558.00
2	K & R BUILDERS, INC.		0.90	23,902.20
3	L & N BRIDGE, LLC		1.00	26,558.00
4	EARTH BUILDERS, L.P.		1.00	26,558.00
0026	514(A) 6010	PILES, FURNISHED (HP 10X42)	80.000 LF	
	Engineer's Estimate		**30.00**	**2,400.00**
1	HUB Construction, Inc.		35.00	2,800.00
2	K & R BUILDERS, INC.		39.55	3,164.00
3	L & N BRIDGE, LLC		30.00	2,400.00
4	EARTH BUILDERS, L.P.		30.00	2,400.00
0027	514(A) 6011	PILES, FURNISHED (HP 12X53)	882.000 LF	
	Engineer's Estimate		**35.00**	**30,870.00**
1	HUB Construction, Inc.		40.00	35,280.00
2	K & R BUILDERS, INC.		33.25	29,326.50
3	L & N BRIDGE, LLC		32.00	28,224.00
4	EARTH BUILDERS, L.P.		35.00	30,870.00
0028	514(B) 6292	PILES, DRIVEN (HP 10X42)	80.000 LF	
	Engineer's Estimate		**15.00**	**1,200.00**
1	HUB Construction, Inc.		10.00	800.00
2	K & R BUILDERS, INC.		16.95	1,356.00
3	L & N BRIDGE, LLC		16.00	1,280.00
4	EARTH BUILDERS, L.P.		40.00	3,200.00
0029	514(B) 6294	PILES, DRIVEN (HP 12X53)	882.000 LF	
	Engineer's Estimate		**15.00**	**13,230.00**
1	HUB Construction, Inc.		10.00	8,820.00
2	K & R BUILDERS, INC.		14.25	12,568.50
3	L & N BRIDGE, LLC		14.00	12,348.00
4	EARTH BUILDERS, L.P.		40.00	35,280.00
0030	601(D) 1357	TYPE II SPECIAL PLAIN RIPRAP	1,610.000 TON	
	Engineer's Estimate		**30.00**	**48,300.00**
1	HUB Construction, Inc.		35.00	56,350.00
2	K & R BUILDERS, INC.		36.28	58,410.80
3	L & N BRIDGE, LLC		32.00	51,520.00
4	EARTH BUILDERS, L.P.		40.00	64,400.00
0031	602(C) 4205	FILTER FABRIC	1,000.000 SY	
	Engineer's Estimate		**7.00**	**7,000.00**
1	HUB Construction, Inc.		2.00	2,000.00
2	K & R BUILDERS, INC.		3.00	3,000.00
3	L & N BRIDGE, LLC		2.00	2,000.00
4	EARTH BUILDERS, L.P.		35.00	35,000.00

Letting Date: October 17, 2013, 10:30 A.M.
Call Order: 060 **Contract ID:** 130357

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002 BRIDGE 'A'			
0032	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM
	Engineer's Estimate	**2,500.00**	**2,500.00**
1	HUB Construction, Inc.	5,000.00	5,000.00
2	K & R BUILDERS, INC.	4,850.00	4,850.00
3	L & N BRIDGE, LLC	7,500.00	7,500.00
4	EARTH BUILDERS, L.P.	20,000.00	20,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 TRAFFIC			
0033	623(F) 6033	GUARDRAIL ANCHOR UNIT (TYPE II)	3.000 EA
	Engineer's Estimate	**2,200.00**	**6,600.00**
1	HUB Construction, Inc.	2,200.00	6,600.00
2	K & R BUILDERS, INC.	2,465.00	7,395.00
3	L & N BRIDGE, LLC	2,000.00	6,000.00
4	EARTH BUILDERS, L.P.	2,500.00	7,500.00
0034	623(F) 6034	GUARDRAIL ANCHOR UNIT (TYPE III)	1.000 EA
	Engineer's Estimate	**2,000.00**	**2,000.00**
1	HUB Construction, Inc.	1,950.00	1,950.00
2	K & R BUILDERS, INC.	1,905.00	1,905.00
3	L & N BRIDGE, LLC	1,700.00	1,700.00
4	EARTH BUILDERS, L.P.	2,500.00	2,500.00
0035	850(A) 8110	SHEET ALUMINUM SIGNS	17.000 SF
	Engineer's Estimate	**18.00**	**306.00**
1	HUB Construction, Inc.	18.00	306.00
2	K & R BUILDERS, INC.	15.68	266.56
3	L & N BRIDGE, LLC	14.00	238.00
4	EARTH BUILDERS, L.P.	25.00	425.00
0036	851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	34.000 LF
	Engineer's Estimate	**14.00**	**476.00**
1	HUB Construction, Inc.	20.00	680.00
2	K & R BUILDERS, INC.	8.96	304.64
3	L & N BRIDGE, LLC	8.00	272.00
4	EARTH BUILDERS, L.P.	25.00	850.00
0037	853 9033	DELINEATORS(TYPE 2, CODE 1)	16.000 EA
	Engineer's Estimate	**20.00**	**320.00**
1	HUB Construction, Inc.	30.00	480.00
2	K & R BUILDERS, INC.	20.16	322.56
3	L & N BRIDGE, LLC	18.00	288.00
4	EARTH BUILDERS, L.P.	50.00	800.00
0038	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**2,000.00**	**2,000.00**
1	HUB Construction, Inc.	3,500.00	3,500.00
2	K & R BUILDERS, INC.	2,300.00	2,300.00
3	L & N BRIDGE, LLC	1,800.00	1,800.00
4	EARTH BUILDERS, L.P.	3,500.00	3,500.00

Letting Date: October 17, 2013, 10:30 A.M.
Call Order: 060 **Contract ID:** 130357

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004 STAKING			
0039	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**6,000.00**	**6,000.00**
1	HUB Construction, Inc.	5,000.00	5,000.00
2	K & R BUILDERS, INC.	9,400.00	9,400.00
3	L & N BRIDGE, LLC	2,500.00	2,500.00
4	EARTH BUILDERS, L.P.	5,000.00	5,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0005 CONSTRUCTION			
0040	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	HUB Construction, Inc.	1,500.00	1,500.00
2	K & R BUILDERS, INC.	2,800.00	2,800.00
3	L & N BRIDGE, LLC	2,500.00	2,500.00
4	EARTH BUILDERS, L.P.	3,000.00	3,000.00
0041	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**47,000.00**	**47,000.00**
1	HUB Construction, Inc.	10,000.00	10,000.00
2	K & R BUILDERS, INC.	35,925.00	35,925.00
3	L & N BRIDGE, LLC	50,000.00	50,000.00
4	EARTH BUILDERS, L.P.	35,000.00	35,000.00