Letting Date: June 19, 2014, 10:30 A.M.
Call Order: 280 **Contract ID:** 140146
J/P No.: 29593(04) **Project No.:** SBR-234C(013)SB **Contract Time:**
County: JEFFERSON
Description: BRIDGE REHABILITATION SH-89: OVER MUD CREEK, 1.57 MILES NORTH OF SH-32.

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	616,022.25		
1	K & R BUILDERS, INC.	707,809.50	114.90	100.00
2	GIBSON & ASSOCIATES, INC.	798,824.68	129.67	112.86

Letting Date: June 19, 2014, 10:30 A.M.
Call Order: 280 **Contract ID:** 140146

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**BRIDGE**			
0001	502(C) 6116	(PL)FALSEWORK JACKING	1.000 LSUM	
	Engineer's Estimate		**25,000.00**	**25,000.00**
1	K & R BUILDERS, INC.		30,000.00	30,000.00
2	GIBSON & ASSOCIATES, INC.		45,000.00	45,000.00
0002	504(G) 6390	RAPID CURE JOINT SEALANT	348.400 LF	
	Engineer's Estimate		**25.00**	**8,710.00**
1	K & R BUILDERS, INC.		61.25	21,339.50
2	GIBSON & ASSOCIATES, INC.		29.00	10,103.60
0003	506(A) 1322	STRUCTURAL STEEL	3,350.000 LB	
	Engineer's Estimate		**8.00**	**26,800.00**
1	K & R BUILDERS, INC.		9.69	32,461.50
2	GIBSON & ASSOCIATES, INC.		3.00	10,050.00
0004	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	5.000 EA	
	Engineer's Estimate		**2,000.00**	**10,000.00**
1	K & R BUILDERS, INC.		3,500.00	17,500.00
2	GIBSON & ASSOCIATES, INC.		2,100.00	10,500.00
0005	509(B) 1328	CLASS A CONCRETE	94.400 CY	
	Engineer's Estimate		**800.00**	**75,520.00**
1	K & R BUILDERS, INC.		975.00	92,040.00
2	GIBSON & ASSOCIATES, INC.		1,705.00	160,952.00
0006	509(D) 1331	CLASS C CONCRETE	9.500 CY	
	Engineer's Estimate		**450.00**	**4,275.00**
1	K & R BUILDERS, INC.		750.00	7,125.00
2	GIBSON & ASSOCIATES, INC.		1,275.00	12,112.50
0007	511(B) 6010	EPOXY COATED REINFORCING STEEL	9,760.000 LB	
	Engineer's Estimate		**1.20**	**11,712.00**
1	K & R BUILDERS, INC.		1.50	14,640.00
2	GIBSON & ASSOCIATES, INC.		3.30	32,208.00
0008	513(B) 6019	CLASS B BRIDGE DECK REPAIR	33.800 SY	
	Engineer's Estimate		**400.00**	**13,520.00**
1	K & R BUILDERS, INC.		750.00	25,350.00
2	GIBSON & ASSOCIATES, INC.		320.00	10,816.00
0009	513(C) 6020	CLASS C BRIDGE DECK REPAIR	64.300 SY	
	Engineer's Estimate		**650.00**	**41,795.00**
1	K & R BUILDERS, INC.		1,000.00	64,300.00
2	GIBSON & ASSOCIATES, INC.		720.00	46,296.00
0010	515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	110.000 SY	
	Engineer's Estimate		**5.00**	**550.00**
1	K & R BUILDERS, INC.		5.00	550.00
2	GIBSON & ASSOCIATES, INC.		4.50	495.00
0011	516(A) 6096	DRILLED SHAFTS 60" DIAMETER	70.000 LF	
	Engineer's Estimate		**1,500.00**	**105,000.00**
1	K & R BUILDERS, INC.		1,600.00	112,000.00
2	GIBSON & ASSOCIATES, INC.		1,475.00	103,250.00

Letting Date: June 19, 2014, 10:30 A.M.
Call Order: 280 **Contract ID:** 140146

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**BRIDGE**			
0012	516(C) 6200	CROSSHOLE SONIC LOGGING	1.000 EA	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	K & R BUILDERS, INC.		4,500.00	4,500.00
2	GIBSON & ASSOCIATES, INC.		8,000.00	8,000.00
0013	520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	20.000 LF	
	Engineer's Estimate		**50.00**	**1,000.00**
1	K & R BUILDERS, INC.		50.00	1,000.00
2	GIBSON & ASSOCIATES, INC.		23.00	460.00
0014	520(C) 6060	EPOXY RESIN, ABOVE WATER	2.000 GAL	
	Engineer's Estimate		**91.50**	**183.00**
1	K & R BUILDERS, INC.		100.00	200.00
2	GIBSON & ASSOCIATES, INC.		110.00	220.00
0015	521(A) 6210	PNEUMATICALLY PLACED MORTAR	10.400 SY	
	Engineer's Estimate		**800.00**	**8,320.00**
1	K & R BUILDERS, INC.		1,637.50	17,030.00
2	GIBSON & ASSOCIATES, INC.		690.00	7,176.00
0016	523(A) 6550	SEALER CRACK PREPARATION	105.500 LF	
	Engineer's Estimate		**4.50**	**474.75**
1	K & R BUILDERS, INC.		5.00	527.50
2	GIBSON & ASSOCIATES, INC.		4.40	464.20
0017	523(B) 6560	SEALER RESIN	2.000 GAL	
	Engineer's Estimate		**150.00**	**300.00**
1	K & R BUILDERS, INC.		175.00	350.00
2	GIBSON & ASSOCIATES, INC.		165.00	330.00
0018	535 6225	HAUL AND ERECT STEEL BEAMS	1.000 LSUM	
	Engineer's Estimate		**80,000.00**	**80,000.00**
1	K & R BUILDERS, INC.		50,000.00	50,000.00
2	GIBSON & ASSOCIATES, INC.		112,500.00	112,500.00
0019	542 4600	(PL)INSTALLATION OF BRIDGE ITEMS	1.000 LSUM	
	Engineer's Estimate		**15,000.00**	**15,000.00**
1	K & R BUILDERS, INC.		15,500.00	15,500.00
2	GIBSON & ASSOCIATES, INC.		42,500.00	42,500.00
0020	545 4805	(PL)REPLACE BRIDGE ITEMS	10.000 EA	
	Engineer's Estimate		**150.00**	**1,500.00**
1	K & R BUILDERS, INC.		120.00	1,200.00
2	GIBSON & ASSOCIATES, INC.		385.00	3,850.00
0021	601(A) 1351	TYPE I PLAIN RIPRAP	261.000 TON	
	Engineer's Estimate		**60.00**	**15,660.00**
1	K & R BUILDERS, INC.		58.80	15,346.80
2	GIBSON & ASSOCIATES, INC.		113.00	29,493.00
0022	619(B) 2510	REMOVAL OF BRIDGE ITEM (TYPE A)	1.000 LSUM	
	Engineer's Estimate		**40,000.00**	**40,000.00**
1	K & R BUILDERS, INC.		30,000.00	30,000.00
2	GIBSON & ASSOCIATES, INC.		16,500.00	16,500.00

Letting Date: June 19, 2014, 10:30 A.M.
Call Order: 280 **Contract ID:** 140146

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0001**	**BRIDGE**	
0023	619(B) 2520	REMOVAL OF BRIDGE ITEM (TYPE B)	1.000 LSUM
	Engineer's Estimate	**20,000.00**	**20,000.00**
1	K & R BUILDERS, INC.	20,000.00	20,000.00
2	GIBSON & ASSOCIATES, INC.	6,600.00	6,600.00
0024	823 8478	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	90.000 SD
	Engineer's Estimate	**200.00**	**18,000.00**
1	K & R BUILDERS, INC.	156.25	14,062.50
2	GIBSON & ASSOCIATES, INC.	125.00	11,250.00
0025	855(A) 8840	TRAFFIC STRIPE(PLASTIC)(THIN LINE)(4" WIDE)	3,590.000 LF
	Engineer's Estimate	**1.00**	**3,590.00**
1	K & R BUILDERS, INC.	1.88	6,749.20
2	GIBSON & ASSOCIATES, INC.	1.00	3,590.00
0026	871(B) 8705	(SP)CONST.ZONE IMPACT ATTEN.	90.000 SD
	Engineer's Estimate	**15.00**	**1,350.00**
1	K & R BUILDERS, INC.	37.50	3,375.00
2	GIBSON & ASSOCIATES, INC.	6.60	594.00
0027	877(B) 8484	DELIVER PORTABLE LONGITUDINAL BARRIER	787.500 LF
	Engineer's Estimate	**22.00**	**17,325.00**
1	K & R BUILDERS, INC.	45.00	35,437.50
2	GIBSON & ASSOCIATES, INC.	22.75	17,915.63
0028	877(C) 8486	RELOCATION OF PORTABLE LONGITUDINAL BARRIER	787.500 LF
	Engineer's Estimate	**5.00**	**3,937.50**
1	K & R BUILDERS, INC.	6.00	4,725.00
2	GIBSON & ASSOCIATES, INC.	3.30	2,598.75
0029	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**2,500.00**	**2,500.00**
1	K & R BUILDERS, INC.	12,000.00	12,000.00
2	GIBSON & ASSOCIATES, INC.	19,500.00	19,500.00
Section:	**0003**	**STAKING**	
0030	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**6,000.00**	**6,000.00**
1	K & R BUILDERS, INC.	6,000.00	6,000.00
2	GIBSON & ASSOCIATES, INC.	3,500.00	3,500.00
Section:	**0004**	**CONSTRUCTION**	

Letting Date: June 19, 2014, 10:30 A.M.

Call Order: 280 **Contract ID:** 140146

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0004**	**CONSTRUCTION**		
0031	641 1399	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**53,000.00**	**53,000.00**
	1 K & R BUILDERS, INC.		52,500.00	52,500.00
	2 GIBSON & ASSOCIATES, INC.		70,000.00	70,000.00