Letting Date: June 19, 2014, 10:30 A.M.
Call Order: 600 **Contract ID:** 140218
J/P No.: 29456(04) **Project No.:** NHPPIY-0040-5(424) **Contract Time:**
County: POTTAWATOMIE
Description: BRIDGE REHABILITATION I-40: OVER SH-9A, 6.0 MILES EAST OF SH-18.

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	106,190.00		
1	LOGOS CONSTRUCTION CO., LLC	121,061.00	114.00	100.00
2	SCR CONSTRUCTION CO., INC.	143,400.00	135.04	118.45
3	M.J. HUGHES CONSTRUCTION, INC.	217,000.00	204.35	179.25

Letting Date: June 19, 2014, 10:30 A.M.
Call Order: 600 **Contract ID:** 140218

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	619(B) 4780	REMOVAL OF GUARDRAIL	600.000	LF	
	Engineer's Estimate		**4.00**		**2,400.00**
1	LOGOS CONSTRUCTION CO., LLC		5.50		3,300.00
2	SCR CONSTRUCTION CO., INC.		5.50		3,300.00
3	M.J. HUGHES CONSTRUCTION, INC.		2.70		1,620.00
0002	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	400.000	LF	
	Engineer's Estimate		**20.00**		**8,000.00**
1	LOGOS CONSTRUCTION CO., LLC		27.50		11,000.00
2	SCR CONSTRUCTION CO., INC.		27.00		10,800.00
3	M.J. HUGHES CONSTRUCTION, INC.		26.25		10,500.00
0003	623(G) 8590	GUARDRAIL END TREATMENT (31")	4.000	EA	
	Engineer's Estimate		**2,200.00**		**8,800.00**
1	LOGOS CONSTRUCTION CO., LLC		2,535.00		10,140.00
2	SCR CONSTRUCTION CO., INC.		2,400.00		9,600.00
3	M.J. HUGHES CONSTRUCTION, INC.		4,610.00		18,440.00
0004	853 9033	DELINEATORS(TYPE 2, CODE 1)	10.000	EA	
	Engineer's Estimate		**20.00**		**200.00**
1	LOGOS CONSTRUCTION CO., LLC		15.40		154.00
2	SCR CONSTRUCTION CO., INC.		18.00		180.00
3	M.J. HUGHES CONSTRUCTION, INC.		14.00		140.00

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A'					
0005	509 6152	SPECIAL CONCRETE FINISH	369.000	SY	
	Engineer's Estimate		**50.00**		**18,450.00**
1	LOGOS CONSTRUCTION CO., LLC		40.00		14,760.00
2	SCR CONSTRUCTION CO., INC.		45.00		16,605.00
3	M.J. HUGHES CONSTRUCTION, INC.		43.00		15,867.00
0006	520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	60.000	LF	
	Engineer's Estimate		**30.00**		**1,800.00**
1	LOGOS CONSTRUCTION CO., LLC		30.00		1,800.00
2	SCR CONSTRUCTION CO., INC.		90.00		5,400.00
3	M.J. HUGHES CONSTRUCTION, INC.		56.00		3,360.00
0007	520(C) 6060	EPOXY RESIN, ABOVE WATER	6.000	GAL	
	Engineer's Estimate		**110.00**		**660.00**
1	LOGOS CONSTRUCTION CO., LLC		60.00		360.00
2	SCR CONSTRUCTION CO., INC.		80.00		480.00
3	M.J. HUGHES CONSTRUCTION, INC.		562.00		3,372.00
0008	521(A) 6210	PNEUMATICALLY PLACED MORTAR	23.000	SY	
	Engineer's Estimate		**600.00**		**13,800.00**
1	LOGOS CONSTRUCTION CO., LLC		635.00		14,605.00
2	SCR CONSTRUCTION CO., INC.		700.00		16,100.00
3	M.J. HUGHES CONSTRUCTION, INC.		921.00		21,183.00

Letting Date: June 19, 2014, 10:30 A.M.
Call Order: 600 **Contract ID:** 140218

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002 BRIDGE 'A'			
0009	535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	23.000 SY
	Engineer's Estimate	**60.00**	**1,380.00**
1	LOGOS CONSTRUCTION CO., LLC	50.00	1,150.00
2	SCR CONSTRUCTION CO., INC.	100.00	2,300.00
3	M.J. HUGHES CONSTRUCTION, INC.	172.00	3,956.00
0010	540 4501	(PL)REPAIR BRIDGE ITEMS	5.000 SY
	Engineer's Estimate	**700.00**	**3,500.00**
1	LOGOS CONSTRUCTION CO., LLC	1,520.00	7,600.00
2	SCR CONSTRUCTION CO., INC.	1,400.00	7,000.00
3	M.J. HUGHES CONSTRUCTION, INC.	3,762.00	18,810.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 BRIDGE 'B'			
0011	509 6152	SPECIAL CONCRETE FINISH	375.000 SY
	Engineer's Estimate	**50.00**	**18,750.00**
1	LOGOS CONSTRUCTION CO., LLC	40.00	15,000.00
2	SCR CONSTRUCTION CO., INC.	45.00	16,875.00
3	M.J. HUGHES CONSTRUCTION, INC.	31.75	11,906.25
0012	520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	57.000 LF
	Engineer's Estimate	**30.00**	**1,710.00**
1	LOGOS CONSTRUCTION CO., LLC	30.00	1,710.00
2	SCR CONSTRUCTION CO., INC.	90.00	5,130.00
3	M.J. HUGHES CONSTRUCTION, INC.	56.00	3,192.00
0013	520(C) 6060	EPOXY RESIN, ABOVE WATER	6.000 GAL
	Engineer's Estimate	**110.00**	**660.00**
1	LOGOS CONSTRUCTION CO., LLC	60.00	360.00
2	SCR CONSTRUCTION CO., INC.	80.00	480.00
3	M.J. HUGHES CONSTRUCTION, INC.	562.00	3,372.00
0014	521(A) 6210	PNEUMATICALLY PLACED MORTAR	13.000 SY
	Engineer's Estimate	**600.00**	**7,800.00**
1	LOGOS CONSTRUCTION CO., LLC	635.00	8,255.00
2	SCR CONSTRUCTION CO., INC.	700.00	9,100.00
3	M.J. HUGHES CONSTRUCTION, INC.	921.00	11,973.00
0015	535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	13.000 SY
	Engineer's Estimate	**60.00**	**780.00**
1	LOGOS CONSTRUCTION CO., LLC	50.00	650.00
2	SCR CONSTRUCTION CO., INC.	100.00	1,300.00
3	M.J. HUGHES CONSTRUCTION, INC.	172.00	2,236.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004 TRAFFIC			

Letting Date: June 19, 2014, 10:30 A.M.
Call Order: 600 **Contract ID:** 140218

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004 TRAFFIC			
0016	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	2,200.000 LF
	Engineer's Estimate	**1.00**	**2,200.00**
1	LOGOS CONSTRUCTION CO., LLC	3.06	6,732.00
2	SCR CONSTRUCTION CO., INC.	2.25	4,950.00
3	M.J. HUGHES CONSTRUCTION, INC.	3.50	7,700.00
0017	876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	5.000 SD
	Engineer's Estimate	**60.00**	**300.00**
1	LOGOS CONSTRUCTION CO., LLC	110.00	550.00
2	SCR CONSTRUCTION CO., INC.	100.00	500.00
3	M.J. HUGHES CONSTRUCTION, INC.	213.00	1,065.00
0018	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	LOGOS CONSTRUCTION CO., LLC	11,535.00	11,535.00
2	SCR CONSTRUCTION CO., INC.	19,000.00	19,000.00
3	M.J. HUGHES CONSTRUCTION, INC.	56,607.75	56,607.75

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0005 CONSTRUCTION			
0019	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**10,000.00**	**10,000.00**
1	LOGOS CONSTRUCTION CO., LLC	11,400.00	11,400.00
2	SCR CONSTRUCTION CO., INC.	14,300.00	14,300.00
3	M.J. HUGHES CONSTRUCTION, INC.	21,700.00	21,700.00