Letting Date: July 24, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140232
J/P No.: 29582(04) **Project No.:** SSP-210B(014)SS **Contract Time:**
County: CARTER
Description: BRIDGE REHABILITATION US-177: OVER KEMP CREEK, 1.5 MILES SOUTH OF SH-53.

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	1,061,646.50		
1	B & B CONSTRUCTION SERVICE J.T., INC.	1,132,450.39	106.67	100.00
2	K & R BUILDERS, INC.	1,142,206.69	107.59	100.86
3	BRIDGECO CONTRACTORS, INC.	1,206,740.96	113.67	106.56

Letting Date: July 24, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140232

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	201(A) 0102	CLEARING AND GRUBBING	1.000 LSUM	
	Engineer's Estimate		**10,000.00**	**10,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		22,000.00	22,000.00
2	K & R BUILDERS, INC.		12,500.00	12,500.00
3	BRIDGECO CONTRACTORS, INC.		18,000.00	18,000.00
0002	202(D) 0184	UNCLASSIFIED BORROW	990.000 CY	
	Engineer's Estimate		**15.00**	**14,850.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		14.00	13,860.00
2	K & R BUILDERS, INC.		18.00	17,820.00
3	BRIDGECO CONTRACTORS, INC.		20.00	19,800.00
0003	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000 LSUM	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		6,500.00	6,500.00
2	K & R BUILDERS, INC.		7,750.00	7,750.00
3	BRIDGECO CONTRACTORS, INC.		5,000.00	5,000.00
0004	221(C) 2801	TEMPORARY SILT FENCE	1,132.000 LF	
	Engineer's Estimate		**5.00**	**5,660.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		2.00	2,264.00
2	K & R BUILDERS, INC.		2.50	2,830.00
3	BRIDGECO CONTRACTORS, INC.		2.00	2,264.00
0005	221(F) 0100	TEMPORARY SILT DIKE	20.000 LF	
	Engineer's Estimate		**20.00**	**400.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		11.00	220.00
2	K & R BUILDERS, INC.		25.00	500.00
3	BRIDGECO CONTRACTORS, INC.		10.00	200.00
0006	230(A) 2806	SOLID SLAB SODDING	2,270.000 SY	
	Engineer's Estimate		**5.00**	**11,350.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		2.00	4,540.00
2	K & R BUILDERS, INC.		6.60	14,982.00
3	BRIDGECO CONTRACTORS, INC.		3.30	7,491.00
0007	230(F) 2812	WATERING	181.000 KGAL	
	Engineer's Estimate		**10.00**	**1,810.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		11.50	2,081.50
2	K & R BUILDERS, INC.		12.00	2,172.00
3	BRIDGECO CONTRACTORS, INC.		11.00	1,991.00
0008	234(A) 2824	FERTILIZING (10-20-10)	0.230 TON	
	Engineer's Estimate		**1,500.00**	**345.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		1,500.00	345.00
2	K & R BUILDERS, INC.		1,000.00	230.00
3	BRIDGECO CONTRACTORS, INC.		1,700.00	391.00
0009	303(A) 2100	AGGREGATE BASE TYPE A	216.000 CY	
	Engineer's Estimate		**80.00**	**17,280.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		126.00	27,216.00
2	K & R BUILDERS, INC.		134.00	28,944.00
3	BRIDGECO CONTRACTORS, INC.		80.00	17,280.00

Letting Date: July 24, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140232

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001	**ROADWAY**				
0010	408 5774	PRIME COAT	280.000	GAL	
	Engineer's Estimate		**10.00**		**2,800.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		8.00		2,240.00
2	K & R BUILDERS, INC.		6.00		1,680.00
3	BRIDGECO CONTRACTORS, INC.		10.50		2,940.00
0011	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	278.000	TON	
	Engineer's Estimate		**150.00**		**41,700.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		125.00		34,750.00
2	K & R BUILDERS, INC.		137.50		38,225.00
3	BRIDGECO CONTRACTORS, INC.		162.00		45,036.00
0012	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	311.000	TON	
	Engineer's Estimate		**150.00**		**46,650.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		132.25		41,129.75
2	K & R BUILDERS, INC.		143.75		44,706.25
3	BRIDGECO CONTRACTORS, INC.		177.00		55,047.00
0013	412 5267	COLD MILLING PAVEMENT	1,145.000	SY	
	Engineer's Estimate		**15.00**		**17,175.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		15.00		17,175.00
2	K & R BUILDERS, INC.		22.00		25,190.00
3	BRIDGECO CONTRACTORS, INC.		10.50		12,022.50
0014	509(D) 0325	CLASS C CONCRETE	6.600	CY	
	Engineer's Estimate		**400.00**		**2,640.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		700.00		4,620.00
2	K & R BUILDERS, INC.		725.00		4,785.00
3	BRIDGECO CONTRACTORS, INC.		510.00		3,366.00
0015	619(B) 4780	REMOVAL OF GUARDRAIL	660.000	LF	
	Engineer's Estimate		**5.00**		**3,300.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		3.00		1,980.00
2	K & R BUILDERS, INC.		5.50		3,630.00
3	BRIDGECO CONTRACTORS, INC.		4.00		2,640.00
0016	623 0100	(PL)GUARDRAIL CURBING	4.000	EA	
	Engineer's Estimate		**750.00**		**3,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		1,500.00		6,000.00
2	K & R BUILDERS, INC.		1,575.00		6,300.00
3	BRIDGECO CONTRACTORS, INC.		1,500.00		6,000.00
0017	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	300.000	LF	
	Engineer's Estimate		**25.00**		**7,500.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		19.20		5,760.00
2	K & R BUILDERS, INC.		20.00		6,000.00
3	BRIDGECO CONTRACTORS, INC.		17.49		5,247.00
0018	623(G) 8590	GUARDRAIL END TREATMENT (31")	4.000	EA	
	Engineer's Estimate		**3,000.00**		**12,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		2,640.00		10,560.00
2	K & R BUILDERS, INC.		2,520.00		10,080.00
3	BRIDGECO CONTRACTORS, INC.		2,420.00		9,680.00

Letting Date: July 24, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140232

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0019	623(I) 8700	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000 EA	
	Engineer's Estimate		**2,500.00**	**10,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		2,600.00	10,400.00
2	K & R BUILDERS, INC.		2,010.00	8,040.00
3	BRIDGECO CONTRACTORS, INC.		2,350.00	9,400.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE				
0020	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	1,000.000 CY	
	Engineer's Estimate		**15.00**	**15,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		25.00	25,000.00
2	K & R BUILDERS, INC.		22.00	22,000.00
3	BRIDGECO CONTRACTORS, INC.		33.00	33,000.00
0021	504(A) 1304	APPROACH SLAB	174.000 SY	
	Engineer's Estimate		**250.00**	**43,500.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		292.37	50,872.38
2	K & R BUILDERS, INC.		295.00	51,330.00
3	BRIDGECO CONTRACTORS, INC.		280.00	48,720.00
0022	504(B) 1305	SAW-CUT GROOVING	581.000 SY	
	Engineer's Estimate		**5.00**	**2,905.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		7.50	4,357.50
2	K & R BUILDERS, INC.		6.00	3,486.00
3	BRIDGECO CONTRACTORS, INC.		4.40	2,556.40
0023	504(C) 6250	SEALED EXPANSION JOINT	40.200 LF	
	Engineer's Estimate		**350.00**	**14,070.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		280.00	11,256.00
2	K & R BUILDERS, INC.		335.00	13,467.00
3	BRIDGECO CONTRACTORS, INC.		465.00	18,693.00
0024	504(D) 6245	CONCRETE RAIL (TR4)	282.600 LF	
	Engineer's Estimate		**100.00**	**28,260.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		172.32	48,697.63
2	K & R BUILDERS, INC.		112.50	31,792.50
3	BRIDGECO CONTRACTORS, INC.		105.00	29,673.00
0025	506(A) 1322	STRUCTURAL STEEL	74,640.000 LB	
	Engineer's Estimate		**3.00**	**223,920.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		2.65	197,796.00
2	K & R BUILDERS, INC.		2.50	186,600.00
3	BRIDGECO CONTRACTORS, INC.		2.70	201,528.00
0026	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000 EA	
	Engineer's Estimate		**2,000.00**	**24,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		1,500.00	18,000.00
2	K & R BUILDERS, INC.		1,700.00	20,400.00
3	BRIDGECO CONTRACTORS, INC.		880.00	10,560.00

Letting Date: July 24, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140232

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE				
0027	507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	24.000 EA	
	Engineer's Estimate		**2,000.00**	**48,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		1,620.00	38,880.00
2	K & R BUILDERS, INC.		1,700.00	40,800.00
3	BRIDGECO CONTRACTORS, INC.		880.00	21,120.00
0028	509(A) 1326	CLASS AA CONCRETE	118.000 CY	
	Engineer's Estimate		**850.00**	**100,300.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		993.22	117,199.96
2	K & R BUILDERS, INC.		975.00	115,050.00
3	BRIDGECO CONTRACTORS, INC.		1,100.00	129,800.00
0029	509(B) 1328	CLASS A CONCRETE	17.200 CY	
	Engineer's Estimate		**800.00**	**13,760.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		3,025.00	52,030.00
2	K & R BUILDERS, INC.		4,500.00	77,400.00
3	BRIDGECO CONTRACTORS, INC.		1,100.00	18,920.00
0030	511 6306	MECHANICAL SPLICES	254.000 EA	
	Engineer's Estimate		**30.00**	**7,620.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		24.00	6,096.00
2	K & R BUILDERS, INC.		30.00	7,620.00
3	BRIDGECO CONTRACTORS, INC.		45.00	11,430.00
0031	511(B) 6010	EPOXY COATED REINFORCING STEEL	26,160.000 LB	
	Engineer's Estimate		**1.30**	**34,008.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		1.46	38,193.60
2	K & R BUILDERS, INC.		1.23	32,176.80
3	BRIDGECO CONTRACTORS, INC.		1.75	45,780.00
0032	515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	324.000 SY	
	Engineer's Estimate		**5.00**	**1,620.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		3.50	1,134.00
2	K & R BUILDERS, INC.		7.50	2,430.00
3	BRIDGECO CONTRACTORS, INC.		4.00	1,296.00
0033	520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	28.000 LF	
	Engineer's Estimate		**50.00**	**1,400.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		35.94	1,006.32
2	K & R BUILDERS, INC.		96.00	2,688.00
3	BRIDGECO CONTRACTORS, INC.		150.00	4,200.00
0034	520(C) 6060	EPOXY RESIN, ABOVE WATER	3.000 GAL	
	Engineer's Estimate		**150.00**	**450.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		100.00	300.00
2	K & R BUILDERS, INC.		150.00	450.00
3	BRIDGECO CONTRACTORS, INC.		1,200.00	3,600.00
0035	521(A) 6210	PNEUMATICALLY PLACED MORTAR	8.200 SY	
	Engineer's Estimate		**850.00**	**6,970.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.		915.00	7,503.00
2	K & R BUILDERS, INC.		1,281.60	10,509.12
3	BRIDGECO CONTRACTORS, INC.		1,600.00	13,120.00

Letting Date: July 24, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140232

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002 BRIDGE			
0036	523(A) 6550	SEALER CRACK PREPARATION	140.500 LF
	Engineer's Estimate	**5.00**	**702.50**
1	B & B CONSTRUCTION SERVICE J.T., INC.	2.50	351.25
2	K & R BUILDERS, INC.	7.00	983.50
3	BRIDGECO CONTRACTORS, INC.	4.40	618.20
0037	523(B) 6560	SEALER RESIN	3.000 GAL
	Engineer's Estimate	**150.00**	**450.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	75.00	225.00
2	K & R BUILDERS, INC.	240.00	720.00
3	BRIDGECO CONTRACTORS, INC.	200.00	600.00
0038	619(B) 2500	REMOVAL OF BRIDGE ITEMS	1.000 LSUM
	Engineer's Estimate	**80,000.00**	**80,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	86,000.00	86,000.00
2	K & R BUILDERS, INC.	105,000.00	105,000.00
3	BRIDGECO CONTRACTORS, INC.	150,000.00	150,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 TRAFFIC			
0039	823 8478	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	300.000 SD
	Engineer's Estimate	**200.00**	**60,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	90.00	27,000.00
2	K & R BUILDERS, INC.	5.00	1,500.00
3	BRIDGECO CONTRACTORS, INC.	71.50	21,450.00
0040	853 9033	DELINEATORS(TYPE 2, CODE 1)	40.000 EA
	Engineer's Estimate	**22.00**	**880.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	7.00	280.00
2	K & R BUILDERS, INC.	24.00	960.00
3	BRIDGECO CONTRACTORS, INC.	6.16	246.40
0041	855(A) 8840	TRAFFIC STRIPE(PLASTIC)(THIN LINE)(4" WIDE)	1,546.000 LF
	Engineer's Estimate	**1.00**	**1,546.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	2.00	3,092.00
2	K & R BUILDERS, INC.	1.62	2,504.52
3	BRIDGECO CONTRACTORS, INC.	1.51	2,334.46
0042	871(B) 8705	(SP)CONST.ZONE IMPACT ATTEN.	300.000 SD
	Engineer's Estimate	**15.00**	**4,500.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	11.50	3,450.00
2	K & R BUILDERS, INC.	7.50	2,250.00
3	BRIDGECO CONTRACTORS, INC.	11.00	3,300.00
0043	877(B) 8484	DELIVER PORTABLE LONGITUDINAL BARRIER	1,075.000 LF
	Engineer's Estimate	**35.00**	**37,625.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	28.18	30,293.50
2	K & R BUILDERS, INC.	37.00	39,775.00
3	BRIDGECO CONTRACTORS, INC.	27.00	29,025.00

Letting Date: July 24, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140232

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0003**	**TRAFFIC**	
0044	877(C) 8486	RELOCATION OF PORTABLE LONGITUDINAL BARRIER	1,075.000 LF
	Engineer's Estimate	**10.00**	**10,750.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	2.60	2,795.00
2	K & R BUILDERS, INC.	6.00	6,450.00
3	BRIDGECO CONTRACTORS, INC.	5.00	5,375.00
0045	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**4,950.00**	**4,950.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	45,000.00	45,000.00
2	K & R BUILDERS, INC.	37,500.00	37,500.00
3	BRIDGECO CONTRACTORS, INC.	31,000.00	31,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0004**	**STAKING**	
0046	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**7,000.00**	**7,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	14,000.00	14,000.00
2	K & R BUILDERS, INC.	8,000.00	8,000.00
3	BRIDGECO CONTRACTORS, INC.	9,000.00	9,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0005**	**CONSTRUCTION**	
0047	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**74,000.00**	**74,000.00**
1	B & B CONSTRUCTION SERVICE J.T., INC.	88,000.00	88,000.00
2	K & R BUILDERS, INC.	82,000.00	82,000.00
3	BRIDGECO CONTRACTORS, INC.	136,000.00	136,000.00