Letting Date: June 19, 2014, 10:00 A.M.
Call Order: 010 **Contract ID:** 140285
J/P No.: 30989(04) **Project No.:** SSP-264B(026)SS **Contract Time:**
County: PUSHMATAHA
Description: GRADE, DRAIN, AND SURFACE US-271: EMERGENCY SLIDE REPAIR 0.5 MILES NORTH OF SH-144, EXTEND NORTH. PROJECT LENGTH = 0.047 MILES BOTH BID EXPRESS AND WRITTEN BIDS WILL BE ACCEPTABLE.

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	1,378,259.75		
1	C-GAWF CONSTRUCTION, INC.	1,384,178.00	100.43	100.00
2	SHERWOOD CONSTRUCTION CO., INC.	1,970,880.50	143.00	142.39
3	GLOVER & ASSOCIATES, INC.	2,296,761.60	166.64	165.93

Letting Date: June 19, 2014, 10:00 A.M.
Call Order: 010 **Contract ID:** 140285

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM
	Engineer's Estimate		**20,000.00**	**20,000.00**
1	C-GAWF CONSTRUCTION, INC.		2,500.00	2,500.00
2	SHERWOOD CONSTRUCTION CO., INC.		65,000.00	65,000.00
3	GLOVER & ASSOCIATES, INC.		175,000.00	175,000.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	15,027.000	CY
	Engineer's Estimate		**9.00**	**135,243.00**
1	C-GAWF CONSTRUCTION, INC.		22.50	338,107.50
2	SHERWOOD CONSTRUCTION CO., INC.		15.00	225,405.00
3	GLOVER & ASSOCIATES, INC.		31.00	465,837.00
0003	202(J) 5250	QUARRY STONE EMBANKMENT	23,962.000	TON
	Engineer's Estimate		**30.00**	**718,860.00**
1	C-GAWF CONSTRUCTION, INC.		29.00	694,898.00
2	SHERWOOD CONSTRUCTION CO., INC.		47.50	1,138,195.00
3	GLOVER & ASSOCIATES, INC.		32.00	766,784.00
0004	221(C) 2801	TEMPORARY SILT FENCE	1,200.000	LF
	Engineer's Estimate		**2.25**	**2,700.00**
1	C-GAWF CONSTRUCTION, INC.		1.55	1,860.00
2	SHERWOOD CONSTRUCTION CO., INC.		3.50	4,200.00
3	GLOVER & ASSOCIATES, INC.		2.65	3,180.00
0005	221(F) 0100	TEMPORARY SILT DIKE	84.000	LF
	Engineer's Estimate		**10.00**	**840.00**
1	C-GAWF CONSTRUCTION, INC.		7.10	596.40
2	SHERWOOD CONSTRUCTION CO., INC.		15.00	1,260.00
3	GLOVER & ASSOCIATES, INC.		13.50	1,134.00
0006	230(A) 2806	SOLID SLAB SODDING	57,860.000	SY
	Engineer's Estimate		**1.75**	**101,255.00**
1	C-GAWF CONSTRUCTION, INC.		0.15	8,679.00
2	SHERWOOD CONSTRUCTION CO., INC.		2.00	115,720.00
3	GLOVER & ASSOCIATES, INC.		1.77	102,412.20
0007	303(B) 2110	AGGREGATE BASE TYPE B	1,165.000	CY
	Engineer's Estimate		**60.00**	**69,900.00**
1	C-GAWF CONSTRUCTION, INC.		53.25	62,036.25
2	SHERWOOD CONSTRUCTION CO., INC.		60.00	69,900.00
3	GLOVER & ASSOCIATES, INC.		71.00	82,715.00
0008	325 5271	SEPARATOR FABRIC	2,259.000	SY
	Engineer's Estimate		**1.25**	**2,823.75**
1	C-GAWF CONSTRUCTION, INC.		2.49	5,624.91
2	SHERWOOD CONSTRUCTION CO., INC.		2.50	5,647.50
3	GLOVER & ASSOCIATES, INC.		3.00	6,777.00
0009	326(B) 0100	GEOGRID REINFORCEMENT	1,176.000	SY
	Engineer's Estimate		**3.25**	**3,822.00**
1	C-GAWF CONSTRUCTION, INC.		5.85	6,879.60
2	SHERWOOD CONSTRUCTION CO., INC.		3.00	3,528.00
3	GLOVER & ASSOCIATES, INC.		4.65	5,468.40

Letting Date: June 19, 2014, 10:00 A.M.
Call Order: 010 **Contract ID:** 140285

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0010	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	361.000	TON	
	Engineer's Estimate		**25.00**		**9,025.00**
1	C-GAWF CONSTRUCTION, INC.		28.33		10,227.13
2	SHERWOOD CONSTRUCTION CO., INC.		30.00		10,830.00
3	GLOVER & ASSOCIATES, INC.		40.00		14,440.00
0011	407(B) 0250	TACK COAT	120.000	GAL	
	Engineer's Estimate		**3.00**		**360.00**
1	C-GAWF CONSTRUCTION, INC.		7.77		932.40
2	SHERWOOD CONSTRUCTION CO., INC.		10.00		1,200.00
3	GLOVER & ASSOCIATES, INC.		8.00		960.00
0012	408 5774	PRIME COAT	802.000	GAL	
	Engineer's Estimate		**5.00**		**4,010.00**
1	C-GAWF CONSTRUCTION, INC.		7.77		6,231.54
2	SHERWOOD CONSTRUCTION CO., INC.		7.50		6,015.00
3	GLOVER & ASSOCIATES, INC.		5.00		4,010.00
0013	411(B) 5940	SUPERPAVE, TYPE S3(PG 70-28 OK)	270.000	TON	
	Engineer's Estimate		**150.00**		**40,500.00**
1	C-GAWF CONSTRUCTION, INC.		100.00		27,000.00
2	SHERWOOD CONSTRUCTION CO., INC.		125.00		33,750.00
3	GLOVER & ASSOCIATES, INC.		155.00		41,850.00
0014	411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	122.000	TON	
	Engineer's Estimate		**200.00**		**24,400.00**
1	C-GAWF CONSTRUCTION, INC.		100.00		12,200.00
2	SHERWOOD CONSTRUCTION CO., INC.		150.00		18,300.00
3	GLOVER & ASSOCIATES, INC.		200.00		24,400.00
0015	501(A) 0313	STRUCTURAL EXCAVATION UNCLASSIFIED	10.000	CY	
	Engineer's Estimate		**20.00**		**200.00**
1	C-GAWF CONSTRUCTION, INC.		50.00		500.00
2	SHERWOOD CONSTRUCTION CO., INC.		10.00		100.00
3	GLOVER & ASSOCIATES, INC.		1,075.00		10,750.00
0016	509(A) 0319	CLASS AA CONCRETE	35.000	CY	
	Engineer's Estimate		**900.00**		**31,500.00**
1	C-GAWF CONSTRUCTION, INC.		777.00		27,195.00
2	SHERWOOD CONSTRUCTION CO., INC.		700.00		24,500.00
3	GLOVER & ASSOCIATES, INC.		1,300.00		45,500.00
0017	509(D) 0325	CLASS C CONCRETE	114.000	CY	
	Engineer's Estimate		**300.00**		**34,200.00**
1	C-GAWF CONSTRUCTION, INC.		289.75		33,031.50
2	SHERWOOD CONSTRUCTION CO., INC.		425.00		48,450.00
3	GLOVER & ASSOCIATES, INC.		500.00		57,000.00
0018	511(A) 0332	REINFORCING STEEL	4,500.000	LB	
	Engineer's Estimate		**1.60**		**7,200.00**
1	C-GAWF CONSTRUCTION, INC.		1.44		6,480.00
2	SHERWOOD CONSTRUCTION CO., INC.		2.00		9,000.00
3	GLOVER & ASSOCIATES, INC.		3.00		13,500.00

Letting Date: June 19, 2014, 10:00 A.M.
Call Order: 010 **Contract ID:** 140285

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001	**ROADWAY**				
0019	601(B) 0536	TYPE I-A PLAIN RIPRAP	173.000	TON	
	Engineer's Estimate		**50.00**		**8,650.00**
1	C-GAWF CONSTRUCTION, INC.		37.11		6,420.03
2	SHERWOOD CONSTRUCTION CO., INC.		55.00		9,515.00
3	GLOVER & ASSOCIATES, INC.		80.00		13,840.00
0020	601(C) 0538	TYPE I-A FILTER BLANKET	43.000	TON	
	Engineer's Estimate		**50.00**		**2,150.00**
1	C-GAWF CONSTRUCTION, INC.		31.68		1,362.24
2	SHERWOOD CONSTRUCTION CO., INC.		45.00		1,935.00
3	GLOVER & ASSOCIATES, INC.		70.00		3,010.00
0021	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM	
	Engineer's Estimate		**25,000.00**		**25,000.00**
1	C-GAWF CONSTRUCTION, INC.		500.00		500.00
2	SHERWOOD CONSTRUCTION CO., INC.		15,000.00		15,000.00
3	GLOVER & ASSOCIATES, INC.		100,000.00		100,000.00
0022	619(B) 0291	REMOVAL OF HEADWALL	1.000	EA	
	Engineer's Estimate		**1,500.00**		**1,500.00**
1	C-GAWF CONSTRUCTION, INC.		500.00		500.00
2	SHERWOOD CONSTRUCTION CO., INC.		3,000.00		3,000.00
3	GLOVER & ASSOCIATES, INC.		50,000.00		50,000.00
0023	619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	890.000	SY	
	Engineer's Estimate		**10.00**		**8,900.00**
1	C-GAWF CONSTRUCTION, INC.		3.00		2,670.00
2	SHERWOOD CONSTRUCTION CO., INC.		5.00		4,450.00
3	GLOVER & ASSOCIATES, INC.		23.00		20,470.00
0024	619(C) 0924	SAWING PAVEMENT	60.000	LF	
	Engineer's Estimate		**4.00**		**240.00**
1	C-GAWF CONSTRUCTION, INC.		10.00		600.00
2	SHERWOOD CONSTRUCTION CO., INC.		4.50		270.00
3	GLOVER & ASSOCIATES, INC.		21.00		1,260.00
0025	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF	
	Engineer's Estimate		**25.00**		**5,000.00**
1	C-GAWF CONSTRUCTION, INC.		20.00		4,000.00
2	SHERWOOD CONSTRUCTION CO., INC.		17.50		3,500.00
3	GLOVER & ASSOCIATES, INC.		37.00		7,400.00
0026	623(G) 8590	GUARDRAIL END TREATMENT (31")	1.000	EA	
	Engineer's Estimate		**2,250.00**		**2,250.00**
1	C-GAWF CONSTRUCTION, INC.		2,750.00		2,750.00
2	SHERWOOD CONSTRUCTION CO., INC.		2,100.00		2,100.00
3	GLOVER & ASSOCIATES, INC.		3,200.00		3,200.00
0027	625(D) 1254	REMOVE AND RECONSTRUCT GUARDRAIL	233.000	LF	
	Engineer's Estimate		**15.00**		**3,495.00**
1	C-GAWF CONSTRUCTION, INC.		3.00		699.00
2	SHERWOOD CONSTRUCTION CO., INC.		20.00		4,660.00
3	GLOVER & ASSOCIATES, INC.		38.00		8,854.00

Letting Date: June 19, 2014, 10:00 A.M.
Call Order: 010 **Contract ID:** 140285

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0001**	**ROADWAY**	
0028	802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	250.000 LF
	Engineer's Estimate	**5.00**	**1,250.00**
1	C-GAWF CONSTRUCTION, INC.	5.00	1,250.00
2	SHERWOOD CONSTRUCTION CO., INC.	50.00	12,500.00
3	GLOVER & ASSOCIATES, INC.	63.00	15,750.00
0029	853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	5.000 EA
	Engineer's Estimate	**50.00**	**250.00**
1	C-GAWF CONSTRUCTION, INC.	7.00	35.00
2	SHERWOOD CONSTRUCTION CO., INC.	5.00	25.00
3	GLOVER & ASSOCIATES, INC.	82.00	410.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0002**	**TRAFFIC CONTROL**	
0030	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	C-GAWF CONSTRUCTION, INC.	12,500.00	12,500.00
2	SHERWOOD CONSTRUCTION CO., INC.	25,000.00	25,000.00
3	GLOVER & ASSOCIATES, INC.	75,000.00	75,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0003**	**STRIPING**	
0031	855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	1,950.000 LF
	Engineer's Estimate	**0.90**	**1,755.00**
1	C-GAWF CONSTRUCTION, INC.	1.75	3,412.50
2	SHERWOOD CONSTRUCTION CO., INC.	1.50	2,925.00
3	GLOVER & ASSOCIATES, INC.	3.00	5,850.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0004**	**STAKING**	
0032	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**16,540.00**	**16,540.00**
1	C-GAWF CONSTRUCTION, INC.	2,500.00	2,500.00
2	SHERWOOD CONSTRUCTION CO., INC.	30,000.00	30,000.00
3	GLOVER & ASSOCIATES, INC.	45,000.00	45,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0005**	**CONSTRUCTION**	
0033	641 1552	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**89,441.00**	**89,441.00**
1	C-GAWF CONSTRUCTION, INC.	100,000.00	100,000.00
2	SHERWOOD CONSTRUCTION CO., INC.	75,000.00	75,000.00
3	GLOVER & ASSOCIATES, INC.	125,000.00	125,000.00