Letting Date: September 18, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140306
J/P No.: 30967(04) **Project No.:** SAP-211D(013) **Contract Time:**
County: CHEROKEE
Description: RESURFACE (ASPHALT) PARK ROAD (SEQUOYAH STATE PARK ROAD): BEGIN AT SH-51, EXTEND SOUTH. PROJECT LENGTH = 2.750 MILES

	VENDORNAME	PROPOSALITEMTO		
1	Paragon Contractors, LLC	387,618.40	97.07	100.00
2	GLOVER & ASSOCIATES, INC.	399,014.00	99.92	102.94

Letting Date: September 18, 2014, 10:30 A.M.
Call Order: 100 **Contract ID:** 140306

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0001**	**ROADWAY**		
0001	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	582.000	TON
	Engineer's Estimate		**18.00**	**10,476.00**
1	Paragon Contractors, LLC		52.25	30,409.50
2	GLOVER & ASSOCIATES, INC.		26.00	15,132.00
0002	407(B) 0250	TACK COAT	3,196.000	GAL
	Engineer's Estimate		**2.00**	**6,392.00**
1	Paragon Contractors, LLC		3.15	10,067.40
2	GLOVER & ASSOCIATES, INC.		2.00	6,392.00
0003	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	4,357.000	TON
	Engineer's Estimate		**80.00**	**348,560.00**
1	Paragon Contractors, LLC		69.50	302,811.50
2	GLOVER & ASSOCIATES, INC.		75.00	326,775.00
0004	411(I) 6310	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	163.000	TON
	Engineer's Estimate		**130.00**	**21,190.00**
1	Paragon Contractors, LLC		225.00	36,675.00
2	GLOVER & ASSOCIATES, INC.		155.00	25,265.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**TRAFFIC**		
0005	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
	Engineer's Estimate		**10,000.00**	**10,000.00**
1	Paragon Contractors, LLC		7,250.00	7,250.00
2	GLOVER & ASSOCIATES, INC.		25,000.00	25,000.00
0006	882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	90.000	SD
	Engineer's Estimate		**30.00**	**2,700.00**
1	Paragon Contractors, LLC		4.50	405.00
2	GLOVER & ASSOCIATES, INC.		5.00	450.00