Letting Date: November 20, 2014, 10:30 A.M.
Call Order: 420 **Contract ID:** 140368
J/P No.: 27720(04) **Project No.:** STP-152D(188)CI **Contract Time:**
County: NOBLE
Description: BRIDGE AND APPROACHES COUNTY ROAD (EW-35): OVER GRASSY CREEK, 0.1 MILES WEST AND 2.0 MILES SOUTH OF I-35/SH-15 JUNCTION. PROJECT LENGTH = 0.160 MILE

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	452,210.90		
1	K & R BUILDERS, INC.	491,306.83	108.65	100.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	499,984.80	110.56	101.77
3	B & B BRIDGE COMPANY, LLC	517,913.92	114.53	105.42
4	RRY SERVICES LLC	544,892.10	120.50	110.91
5	Reece Construction Co, Inc.	559,809.25	123.79	113.94

Letting Date: November 20, 2014, 10:30 A.M.
Call Order: 420 **Contract ID:** 140368

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM	
	Engineer's Estimate		**5,000.00**		**5,000.00**
1	K & R BUILDERS, INC.		7,000.00		7,000.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		3,600.00		3,600.00
3	B & B BRIDGE COMPANY, LLC		5,000.00		5,000.00
4	RRY SERVICES LLC		5,000.00		5,000.00
5	Reece Construction Co, Inc.		5,796.00		5,796.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	705.000	CY	
	Engineer's Estimate		**4.50**		**3,172.50**
1	K & R BUILDERS, INC.		10.38		7,317.90
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		7.15		5,040.75
3	B & B BRIDGE COMPANY, LLC		6.00		4,230.00
4	RRY SERVICES LLC		13.00		9,165.00
5	Reece Construction Co, Inc.		7.06		4,977.30
0003	202(D) 0184	UNCLASSIFIED BORROW	1,163.000	CY	
	Engineer's Estimate		**6.00**		**6,978.00**
1	K & R BUILDERS, INC.		12.00		13,956.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		13.50		15,700.50
3	B & B BRIDGE COMPANY, LLC		10.00		11,630.00
4	RRY SERVICES LLC		13.00		15,119.00
5	Reece Construction Co, Inc.		11.00		12,793.00
0004	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM	
	Engineer's Estimate		**4,500.00**		**4,500.00**
1	K & R BUILDERS, INC.		6,000.00		6,000.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		2,500.00		2,500.00
3	B & B BRIDGE COMPANY, LLC		5,000.00		5,000.00
4	RRY SERVICES LLC		6,000.00		6,000.00
5	Reece Construction Co, Inc.		4,830.00		4,830.00
0005	221(C) 2801	TEMPORARY SILT FENCE	1,360.000	LF	
	Engineer's Estimate		**2.00**		**2,720.00**
1	K & R BUILDERS, INC.		1.80		2,448.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		1.99		2,706.40
3	B & B BRIDGE COMPANY, LLC		1.99		2,706.40
4	RRY SERVICES LLC		2.00		2,720.00
5	Reece Construction Co, Inc.		1.34		1,822.40
0006	221(F) 0100	TEMPORARY SILT DIKE	140.000	LF	
	Engineer's Estimate		**8.00**		**1,120.00**
1	K & R BUILDERS, INC.		9.00		1,260.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		9.95		1,393.00
3	B & B BRIDGE COMPANY, LLC		9.95		1,393.00
4	RRY SERVICES LLC		10.00		1,400.00
5	Reece Construction Co, Inc.		7.89		1,104.60
0007	230(A) 2806	SOLID SLAB SODDING	2,900.000	SY	
	Engineer's Estimate		**2.00**		**5,800.00**
1	K & R BUILDERS, INC.		2.34		6,786.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		1.95		5,655.00
3	B & B BRIDGE COMPANY, LLC		1.95		5,655.00
4	RRY SERVICES LLC		2.00		5,800.00
5	Reece Construction Co, Inc.		2.19		6,351.00

Letting Date: November 20, 2014, 10:30 A.M.
Call Order: 420 **Contract ID:** 140368

Line #	Item Number / Item Description / Bidder	Unit Price	Quantity/Unit / Ext Amount
Section: 0001 ROADWAY			
0008	233(A) 2817 VEGETATIVE MULCHING		0.600 AC
	Engineer's Estimate	**500.00**	**300.00**
1	K & R BUILDERS, INC.	200.00	120.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	199.00	119.40
3	B & B BRIDGE COMPANY, LLC	199.00	119.40
4	RRY SERVICES LLC	215.00	129.00
5	Reece Construction Co, Inc.	1,200.00	720.00
0009	402(E) 0225 TRAFFIC BOUND SURFACE COURSE TYPE E		459.000 TON
	Engineer's Estimate	**20.00**	**9,180.00**
1	K & R BUILDERS, INC.	38.57	17,703.63
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	46.50	21,343.50
3	B & B BRIDGE COMPANY, LLC	35.00	16,065.00
4	RRY SERVICES LLC	37.00	16,983.00
5	Reece Construction Co, Inc.	38.00	17,442.00
0010	509(D) 0325 CLASS C CONCRETE		20.000 CY
	Engineer's Estimate	**270.00**	**5,400.00**
1	K & R BUILDERS, INC.	300.00	6,000.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	180.00	3,600.00
3	B & B BRIDGE COMPANY, LLC	350.00	7,000.00
4	RRY SERVICES LLC	200.00	4,000.00
5	Reece Construction Co, Inc.	333.00	6,660.00
0011	601(A) 0297 TYPE I PLAIN RIPRAP		150.000 TON
	Engineer's Estimate	**21.50**	**3,225.00**
1	K & R BUILDERS, INC.	52.18	7,827.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	50.00	7,500.00
3	B & B BRIDGE COMPANY, LLC	50.00	7,500.00
4	RRY SERVICES LLC	50.00	7,500.00
5	Reece Construction Co, Inc.	48.00	7,200.00
0012	623(F) 4446 GUARDRAIL ANCHOR UNIT (TYPE A)		4.000 EA
	Engineer's Estimate	**1,300.00**	**5,200.00**
1	K & R BUILDERS, INC.	1,560.00	6,240.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	1,300.00	5,200.00
3	B & B BRIDGE COMPANY, LLC	1,300.00	5,200.00
4	RRY SERVICES LLC	1,800.00	7,200.00
5	Reece Construction Co, Inc.	1,300.00	5,200.00
0013	623(F) 5686 GUARDRAIL ANCHOR UNIT (TYPE D-BF)		4.000 EA
	Engineer's Estimate	**1,500.00**	**6,000.00**
1	K & R BUILDERS, INC.	1,717.50	6,870.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	1,421.25	5,685.00
3	B & B BRIDGE COMPANY, LLC	1,431.25	5,725.00
4	RRY SERVICES LLC	1,800.00	7,200.00
5	Reece Construction Co, Inc.	1,431.25	5,725.00
0014	880(J) 8905 CONSTRUCTION TRAFFIC CONTROL		1.000 LSUM
	Engineer's Estimate	**7,400.00**	**7,400.00**
1	K & R BUILDERS, INC.	3,500.00	3,500.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	2,176.25	2,176.25
3	B & B BRIDGE COMPANY, LLC	2,176.12	2,176.12
4	RRY SERVICES LLC	2,100.00	2,100.00
5	Reece Construction Co, Inc.	1,950.00	1,950.00

Letting Date: November 20, 2014, 10:30 A.M.
Call Order: 420 **Contract ID:** 140368

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A'**			
0015	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	168.000 CY	
	Engineer's Estimate		**17.00**	**2,856.00**
1	K & R BUILDERS, INC.		11.00	1,848.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		35.00	5,880.00
3	B & B BRIDGE COMPANY, LLC		35.00	5,880.00
4	RRY SERVICES LLC		25.00	4,200.00
5	Reece Construction Co, Inc.		23.00	3,864.00
0016	501(F) 6352	GRANULAR BACKFILL	64.000 CY	
	Engineer's Estimate		**54.00**	**3,456.00**
1	K & R BUILDERS, INC.		77.00	4,928.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		75.00	4,800.00
3	B & B BRIDGE COMPANY, LLC		125.00	8,000.00
4	RRY SERVICES LLC		65.00	4,160.00
5	Reece Construction Co, Inc.		70.00	4,480.00
0017	504(D) 6239	CONCRETE RAIL (TR3)	238.400 LF	
	Engineer's Estimate		**71.00**	**16,926.40**
1	K & R BUILDERS, INC.		81.50	19,429.60
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		100.00	23,840.00
3	B & B BRIDGE COMPANY, LLC		85.00	20,264.00
4	RRY SERVICES LLC		75.00	17,880.00
5	Reece Construction Co, Inc.		134.00	31,945.60
0018	506(A) 1322	STRUCTURAL STEEL	73,960.000 LB	
	Engineer's Estimate		**2.00**	**147,920.00**
1	K & R BUILDERS, INC.		1.88	139,044.80
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		1.80	133,128.00
3	B & B BRIDGE COMPANY, LLC		2.20	162,712.00
4	RRY SERVICES LLC		2.36	174,545.60
5	Reece Construction Co, Inc.		2.00	147,920.00
0019	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	3.000 EA	
	Engineer's Estimate		**860.00**	**2,580.00**
1	K & R BUILDERS, INC.		1,100.00	3,300.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		930.00	2,790.00
3	B & B BRIDGE COMPANY, LLC		1,800.00	5,400.00
4	RRY SERVICES LLC		1,300.00	3,900.00
5	Reece Construction Co, Inc.		1,152.00	3,456.00
0020	507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	3.000 EA	
	Engineer's Estimate		**1,075.00**	**3,225.00**
1	K & R BUILDERS, INC.		1,100.00	3,300.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		1,200.00	3,600.00
3	B & B BRIDGE COMPANY, LLC		1,800.00	5,400.00
4	RRY SERVICES LLC		1,300.00	3,900.00
5	Reece Construction Co, Inc.		1,152.00	3,456.00

Letting Date: November 20, 2014, 10:30 A.M.
Call Order: 420 **Contract ID:** 140368

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A'					
0021	509(A) 1326	CLASS AA CONCRETE	67.700	CY	
	Engineer's Estimate		**500.00**		**33,850.00**
1	K & R BUILDERS, INC.		735.00		49,759.50
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		870.00		58,899.00
3	B & B BRIDGE COMPANY, LLC		620.00		41,974.00
4	RRY SERVICES LLC		625.00		42,312.50
5	Reece Construction Co, Inc.		1,028.00		69,595.60
0022	509(B) 1328	CLASS A CONCRETE	62.800	CY	
	Engineer's Estimate		**500.00**		**31,400.00**
1	K & R BUILDERS, INC.		685.00		43,018.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		735.00		46,158.00
3	B & B BRIDGE COMPANY, LLC		620.00		38,936.00
4	RRY SERVICES LLC		675.00		42,390.00
5	Reece Construction Co, Inc.		865.00		54,322.00
0023	511(A) 1332	REINFORCING STEEL	24,940.000	LB	
	Engineer's Estimate		**1.00**		**24,940.00**
1	K & R BUILDERS, INC.		0.98		24,441.20
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		1.00		24,940.00
3	B & B BRIDGE COMPANY, LLC		1.00		24,940.00
4	RRY SERVICES LLC		1.00		24,940.00
5	Reece Construction Co, Inc.		0.80		19,952.00
0024	514(A) 6010	PILES, FURNISHED (HP 10X42)	104.000	LF	
	Engineer's Estimate		**30.00**		**3,120.00**
1	K & R BUILDERS, INC.		37.10		3,858.40
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		45.00		4,680.00
3	B & B BRIDGE COMPANY, LLC		37.00		3,848.00
4	RRY SERVICES LLC		47.00		4,888.00
5	Reece Construction Co, Inc.		53.00		5,512.00
0025	514(A) 6011	PILES, FURNISHED (HP 12X53)	230.000	LF	
	Engineer's Estimate		**34.50**		**7,935.00**
1	K & R BUILDERS, INC.		44.10		10,143.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		58.00		13,340.00
3	B & B BRIDGE COMPANY, LLC		46.00		10,580.00
4	RRY SERVICES LLC		58.00		13,340.00
5	Reece Construction Co, Inc.		68.00		15,640.00
0026	514(B) 6292	PILES, DRIVEN (HP 10X42)	104.000	LF	
	Engineer's Estimate		**16.00**		**1,664.00**
1	K & R BUILDERS, INC.		15.90		1,653.60
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		30.00		3,120.00
3	B & B BRIDGE COMPANY, LLC		25.00		2,600.00
4	RRY SERVICES LLC		10.00		1,040.00
5	Reece Construction Co, Inc.		21.00		2,184.00
0027	514(B) 6294	PILES, DRIVEN (HP 12X53)	230.000	LF	
	Engineer's Estimate		**17.00**		**3,910.00**
1	K & R BUILDERS, INC.		18.90		4,347.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		30.00		6,900.00
3	B & B BRIDGE COMPANY, LLC		23.00		5,290.00
4	RRY SERVICES LLC		10.00		2,300.00
5	Reece Construction Co, Inc.		19.00		4,370.00

Letting Date: November 20, 2014, 10:30 A.M.
Call Order: 420 **Contract ID:** 140368

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A'**			
0028	514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000 EA	
	Engineer's Estimate		**400.00**	**400.00**
1	K & R BUILDERS, INC.		400.00	400.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		400.00	400.00
3	B & B BRIDGE COMPANY, LLC		400.00	400.00
4	RRY SERVICES LLC		400.00	400.00
5	Reece Construction Co, Inc.		400.00	400.00
0029	601(B) 1353	TYPE I-A PLAIN RIPRAP	570.000 TON	
	Engineer's Estimate		**37.50**	**21,375.00**
1	K & R BUILDERS, INC.		45.68	26,037.60
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		48.00	27,360.00
3	B & B BRIDGE COMPANY, LLC		40.00	22,800.00
4	RRY SERVICES LLC		51.00	29,070.00
5	Reece Construction Co, Inc.		45.00	25,650.00
0030	601(C) 1355	TYPE I-A FILTER BLANKET	280.000 TON	
	Engineer's Estimate		**33.00**	**9,240.00**
1	K & R BUILDERS, INC.		37.57	10,519.60
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		43.50	12,180.00
3	B & B BRIDGE COMPANY, LLC		35.00	9,800.00
4	RRY SERVICES LLC		42.00	11,760.00
5	Reece Construction Co, Inc.		36.00	10,080.00
0031	613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	52.000 LF	
	Engineer's Estimate		**28.00**	**1,456.00**
1	K & R BUILDERS, INC.		35.00	1,820.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		25.00	1,300.00
3	B & B BRIDGE COMPANY, LLC		35.00	1,820.00
4	RRY SERVICES LLC		25.00	1,300.00
5	Reece Construction Co, Inc.		15.00	780.00
0032	613(I) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	22.000 LF	
	Engineer's Estimate		**21.00**	**462.00**
1	K & R BUILDERS, INC.		65.00	1,430.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		25.00	550.00
3	B & B BRIDGE COMPANY, LLC		35.00	770.00
4	RRY SERVICES LLC		25.00	550.00
5	Reece Construction Co, Inc.		15.00	330.00
0033	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM	
	Engineer's Estimate		**8,000.00**	**8,000.00**
1	K & R BUILDERS, INC.		5,000.00	5,000.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES		3,000.00	3,000.00
3	B & B BRIDGE COMPANY, LLC		7,500.00	7,500.00
4	RRY SERVICES LLC		12,500.00	12,500.00
5	Reece Construction Co, Inc.		8,630.75	8,630.75

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003	**STAKING**			

Letting Date: November 20, 2014, 10:30 A.M.
Call Order: 420 **Contract ID:** 140368

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003	**STAKING**		
0034	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**6,500.00**	**6,500.00**
1	K & R BUILDERS, INC.	6,500.00	6,500.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	5,400.00	5,400.00
3	B & B BRIDGE COMPANY, LLC	5,700.00	5,700.00
4	RRY SERVICES LLC	5,500.00	5,500.00
5	Reece Construction Co, Inc.	5,470.00	5,470.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004	**CONSTRUCTION**		
0035	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	K & R BUILDERS, INC.	3,500.00	3,500.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	1,500.00	1,500.00
3	B & B BRIDGE COMPANY, LLC	3,000.00	3,000.00
4	RRY SERVICES LLC	2,700.00	2,700.00
5	Reece Construction Co, Inc.	2,500.00	2,500.00
0036	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**50,000.00**	**50,000.00**
1	K & R BUILDERS, INC.	34,000.00	34,000.00
2	WILDCAT CONSTRUCTION CO., INC. & SUBSIDIARIES	34,000.00	34,000.00
3	B & B BRIDGE COMPANY, LLC	50,900.00	50,900.00
4	RRY SERVICES LLC	51,000.00	51,000.00
5	Reece Construction Co, Inc.	56,700.00	56,700.00