Letting Date: April 16, 2015, 10:30 A.M.
Call Order: 250 **Contract ID:** 150143
J/P No.: 29963(04) **Project No.:** CIRB-245C(031)RB **Contract Time:**
County: MCCURTAIN
Description: RESURFACE (ASPHALT) COUNTY ROAD (NS-472/GOODWATER ROAD): ON NS-472, FROM SH-3 EXTEND NORTH, THEN EAST ON GOODWATER ROAD. PROJECT LENGTH = 8.000 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	2,263,170.62		
1	THE CUMMINS CONSTRUCTION CO., INC.	3,116,984.71	137.73	100.00

Letting Date: April 16, 2015, 10:30 A.M.
Call Order: 250 **Contract ID:** 150143

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0001	202(H) 0185	EARTHWORK	1.000	LSUM
	Engineer's Estimate		**20,000.00**	**20,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		28,000.00	28,000.00
0002	311(D) 0154	PROCESSING EXISTING BASE & SURFACE, METHOD D	13,728.000	LF
	Engineer's Estimate		**7.00**	**96,096.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		3.75	51,480.00
0003	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	25,080.000	TON
	Engineer's Estimate		**22.00**	**551,760.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		31.65	793,782.00
0004	407(D) 0401	(SP) NT TACK MATERIAL	9,150.000	GAL
	Engineer's Estimate		**3.00**	**27,450.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		3.55	32,482.50
0005	408 5774	PRIME COAT	3,930.000	GAL
	Engineer's Estimate		**4.80**	**18,864.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		5.30	20,829.00
0006	411(B) 5940	SUPERPAVE, TYPE S3(PG 70-28 OK)	3,090.000	TON
	Engineer's Estimate		**75.00**	**231,750.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		97.30	300,657.00
0007	411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	13,810.000	TON
	Engineer's Estimate		**74.00**	**1,021,940.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		102.65	1,417,596.50
0008	509(A) 0319	CLASS AA CONCRETE	21.800	CY
	Engineer's Estimate		**370.00**	**8,066.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		952.00	20,753.60
0009	509(D) 0325	CLASS C CONCRETE	16.000	CY
	Engineer's Estimate		**337.00**	**5,392.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		1,345.00	21,520.00
0010	511(A) 0332	REINFORCING STEEL	4,690.700	LB
	Engineer's Estimate		**1.25**	**5,863.38**
1	THE CUMMINS CONSTRUCTION CO., INC.		1.70	7,974.19
0011	601(B) 0536	TYPE I-A PLAIN RIPRAP	300.000	TON
	Engineer's Estimate		**39.00**	**11,700.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		61.60	18,480.00
0012	613(C) 5221	35" X 24" PRECOATED CORR. STL. PIPE ARCH	168.000	LF
	Engineer's Estimate		**75.00**	**12,600.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		196.00	32,928.00
0013	613(C) 5285	57" X 38" PRECOATED CORR. STL. PIPE ARCH	24.000	LF
	Engineer's Estimate		**85.00**	**2,040.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		241.00	5,784.00
0014	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	225.000	LF
	Engineer's Estimate		**20.00**	**4,500.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		19.60	4,410.00

Letting Date: April 16, 2015, 10:30 A.M.
Call Order: 250 **Contract ID:** 150143

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0001**	**ROADWAY**	
0015	623(G) 8571	GUARDRAIL END TREATMENT (GET)	8.000 EA
	Engineer's Estimate	**2,000.00**	**16,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.	2,464.00	19,712.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0002**	**BRIDGE 'A'**	
0016	509(A) 1326	CLASS AA CONCRETE	38.700 CY
	Engineer's Estimate	**700.00**	**27,090.00**
1	THE CUMMINS CONSTRUCTION CO., INC.	952.00	36,842.40
0017	511(A) 1332	REINFORCING STEEL	6,672.000 LB
	Engineer's Estimate	**1.00**	**6,672.00**
1	THE CUMMINS CONSTRUCTION CO., INC.	1.25	8,340.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0003**	**BRIDGE 'B'**	
0018	509(A) 1326	CLASS AA CONCRETE	51.800 CY
	Engineer's Estimate	**700.00**	**36,260.00**
1	THE CUMMINS CONSTRUCTION CO., INC.	952.00	49,313.60
0019	511(A) 1332	REINFORCING STEEL	8,899.500 LB
	Engineer's Estimate	**1.00**	**8,899.50**
1	THE CUMMINS CONSTRUCTION CO., INC.	1.25	11,124.38

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0004**	**BRIDGE 'C'**	
0020	509(A) 1326	CLASS AA CONCRETE	51.800 CY
	Engineer's Estimate	**700.00**	**36,260.00**
1	THE CUMMINS CONSTRUCTION CO., INC.	952.00	49,313.60
0021	511(A) 1332	REINFORCING STEEL	8,899.500 LB
	Engineer's Estimate	**1.00**	**8,899.50**
1	THE CUMMINS CONSTRUCTION CO., INC.	1.25	11,124.38
0022	619(B) 2500	REMOVAL OF BRIDGE ITEMS	1.000 LSUM
	Engineer's Estimate	**20,000.00**	**20,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.	3,920.00	3,920.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0005**	**TRAFFIC**	
0023	850(A) 8110	SHEET ALUMINUM SIGNS	256.720 SF
	Engineer's Estimate	**15.00**	**3,850.80**
1	THE CUMMINS CONSTRUCTION CO., INC.	20.20	5,185.74

Letting Date: April 16, 2015, 10:30 A.M.
Call Order: 250 **Contract ID:** 150143

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0005**	**TRAFFIC**		
0024	851(C) 8324	2" SQUARE TUBE POST	337.580 LF	
	Engineer's Estimate		**8.00**	**2,700.64**
1	THE CUMMINS CONSTRUCTION CO., INC.		9.00	3,038.22
0025	854(A) 8800	TRAFFIC STRIPE(PAINT)(4" WIDE)	168,960.000 LF	
	Engineer's Estimate		**0.08**	**13,516.80**
1	THE CUMMINS CONSTRUCTION CO., INC.		0.16	27,033.60
0026	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM	
	Engineer's Estimate		**10,000.00**	**10,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		11,760.00	11,760.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0006**	**STAKING**		
0027	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM	
	Engineer's Estimate		**15,000.00**	**15,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		5,600.00	5,600.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0007**	**CONSTRUCTION**		
0028	641 1399	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**40,000.00**	**40,000.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		118,000.00	118,000.00