Letting Date: September 17, 2015, 10:30 A.M.
Call Order: 010 **Contract ID:** 150281
J/P No.: 31669(04) **Project No.:** STP-205F(052)3B **Contract Time:**
County: BECKHAM, KIOWA
Description: JOINT SEAL/REPAIR US-62/RANDALL STREET: AT MULTIPLE LOCATIONS IN DIVISION V.

	VENDORNAME	PROPOSALITEMTO		
1	LOGOS CONSTRUCTION CO., LLC	275,528.88	97.73	100.00
	Engineer's Estimate	281,939.15		
2	PBX Corporation	294,917.20	104.60	107.04
3	Bettis Asphalt and Construction, Inc.	319,205.00	113.22	115.85

Letting Date: September 17, 2015, 10:30 A.M.
Call Order: 010 **Contract ID:** 150281

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**BRIDGE - NBI NO. 17556**			
0001	504(C) 1450	EXPANSION DEVICE	68.000 LF	
	Engineer's Estimate		**165.00**	**11,220.00**
1	LOGOS CONSTRUCTION CO., LLC		112.00	7,616.00
2	PBX Corporation		100.00	6,800.00
3	Bettis Asphalt and Construction, Inc.		162.00	11,016.00
0002	504(G) 6390	RAPID CURE JOINT SEALANT	102.000 LF	
	Engineer's Estimate		**35.00**	**3,570.00**
1	LOGOS CONSTRUCTION CO., LLC		28.00	2,856.00
2	PBX Corporation		25.00	2,550.00
3	Bettis Asphalt and Construction, Inc.		44.00	4,488.00
0003	505(C) 6075	MULTIPLE LAYER POLYMER CONCRETE OVERLAY	920.000 SY	
	Engineer's Estimate		**40.00**	**36,800.00**
1	LOGOS CONSTRUCTION CO., LLC		60.00	55,200.00
2	PBX Corporation		45.00	41,400.00
3	Bettis Asphalt and Construction, Inc.		46.00	42,320.00
0004	513(B) 6019	CLASS B BRIDGE DECK REPAIR	30.000 SY	
	Engineer's Estimate		**350.00**	**10,500.00**
1	LOGOS CONSTRUCTION CO., LLC		260.00	7,800.00
2	PBX Corporation		350.00	10,500.00
3	Bettis Asphalt and Construction, Inc.		300.00	9,000.00
0005	520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	20.000 LF	
	Engineer's Estimate		**50.00**	**1,000.00**
1	LOGOS CONSTRUCTION CO., LLC		35.00	700.00
2	PBX Corporation		35.00	700.00
3	Bettis Asphalt and Construction, Inc.		42.00	840.00
0006	520(C) 6060	EPOXY RESIN, ABOVE WATER	1.000 GAL	
	Engineer's Estimate		**150.00**	**150.00**
1	LOGOS CONSTRUCTION CO., LLC		50.00	50.00
2	PBX Corporation		100.00	100.00
3	Bettis Asphalt and Construction, Inc.		150.00	150.00
0007	521(A) 6210	PNEUMATICALLY PLACED MORTAR	5.000 SY	
	Engineer's Estimate		**900.00**	**4,500.00**
1	LOGOS CONSTRUCTION CO., LLC		850.00	4,250.00
2	PBX Corporation		675.00	3,375.00
3	Bettis Asphalt and Construction, Inc.		1,200.00	6,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE B- NBI NO. 18074**			
0008	502 6116	(PL)FALSEWORK JACKING	1.000 LSUM	
	Engineer's Estimate		**30,000.00**	**30,000.00**
1	LOGOS CONSTRUCTION CO., LLC		16,000.00	16,000.00
2	PBX Corporation		24,000.00	24,000.00
3	Bettis Asphalt and Construction, Inc.		34,010.00	34,010.00

Letting Date: September 17, 2015, 10:30 A.M.
Call Order: 010 **Contract ID:** 150281

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE B- NBI NO. 18074**			
0009	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	10.000 EA	
	Engineer's Estimate		**2,500.00**	**25,000.00**
1	LOGOS CONSTRUCTION CO., LLC		2,000.00	20,000.00
2	PBX Corporation		2,500.00	25,000.00
3	Bettis Asphalt and Construction, Inc.		2,350.00	23,500.00
0010	513(B) 6019	CLASS B BRIDGE DECK REPAIR	20.000 SY	
	Engineer's Estimate		**350.00**	**7,000.00**
1	LOGOS CONSTRUCTION CO., LLC		260.00	5,200.00
2	PBX Corporation		350.00	7,000.00
3	Bettis Asphalt and Construction, Inc.		300.00	6,000.00
0011	520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	60.000 LF	
	Engineer's Estimate		**50.00**	**3,000.00**
1	LOGOS CONSTRUCTION CO., LLC		35.00	2,100.00
2	PBX Corporation		35.00	2,100.00
3	Bettis Asphalt and Construction, Inc.		42.00	2,520.00
0012	520(C) 6060	EPOXY RESIN, ABOVE WATER	2.000 GAL	
	Engineer's Estimate		**150.00**	**300.00**
1	LOGOS CONSTRUCTION CO., LLC		50.00	100.00
2	PBX Corporation		100.00	200.00
3	Bettis Asphalt and Construction, Inc.		150.00	300.00
0013	521(A) 6210	PNEUMATICALLY PLACED MORTAR	20.000 SY	
	Engineer's Estimate		**900.00**	**18,000.00**
1	LOGOS CONSTRUCTION CO., LLC		530.00	10,600.00
2	PBX Corporation		675.00	13,500.00
3	Bettis Asphalt and Construction, Inc.		800.00	16,000.00
0014	540 4515	(PL)REPAIR BRIDGE ITEM (TYPE A)	2.000 EA	
	Engineer's Estimate		**37,000.00**	**74,000.00**
1	LOGOS CONSTRUCTION CO., LLC		38,556.00	77,112.00
2	PBX Corporation		36,000.00	72,000.00
3	Bettis Asphalt and Construction, Inc.		31,810.00	63,620.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003	**TRAFFIC CONTROL**			
0015	871(B) 8705	(SP)CONST.ZONE IMPACT ATTEN.	35.000 SD	
	Engineer's Estimate		**16.00**	**560.00**
1	LOGOS CONSTRUCTION CO., LLC		60.00	2,100.00
2	PBX Corporation		66.00	2,310.00
3	Bettis Asphalt and Construction, Inc.		55.00	1,925.00
0016	876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	35.000 SD	
	Engineer's Estimate		**19.40**	**679.00**
1	LOGOS CONSTRUCTION CO., LLC		60.00	2,100.00
2	PBX Corporation		66.00	2,310.00
3	Bettis Asphalt and Construction, Inc.		55.00	1,925.00

Letting Date: September 17, 2015, 10:30 A.M.
Call Order: 010 **Contract ID:** 150281

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0003	**TRAFFIC CONTROL**				
0017	877(B) 8484	DELIVER PORTABLE LONGITUDINAL BARRIER	388.000	LF	
	Engineer's Estimate		**20.65**		**8,012.20**
1	LOGOS CONSTRUCTION CO., LLC		31.76		12,322.88
2	PBX Corporation		31.00		12,028.00
3	Bettis Asphalt and Construction, Inc.		25.00		9,700.00
0018	877(C) 8486	RELOCATION OF PORTABLE LONGITUDINAL BARRIER	2,716.000	LF	
	Engineer's Estimate		**3.75**		**10,185.00**
1	LOGOS CONSTRUCTION CO., LLC		0.40		1,086.40
2	PBX Corporation		1.65		4,481.40
3	Bettis Asphalt and Construction, Inc.		0.50		1,358.00
0019	880(A) 8812	ARROW DISPLAY(TYPE C)	35.000	SD	
	Engineer's Estimate		**6.85**		**239.75**
1	LOGOS CONSTRUCTION CO., LLC		11.00		385.00
2	PBX Corporation		11.00		385.00
3	Bettis Asphalt and Construction, Inc.		10.00		350.00
0020	880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	840.000	SD	
	Engineer's Estimate		**0.30**		**252.00**
1	LOGOS CONSTRUCTION CO., LLC		0.17		142.80
2	PBX Corporation		0.16		134.40
3	Bettis Asphalt and Construction, Inc.		0.15		126.00
0021	880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	980.000	SD	
	Engineer's Estimate		**0.60**		**588.00**
1	LOGOS CONSTRUCTION CO., LLC		0.17		166.60
2	PBX Corporation		0.16		156.80
3	Bettis Asphalt and Construction, Inc.		0.15		147.00
0022	880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	770.000	SD	
	Engineer's Estimate		**1.70**		**1,309.00**
1	LOGOS CONSTRUCTION CO., LLC		11.00		8,470.00
2	PBX Corporation		11.00		8,470.00
3	Bettis Asphalt and Construction, Inc.		10.00		7,700.00
0023	880(C) 8842	CONSTRUCTION BARRICADES(TYPE III)	420.000	SD	
	Engineer's Estimate		**0.90**		**378.00**
1	LOGOS CONSTRUCTION CO., LLC		0.06		25.20
2	PBX Corporation		0.05		21.00
3	Bettis Asphalt and Construction, Inc.		0.05		21.00
0024	880(C) 8848	WING BARRICADES	280.000	SD	
	Engineer's Estimate		**1.05**		**294.00**
1	LOGOS CONSTRUCTION CO., LLC		0.06		16.80
2	PBX Corporation		0.05		14.00
3	Bettis Asphalt and Construction, Inc.		0.05		14.00
0025	880(E) 8860	WARNING LIGHTS(TYPE A)	1,400.000	SD	
	Engineer's Estimate		**0.25**		**350.00**
1	LOGOS CONSTRUCTION CO., LLC		0.28		392.00
2	PBX Corporation		0.27		378.00
3	Bettis Asphalt and Construction, Inc.		0.25		350.00

Letting Date: September 17, 2015, 10:30 A.M.
Call Order: 010 **Contract ID:** 150281

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003	**TRAFFIC CONTROL**			
0026	880(F) 8878	DRUMS	1,820.000 SD	
	Engineer's Estimate		**0.55**	**1,001.00**
1	LOGOS CONSTRUCTION CO., LLC		0.28	509.60
2	PBX Corporation		0.27	491.40
3	Bettis Asphalt and Construction, Inc.		0.25	455.00
0027	880(G) 8890	CHANNELIZER CONES	2,800.000 SD	
	Engineer's Estimate		**0.35**	**980.00**
1	LOGOS CONSTRUCTION CO., LLC		1.10	3,080.00
2	PBX Corporation		1.10	3,080.00
3	Bettis Asphalt and Construction, Inc.		1.00	2,800.00
0028	880(I) 8902	FLAGGER	35.000 SD	
	Engineer's Estimate		**130.00**	**4,550.00**
1	LOGOS CONSTRUCTION CO., LLC		20.00	700.00
2	PBX Corporation		100.00	3,500.00
3	Bettis Asphalt and Construction, Inc.		150.00	5,250.00
0029	882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	140.000 SD	
	Engineer's Estimate		**15.00**	**2,100.00**
1	LOGOS CONSTRUCTION CO., LLC		5.50	770.00
2	PBX Corporation		7.70	1,078.00
3	Bettis Asphalt and Construction, Inc.		5.00	700.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0004	**SIGNING & STRIPING**			
0030	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	936.000 LF	
	Engineer's Estimate		**0.45**	**421.20**
1	LOGOS CONSTRUCTION CO., LLC		6.60	6,177.60
2	PBX Corporation		7.70	7,207.20
3	Bettis Asphalt and Construction, Inc.		6.00	5,616.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0005	**CONSTRUCTION**			
0031	641 1399	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**25,000.00**	**25,000.00**
1	LOGOS CONSTRUCTION CO., LLC		27,500.00	27,500.00
2	PBX Corporation		39,647.00	39,647.00
3	Bettis Asphalt and Construction, Inc.		61,004.00	61,004.00