Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 190 **Contract ID:** 160024
J/P No.: 30298(04) **Project No.:** STP-225C(050)CI **Contract Time:**
County: GARVIN
Description: RESURFACE (ASPHALT) COUNTY ROAD (INDIAN MERIDIAN RD/NS-323): FROM SH-29, EXTEND NORTH NEAR PAULS VALLEY. PROJECT LENGTH = 5.011 MILES

	VENDORNAME	PROPOSALITEMTO		
1	Silver Star Construction Company, Inc.	1,157,300.00	30.07	100.00
2	MARKWELL PAVING COMPANY, INC.	1,222,437.89	31.76	105.63
3	HASKELL LEMON CONSTRUCTION CO.	1,664,439.20	43.25	143.82

Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 190 **Contract ID:** 160024

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	202(D) 0184	UNCLASSIFIED BORROW	1,610.000	CY	
	Engineer's Estimate		**1,610.00**		**2,592,100.00**
1	Silver Star Construction Company, Inc.		0.50		805.00
2	MARKWELL PAVING COMPANY, INC.		20.00		32,200.00
3	HASKELL LEMON CONSTRUCTION CO.		35.00		56,350.00
0002	221(C) 2801	TEMPORARY SILT FENCE	5,000.000	LF	
	Engineer's Estimate		**1.25**		**6,250.00**
1	Silver Star Construction Company, Inc.		1.30		6,500.00
2	MARKWELL PAVING COMPANY, INC.		1.30		6,500.00
3	HASKELL LEMON CONSTRUCTION CO.		1.30		6,500.00
0003	221(F) 0100	TEMPORARY SILT DIKE	300.000	LF	
	Engineer's Estimate		**5.50**		**1,650.00**
1	Silver Star Construction Company, Inc.		9.90		2,970.00
2	MARKWELL PAVING COMPANY, INC.		10.65		3,195.00
3	HASKELL LEMON CONSTRUCTION CO.		9.95		2,985.00
0004	230(A) 2806	SOLID SLAB SODDING	17,641.000	SY	
	Engineer's Estimate		**1.50**		**26,461.50**
1	Silver Star Construction Company, Inc.		1.25		22,051.25
2	MARKWELL PAVING COMPANY, INC.		1.29		22,756.89
3	HASKELL LEMON CONSTRUCTION CO.		1.30		22,933.30
0005	303(A) 2100	AGGREGATE BASE TYPE A	1,012.000	CY	
	Engineer's Estimate		**45.00**		**45,540.00**
1	Silver Star Construction Company, Inc.		58.40		59,100.80
2	MARKWELL PAVING COMPANY, INC.		40.00		40,480.00
3	HASKELL LEMON CONSTRUCTION CO.		57.55		58,240.60
0006	307(K) 4300	STABILIZED SUBGRADE	12,427.000	SY	
	Engineer's Estimate		**7.00**		**86,989.00**
1	Silver Star Construction Company, Inc.		4.40		54,678.80
2	MARKWELL PAVING COMPANY, INC.		5.00		62,135.00
3	HASKELL LEMON CONSTRUCTION CO.		7.50		93,202.50
0007	325 5271	SEPARATOR FABRIC	6,067.000	SY	
	Engineer's Estimate		**1.00**		**6,067.00**
1	Silver Star Construction Company, Inc.		0.60		3,640.20
2	MARKWELL PAVING COMPANY, INC.		1.00		6,067.00
3	HASKELL LEMON CONSTRUCTION CO.		2.85		17,290.95
0008	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	760.000	TON	
	Engineer's Estimate		**30.00**		**22,800.00**
1	Silver Star Construction Company, Inc.		40.00		30,400.00
2	MARKWELL PAVING COMPANY, INC.		30.00		22,800.00
3	HASKELL LEMON CONSTRUCTION CO.		63.50		48,260.00
0009	408 5774	PRIME COAT	5,867.000	GAL	
	Engineer's Estimate		**5.00**		**29,335.00**
1	Silver Star Construction Company, Inc.		3.00		17,601.00
2	MARKWELL PAVING COMPANY, INC.		5.00		29,335.00
3	HASKELL LEMON CONSTRUCTION CO.		7.00		41,069.00

Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 190 **Contract ID:** 160024

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0010	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	2,603.000	TON	
	Engineer's Estimate		**75.00**		**195,225.00**
1	Silver Star Construction Company, Inc.		55.00		143,165.00
2	MARKWELL PAVING COMPANY, INC.		67.00		174,401.00
3	HASKELL LEMON CONSTRUCTION CO.		72.00		187,416.00
0011	411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	801.000	TON	
	Engineer's Estimate		**90.00**		**72,090.00**
1	Silver Star Construction Company, Inc.		73.00		58,473.00
2	MARKWELL PAVING COMPANY, INC.		77.00		61,677.00
3	HASKELL LEMON CONSTRUCTION CO.		107.50		86,107.50
0012	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	5,808.000	TON	
	Engineer's Estimate		**80.00**		**464,640.00**
1	Silver Star Construction Company, Inc.		64.00		371,712.00
2	MARKWELL PAVING COMPANY, INC.		73.00		423,984.00
3	HASKELL LEMON CONSTRUCTION CO.		85.50		496,584.00
0013	411(H) 6210	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,246.000	TON	
	Engineer's Estimate		**100.00**		**124,600.00**
1	Silver Star Construction Company, Inc.		93.00		115,878.00
2	MARKWELL PAVING COMPANY, INC.		125.00		155,750.00
3	HASKELL LEMON CONSTRUCTION CO.		165.00		205,590.00
0014	412 5267	COLD MILLING PAVEMENT	1,875.000	SY	
	Engineer's Estimate		**7.00**		**13,125.00**
1	Silver Star Construction Company, Inc.		10.00		18,750.00
2	MARKWELL PAVING COMPANY, INC.		4.00		7,500.00
3	HASKELL LEMON CONSTRUCTION CO.		7.10		13,312.50
0015	613(A) 4497	36" X 22" R.C.PIPE ARCH CLASS A-III	228.000	LF	
	Engineer's Estimate		**95.32**		**21,731.88**
1	Silver Star Construction Company, Inc.		136.00		31,008.00
2	MARKWELL PAVING COMPANY, INC.		143.00		32,604.00
3	HASKELL LEMON CONSTRUCTION CO.		127.00		28,956.00
0016	613(M) 7187	TYPE B4 CULVERT END TREATMENT	8.000	EA	
	Engineer's Estimate		**1,099.06**		**8,792.48**
1	Silver Star Construction Company, Inc.		1,890.00		15,120.00
2	MARKWELL PAVING COMPANY, INC.		1,250.00		10,000.00
3	HASKELL LEMON CONSTRUCTION CO.		1,280.00		10,240.00
0017	619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	11,391.000	SY	
	Engineer's Estimate		**3.00**		**34,173.00**
1	Silver Star Construction Company, Inc.		7.30		83,154.30
2	MARKWELL PAVING COMPANY, INC.		3.00		34,173.00
3	HASKELL LEMON CONSTRUCTION CO.		5.35		60,941.85
0018	623(G) 8590	GUARDRAIL END TREATMENT (31")	6.000	EA	
	Engineer's Estimate		**2,000.00**		**12,000.00**
1	Silver Star Construction Company, Inc.		2,600.00		15,600.00
2	MARKWELL PAVING COMPANY, INC.		2,695.00		16,170.00
3	HASKELL LEMON CONSTRUCTION CO.		4,650.00		27,900.00

Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 190 **Contract ID:** 160024

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0001**	**ROADWAY**		
0019	854(A) 8800	TRAFFIC STRIPE(PAINT)(4" WIDE)	105,600.000 LF	
	Engineer's Estimate		**0.14**	**14,784.00**
1	Silver Star Construction Company, Inc.		0.10	10,560.00
2	MARKWELL PAVING COMPANY, INC.		0.10	10,560.00
3	HASKELL LEMON CONSTRUCTION CO.		0.10	10,560.00
0020	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	Silver Star Construction Company, Inc.		34,632.65	34,632.65
2	MARKWELL PAVING COMPANY, INC.		4,950.00	4,950.00
3	HASKELL LEMON CONSTRUCTION CO.		10,000.00	10,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**CONSTRUCTION**		
0021	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM	
	Engineer's Estimate		**2,500.00**	**2,500.00**
1	Silver Star Construction Company, Inc.		3,500.00	3,500.00
2	MARKWELL PAVING COMPANY, INC.		5,200.00	5,200.00
3	HASKELL LEMON CONSTRUCTION CO.		5,000.00	5,000.00
0022	641 1552	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**62,687.74**	**62,687.74**
1	Silver Star Construction Company, Inc.		58,000.00	58,000.00
2	MARKWELL PAVING COMPANY, INC.		60,000.00	60,000.00
3	HASKELL LEMON CONSTRUCTION CO.		175,000.00	175,000.00