Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 230 **Contract ID:** 160089
J/P No.: 29347(04) **Project No.:** STP-230C(020)CI **Contract Time:**
County: HARPER
Description: GRADE, DRAIN, AND SURFACE COUNTY ROAD (NS-183): FROM 4.0 MILES NORTH OF US-64, EXTEND NORTH NEAR BUFFALO. PROJECT LENGTH = 3.057 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	2,644,142.13		
1	J & R SAND COMPANY, INC.	2,847,700.07	107.70	100.00
2	Venture Corporation dba VCO Paving	3,020,812.92	114.25	106.08
3	THE CUMMINS CONSTRUCTION CO., INC.	3,173,890.15	120.03	111.45

Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 230 **Contract ID:** 160089

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM	
	Engineer's Estimate		**25,000.00**		**25,000.00**
1	J & R SAND COMPANY, INC.		40,000.00		40,000.00
2	Venture Corporation dba VCO Paving		30,000.00		30,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		25,000.00		25,000.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	19,129.070	CY	
	Engineer's Estimate		**7.50**		**143,468.03**
1	J & R SAND COMPANY, INC.		4.25		81,298.55
2	Venture Corporation dba VCO Paving		8.00		153,032.56
3	THE CUMMINS CONSTRUCTION CO., INC.		7.00		133,903.49
0003	202(D) 0184	UNCLASSIFIED BORROW	12,175.490	CY	
	Engineer's Estimate		**9.02**		**109,822.92**
1	J & R SAND COMPANY, INC.		9.65		117,493.48
2	Venture Corporation dba VCO Paving		13.00		158,281.37
3	THE CUMMINS CONSTRUCTION CO., INC.		12.00		146,105.88
0004	221(C) 2801	TEMPORARY SILT FENCE	3,000.000	LF	
	Engineer's Estimate		**2.00**		**6,000.00**
1	J & R SAND COMPANY, INC.		1.22		3,660.00
2	Venture Corporation dba VCO Paving		2.00		6,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		1.65		4,950.00
0005	221(F) 0100	TEMPORARY SILT DIKE	560.000	LF	
	Engineer's Estimate		**8.70**		**4,872.00**
1	J & R SAND COMPANY, INC.		7.89		4,418.40
2	Venture Corporation dba VCO Paving		8.00		4,480.00
3	THE CUMMINS CONSTRUCTION CO., INC.		7.15		4,004.00
0006	230(A) 2806	SOLID SLAB SODDING	43,992.000	SY	
	Engineer's Estimate		**1.50**		**65,988.00**
1	J & R SAND COMPANY, INC.		1.12		49,271.04
2	Venture Corporation dba VCO Paving		1.50		65,988.00
3	THE CUMMINS CONSTRUCTION CO., INC.		1.45		63,788.40
0007	233(A) 2817	VEGETATIVE MULCHING	9.090	AC	
	Engineer's Estimate		**275.00**		**2,499.75**
1	J & R SAND COMPANY, INC.		200.00		1,818.00
2	Venture Corporation dba VCO Paving		225.00		2,045.25
3	THE CUMMINS CONSTRUCTION CO., INC.		395.00		3,590.55
0008	307(B) 4210	CEMENT KILN DUST	1,785.030	TON	
	Engineer's Estimate		**58.00**		**103,531.74**
1	J & R SAND COMPANY, INC.		46.00		82,111.38
2	Venture Corporation dba VCO Paving		85.00		151,727.55
3	THE CUMMINS CONSTRUCTION CO., INC.		85.00		151,727.55
0009	307(E) 4240	CEMENTITIOUS STABILIZED SUBGRADE	44,074.320	SY	
	Engineer's Estimate		**2.80**		**123,408.10**
1	J & R SAND COMPANY, INC.		4.25		187,315.86
2	Venture Corporation dba VCO Paving		3.00		132,222.96
3	THE CUMMINS CONSTRUCTION CO., INC.		2.80		123,408.10

Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 230 **Contract ID:** 160089

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0010	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	2,925.020 TON	
	Engineer's Estimate		**54.33**	**158,916.34**
1	J & R SAND COMPANY, INC.		49.85	145,812.25
2	Venture Corporation dba VCO Paving		65.00	190,126.30
3	THE CUMMINS CONSTRUCTION CO., INC.		54.50	159,413.59
0011	407(B) 0250	TACK COAT	2,024.380 GAL	
	Engineer's Estimate		**3.33**	**6,741.19**
1	J & R SAND COMPANY, INC.		2.60	5,263.39
2	Venture Corporation dba VCO Paving		2.00	4,048.76
3	THE CUMMINS CONSTRUCTION CO., INC.		3.95	7,996.30
0012	408 5774	PRIME COAT	14,170.870 GAL	
	Engineer's Estimate		**4.00**	**56,683.48**
1	J & R SAND COMPANY, INC.		3.50	49,598.05
2	Venture Corporation dba VCO Paving		3.00	42,512.61
3	THE CUMMINS CONSTRUCTION CO., INC.		8.15	115,492.59
0013	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	9,128.310 TON	
	Engineer's Estimate		**85.00**	**775,906.35**
1	J & R SAND COMPANY, INC.		96.00	876,317.76
2	Venture Corporation dba VCO Paving		89.00	812,419.59
3	THE CUMMINS CONSTRUCTION CO., INC.		103.25	942,498.01
0014	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	4,628.310 TON	
	Engineer's Estimate		**90.00**	**416,547.90**
1	J & R SAND COMPANY, INC.		103.00	476,715.93
2	Venture Corporation dba VCO Paving		99.00	458,202.69
3	THE CUMMINS CONSTRUCTION CO., INC.		108.00	499,857.48
0015	501(G) 6309	CLSM BACKFILL	14.000 CY	
	Engineer's Estimate		**225.00**	**3,150.00**
1	J & R SAND COMPANY, INC.		300.00	4,200.00
2	Venture Corporation dba VCO Paving		250.00	3,500.00
3	THE CUMMINS CONSTRUCTION CO., INC.		225.00	3,150.00
0016	509(B) 0321	CLASS A CONCRETE	26.570 CY	
	Engineer's Estimate		**785.00**	**20,857.45**
1	J & R SAND COMPANY, INC.		1,100.00	29,227.00
2	Venture Corporation dba VCO Paving		880.00	23,381.60
3	THE CUMMINS CONSTRUCTION CO., INC.		800.00	21,256.00
0017	509(C) 0322	CLASS A CONCRETE, SMALL STRUCTURES	4.470 CY	
	Engineer's Estimate		**928.00**	**4,148.16**
1	J & R SAND COMPANY, INC.		1,200.00	5,364.00
2	Venture Corporation dba VCO Paving		1,320.00	5,900.40
3	THE CUMMINS CONSTRUCTION CO., INC.		1,260.00	5,632.20
0018	509(D) 0325	CLASS C CONCRETE	551.820 CY	
	Engineer's Estimate		**340.00**	**187,618.80**
1	J & R SAND COMPANY, INC.		350.00	193,137.00
2	Venture Corporation dba VCO Paving		375.00	206,932.50
3	THE CUMMINS CONSTRUCTION CO., INC.		340.00	187,618.80

Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 230 **Contract ID:** 160089

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0019	511(A) 0332	REINFORCING STEEL	2,797.300	LB	
	Engineer's Estimate		**1.20**		**3,356.76**
1	J & R SAND COMPANY, INC.		1.00		2,797.30
2	Venture Corporation dba VCO Paving		1.30		3,636.49
3	THE CUMMINS CONSTRUCTION CO., INC.		1.20		3,356.76
0020	601(A) 0297	TYPE I PLAIN RIPRAP	8.000	TON	
	Engineer's Estimate		**109.00**		**872.00**
1	J & R SAND COMPANY, INC.		100.00		800.00
2	Venture Corporation dba VCO Paving		150.00		1,200.00
3	THE CUMMINS CONSTRUCTION CO., INC.		109.00		872.00
0021	601(H) 1390	TYPE IV GROUTED RIPRAP	308.220	SY	
	Engineer's Estimate		**98.00**		**30,205.56**
1	J & R SAND COMPANY, INC.		75.00		23,116.50
2	Venture Corporation dba VCO Paving		120.00		36,986.40
3	THE CUMMINS CONSTRUCTION CO., INC.		98.00		30,205.56
0022	611(G) 6002	INLET (SMD-TYPE 2)	1.000	EA	
	Engineer's Estimate		**2,600.00**		**2,600.00**
1	J & R SAND COMPANY, INC.		2,977.75		2,977.75
2	Venture Corporation dba VCO Paving		2,700.00		2,700.00
3	THE CUMMINS CONSTRUCTION CO., INC.		2,600.00		2,600.00
0023	611(L) 0487	JUNCTION BOXES	85.760	CF	
	Engineer's Estimate		**85.00**		**7,289.60**
1	J & R SAND COMPANY, INC.		139.46		11,960.09
2	Venture Corporation dba VCO Paving		120.00		10,291.20
3	THE CUMMINS CONSTRUCTION CO., INC.		110.00		9,433.60
0024	613(A) 0492	24" R.C.PIPE CLASS III	109.000	LF	
	Engineer's Estimate		**90.00**		**9,810.00**
1	J & R SAND COMPANY, INC.		68.65		7,482.85
2	Venture Corporation dba VCO Paving		132.00		14,388.00
3	THE CUMMINS CONSTRUCTION CO., INC.		120.00		13,080.00
0025	613(A) 0496	48" R.C.PIPE CLASS III	144.000	LF	
	Engineer's Estimate		**175.00**		**25,200.00**
1	J & R SAND COMPANY, INC.		154.30		22,219.20
2	Venture Corporation dba VCO Paving		250.00		36,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		225.00		32,400.00
0026	613(A) 4496	28" X 18" R.C.PIPE ARCH CLASS A-III	384.000	LF	
	Engineer's Estimate		**130.00**		**49,920.00**
1	J & R SAND COMPANY, INC.		110.25		42,336.00
2	Venture Corporation dba VCO Paving		143.00		54,912.00
3	THE CUMMINS CONSTRUCTION CO., INC.		130.00		49,920.00
0027	613(B) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	302.000	LF	
	Engineer's Estimate		**21.50**		**6,493.00**
1	J & R SAND COMPANY, INC.		23.50		7,097.00
2	Venture Corporation dba VCO Paving		27.50		8,305.00
3	THE CUMMINS CONSTRUCTION CO., INC.		25.00		7,550.00

Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 230 **Contract ID:** 160089

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001	**ROADWAY**				
0028	613(L) 4504	21" X 15" PREFAB. CULVERT END SECTION, ARCH	2.000	EA	
	Engineer's Estimate		**200.00**		**400.00**
1	J & R SAND COMPANY, INC.		160.00		320.00
2	Venture Corporation dba VCO Paving		330.00		660.00
3	THE CUMMINS CONSTRUCTION CO., INC.		300.00		600.00
0029	613(L) 4515	28" X 18" PREFAB. CULVERT END SECTION, ARCH	15.000	EA	
	Engineer's Estimate		**900.00**		**13,500.00**
1	J & R SAND COMPANY, INC.		1,087.50		16,312.50
2	Venture Corporation dba VCO Paving		440.00		6,600.00
3	THE CUMMINS CONSTRUCTION CO., INC.		400.00		6,000.00
0030	613(L) 5738	48" PREFAB. CULVERT END SECTION, ROUND	4.000	EA	
	Engineer's Estimate		**1,500.00**		**6,000.00**
1	J & R SAND COMPANY, INC.		2,250.00		9,000.00
2	Venture Corporation dba VCO Paving		2,200.00		8,800.00
3	THE CUMMINS CONSTRUCTION CO., INC.		2,000.00		8,000.00
0031	613(M) 7186	TYPE A4 CULVERT END TREATMENT	10.000	EA	
	Engineer's Estimate		**950.00**		**9,500.00**
1	J & R SAND COMPANY, INC.		1,200.00		12,000.00
2	Venture Corporation dba VCO Paving		1,100.00		11,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		1,000.00		10,000.00
0032	613(M) 7187	TYPE B4 CULVERT END TREATMENT	3.000	EA	
	Engineer's Estimate		**1,600.00**		**4,800.00**
1	J & R SAND COMPANY, INC.		1,400.00		4,200.00
2	Venture Corporation dba VCO Paving		1,760.00		5,280.00
3	THE CUMMINS CONSTRUCTION CO., INC.		1,600.00		4,800.00
0033	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM	
	Engineer's Estimate		**35,000.00**		**35,000.00**
1	J & R SAND COMPANY, INC.		37,500.00		37,500.00
2	Venture Corporation dba VCO Paving		40,000.00		40,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		45,000.00		45,000.00
0034	619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	120.000	SY	
	Engineer's Estimate		**18.00**		**2,160.00**
1	J & R SAND COMPANY, INC.		20.00		2,400.00
2	Venture Corporation dba VCO Paving		30.00		3,600.00
3	THE CUMMINS CONSTRUCTION CO., INC.		18.00		2,160.00
0035	619(C) 0924	SAWING PAVEMENT	22.000	LF	
	Engineer's Estimate		**9.75**		**214.50**
1	J & R SAND COMPANY, INC.		5.00		110.00
2	Venture Corporation dba VCO Paving		3.00		66.00
3	THE CUMMINS CONSTRUCTION CO., INC.		22.75		500.50
0036	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF	
	Engineer's Estimate		**22.00**		**4,400.00**
1	J & R SAND COMPANY, INC.		18.00		3,600.00
2	Venture Corporation dba VCO Paving		15.00		3,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		18.00		3,600.00

Letting Date: February 18, 2016, 10:30 A.M.
Call Order: 230 **Contract ID:** 160089

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0037	623(F) 4446	GUARDRAIL ANCHOR UNIT (TYPE A)	10.000 EA	
	Engineer's Estimate		**1,900.00**	**19,000.00**
1	J & R SAND COMPANY, INC.		1,588.00	15,880.00
2	Venture Corporation dba VCO Paving		1,220.00	12,200.00
3	THE CUMMINS CONSTRUCTION CO., INC.		1,600.00	16,000.00
0038	850(A) 8110	SHEET ALUMINUM SIGNS	58.900 SF	
	Engineer's Estimate		**36.00**	**2,120.40**
1	J & R SAND COMPANY, INC.		59.00	3,475.10
2	Venture Corporation dba VCO Paving		35.00	2,061.50
3	THE CUMMINS CONSTRUCTION CO., INC.		59.00	3,475.10
0039	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	32,280.240 LF	
	Engineer's Estimate		**0.50**	**16,140.12**
1	J & R SAND COMPANY, INC.		0.37	11,943.69
2	Venture Corporation dba VCO Paving		0.80	25,824.19
3	THE CUMMINS CONSTRUCTION CO., INC.		0.37	11,943.69
0040	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM	
	Engineer's Estimate		**11,200.00**	**11,200.00**
1	J & R SAND COMPANY, INC.		24,650.00	24,650.00
2	Venture Corporation dba VCO Paving		25,000.00	25,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		28,000.00	28,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 STAKING				
0041	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM	
	Engineer's Estimate		**32,000.00**	**32,000.00**
1	J & R SAND COMPANY, INC.		53,000.00	53,000.00
2	Venture Corporation dba VCO Paving		50,000.00	50,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		81,000.00	81,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003 CONSTRUCTION				
0042	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM	
	Engineer's Estimate		**6,800.00**	**6,800.00**
1	J & R SAND COMPANY, INC.		12,500.00	12,500.00
2	Venture Corporation dba VCO Paving		32,500.00	32,500.00
3	THE CUMMINS CONSTRUCTION CO., INC.		14,000.00	14,000.00
0043	641 1552	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**130,000.00**	**130,000.00**
1	J & R SAND COMPANY, INC.		167,000.00	167,000.00
2	Venture Corporation dba VCO Paving		175,000.00	175,000.00
3	THE CUMMINS CONSTRUCTION CO., INC.		190,000.00	190,000.00