Letting Date: February 16, 2017, 10:30 A.M.
Call Order: 130 **Contract ID:** 170071
J/P No.: 28426(04) **Project No.:** CIRB-216D(062)RB **Contract Time:**
County: COMANCHE
Description: BRIDGE AND APPROACHES COUNTY ROAD (EW-168/BISHOP ROAD): OVER NUMU CREEK, 0.2 MILES EAST OF I-44 NEAR LAWTON. PROJECT LENGTH = 0.224 MILE

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	786,801.70		
1	SEWELL BROS., INC.	797,529.03	101.36	100.00
2	K & R BUILDERS, INC.	828,157.47	105.26	103.84
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	913,290.18	116.08	114.51
4	EARTH BUILDERS, L.P.	980,663.44	124.64	122.96

Letting Date: February 16, 2017, 10:30 A.M.
Call Order: 130 **Contract ID:** 170071

Line #	Item Number / Item Description / Bidder	Unit Price	Quantity/Unit / Ext Amount
Section: 0001 ROADWAY			
0001	201(A) 0102 CLEARING AND GRUBBING		1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	SEWELL BROS., INC.	10,000.00	10,000.00
2	K & R BUILDERS, INC.	12,000.00	12,000.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	18,900.00	18,900.00
4	EARTH BUILDERS, L.P.	20,000.00	20,000.00
0002	202(H) 0185 EARTHWORK		1.000 LSUM
	Engineer's Estimate	**19,450.00**	**19,450.00**
1	SEWELL BROS., INC.	30,000.00	30,000.00
2	K & R BUILDERS, INC.	37,000.00	37,000.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	61,673.85	61,673.85
4	EARTH BUILDERS, L.P.	50,000.00	50,000.00
0003	221(C) 2801 TEMPORARY SILT FENCE		1,385.000 LF
	Engineer's Estimate	**2.50**	**3,462.50**
1	SEWELL BROS., INC.	1.25	1,731.25
2	K & R BUILDERS, INC.	1.35	1,869.75
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	1.18	1,634.30
4	EARTH BUILDERS, L.P.	1.50	2,077.50
0004	221(F) 0100 TEMPORARY SILT DIKE		84.000 LF
	Engineer's Estimate	**8.00**	**672.00**
1	SEWELL BROS., INC.	8.65	726.60
2	K & R BUILDERS, INC.	8.00	672.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	8.29	696.36
4	EARTH BUILDERS, L.P.	8.00	672.00
0005	230(A) 2806 SOLID SLAB SODDING		11,980.000 SY
	Engineer's Estimate	**1.50**	**17,970.00**
1	SEWELL BROS., INC.	1.28	15,334.40
2	K & R BUILDERS, INC.	1.28	15,334.40
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	1.21	14,495.80
4	EARTH BUILDERS, L.P.	1.50	17,970.00
0006	233(A) 2817 VEGETATIVE MULCHING		5.000 AC
	Engineer's Estimate	**450.00**	**2,250.00**
1	SEWELL BROS., INC.	30.00	150.00
2	K & R BUILDERS, INC.	50.00	250.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	26.25	131.25
4	EARTH BUILDERS, L.P.	250.00	1,250.00
0007	307(K) 4300 STABILIZED SUBGRADE		3,425.000 SY
	Engineer's Estimate	**7.00**	**23,975.00**
1	SEWELL BROS., INC.	7.50	25,687.50
2	K & R BUILDERS, INC.	6.40	21,920.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	6.09	20,858.25
4	EARTH BUILDERS, L.P.	9.00	30,825.00
0008	411(B) 5945 SUPERPAVE, TYPE S3(PG 64-22 OK)		704.000 TON
	Engineer's Estimate	**70.00**	**49,280.00**
1	SEWELL BROS., INC.	77.00	54,208.00
2	K & R BUILDERS, INC.	79.00	55,616.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	72.19	50,821.76
4	EARTH BUILDERS, L.P.	80.00	56,320.00

Letting Date: February 16, 2017, 10:30 A.M.
Call Order: 130 **Contract ID:** 170071

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0001	**ROADWAY**		
0009	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	372.000 TON
	Engineer's Estimate	**80.00**	**29,760.00**
1	SEWELL BROS., INC.	90.00	33,480.00
2	K & R BUILDERS, INC.	91.15	33,907.80
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	83.21	30,954.12
4	EARTH BUILDERS, L.P.	98.00	36,456.00
0010	509(D) 0325	CLASS C CONCRETE	10.000 CY
	Engineer's Estimate	**300.00**	**3,000.00**
1	SEWELL BROS., INC.	350.00	3,500.00
2	K & R BUILDERS, INC.	275.00	2,750.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	240.27	2,402.70
4	EARTH BUILDERS, L.P.	400.00	4,000.00
0011	613(B) 0690	24" CORR. GALV. STEEL PIPE	30.000 LF
	Engineer's Estimate	**40.00**	**1,200.00**
1	SEWELL BROS., INC.	40.00	1,200.00
2	K & R BUILDERS, INC.	29.00	870.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	42.00	1,260.00
4	EARTH BUILDERS, L.P.	75.00	2,250.00
0012	613(L) 5730	24" PREFAB. CULVERT END SECTION, ROUND	2.000 EA
	Engineer's Estimate	**500.00**	**1,000.00**
1	SEWELL BROS., INC.	200.00	400.00
2	K & R BUILDERS, INC.	250.00	500.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	472.50	945.00
4	EARTH BUILDERS, L.P.	1,500.00	3,000.00
0013	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	SEWELL BROS., INC.	5,000.00	5,000.00
2	K & R BUILDERS, INC.	3,800.00	3,800.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	5,250.00	5,250.00
4	EARTH BUILDERS, L.P.	10,000.00	10,000.00
0014	619(C) 0924	SAWING PAVEMENT	192.000 LF
	Engineer's Estimate	**5.00**	**960.00**
1	SEWELL BROS., INC.	5.00	960.00
2	K & R BUILDERS, INC.	7.50	1,440.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	5.25	1,008.00
4	EARTH BUILDERS, L.P.	6.00	1,152.00
0015	850(A) 8110	SHEET ALUMINUM SIGNS	10.360 SF
	Engineer's Estimate	**20.00**	**207.20**
1	SEWELL BROS., INC.	22.00	227.92
2	K & R BUILDERS, INC.	25.00	259.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	21.00	217.56
4	EARTH BUILDERS, L.P.	24.00	248.64
0016	851(C) 8327	2 1/4" SQUARE TUBE POST	26.000 LF
	Engineer's Estimate	**12.00**	**312.00**
1	SEWELL BROS., INC.	11.00	286.00
2	K & R BUILDERS, INC.	15.00	390.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	10.50	273.00
4	EARTH BUILDERS, L.P.	14.00	364.00

Letting Date: February 16, 2017, 10:30 A.M.
Call Order: 130 **Contract ID:** 170071

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A' - NBI NO. 14096**			
0017	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	260.000 CY	
	Engineer's Estimate		**18.00**	**4,680.00**
1	SEWELL BROS., INC.		15.00	3,900.00
2	K & R BUILDERS, INC.		8.75	2,275.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		22.00	5,720.00
4	EARTH BUILDERS, L.P.		25.00	6,500.00
0018	501(F) 6352	GRANULAR BACKFILL	170.000 CY	
	Engineer's Estimate		**60.00**	**10,200.00**
1	SEWELL BROS., INC.		75.00	12,750.00
2	K & R BUILDERS, INC.		65.00	11,050.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		80.67	13,713.90
4	EARTH BUILDERS, L.P.		70.00	11,900.00
0019	503(A) 6290	PRESTRESSED CONCRETE BEAMS (TYPE J BT)	538.670 LF	
	Engineer's Estimate		**300.00**	**161,601.00**
1	SEWELL BROS., INC.		310.00	166,987.70
2	K & R BUILDERS, INC.		295.00	158,907.65
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		307.31	165,538.68
4	EARTH BUILDERS, L.P.		300.00	161,601.00
0020	504(B) 1305	SAW-CUT GROOVING	432.700 SY	
	Engineer's Estimate		**5.00**	**2,163.50**
1	SEWELL BROS., INC.		3.80	1,644.26
2	K & R BUILDERS, INC.		4.50	1,947.15
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		4.18	1,808.69
4	EARTH BUILDERS, L.P.		9.00	3,894.30
0021	504(D) 6239	CONCRETE RAIL (TR3)	364.500 LF	
	Engineer's Estimate		**75.00**	**27,337.50**
1	SEWELL BROS., INC.		85.00	30,982.50
2	K & R BUILDERS, INC.		73.00	26,608.50
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		91.27	33,267.92
4	EARTH BUILDERS, L.P.		100.00	36,450.00
0022	506(A) 1322	STRUCTURAL STEEL	1,420.000 LB	
	Engineer's Estimate		**3.00**	**4,260.00**
1	SEWELL BROS., INC.		3.00	4,260.00
2	K & R BUILDERS, INC.		4.50	6,390.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		3.40	4,828.00
4	EARTH BUILDERS, L.P.		6.00	8,520.00
0023	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	4.000 EA	
	Engineer's Estimate		**900.00**	**3,600.00**
1	SEWELL BROS., INC.		1,000.00	4,000.00
2	K & R BUILDERS, INC.		1,300.00	5,200.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		1,463.79	5,855.16
4	EARTH BUILDERS, L.P.		1,600.00	6,400.00

Letting Date: February 16, 2017, 10:30 A.M.
Call Order: 130 **Contract ID:** 170071

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A' - NBI NO. 14096					
0024	507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	4.000	EA	
	Engineer's Estimate		**900.00**		**3,600.00**
1	SEWELL BROS., INC.		1,000.00		4,000.00
2	K & R BUILDERS, INC.		1,300.00		5,200.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		1,463.79		5,855.16
4	EARTH BUILDERS, L.P.		1,600.00		6,400.00
0025	509(A) 1326	CLASS AA CONCRETE	150.600	CY	
	Engineer's Estimate		**450.00**		**67,770.00**
1	SEWELL BROS., INC.		600.00		90,360.00
2	K & R BUILDERS, INC.		650.00		97,890.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		704.48		106,094.69
4	EARTH BUILDERS, L.P.		520.00		78,312.00
0026	509(B) 1328	CLASS A CONCRETE	106.200	CY	
	Engineer's Estimate		**500.00**		**53,100.00**
1	SEWELL BROS., INC.		600.00		63,720.00
2	K & R BUILDERS, INC.		675.00		71,685.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		646.34		68,641.31
4	EARTH BUILDERS, L.P.		500.00		53,100.00
0027	511(A) 1332	REINFORCING STEEL	48,310.000	LB	
	Engineer's Estimate		**1.00**		**48,310.00**
1	SEWELL BROS., INC.		0.70		33,817.00
2	K & R BUILDERS, INC.		0.90		43,479.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		0.91		43,962.10
4	EARTH BUILDERS, L.P.		1.20		57,972.00
0028	514(A) 6010	PILES, FURNISHED (HP 10X42)	216.000	LF	
	Engineer's Estimate		**30.00**		**6,480.00**
1	SEWELL BROS., INC.		25.00		5,400.00
2	K & R BUILDERS, INC.		28.00		6,048.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		32.28		6,972.48
4	EARTH BUILDERS, L.P.		30.00		6,480.00
0029	514(A) 6011	PILES, FURNISHED (HP 12X53)	874.000	LF	
	Engineer's Estimate		**40.00**		**34,960.00**
1	SEWELL BROS., INC.		30.00		26,220.00
2	K & R BUILDERS, INC.		32.20		28,142.80
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		38.83		33,937.42
4	EARTH BUILDERS, L.P.		40.00		34,960.00
0030	514(B) 6292	PILES, DRIVEN (HP 10X42)	216.000	LF	
	Engineer's Estimate		**15.00**		**3,240.00**
1	SEWELL BROS., INC.		15.00		3,240.00
2	K & R BUILDERS, INC.		12.00		2,592.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		22.00		4,752.00
4	EARTH BUILDERS, L.P.		35.00		7,560.00
0031	514(B) 6294	PILES, DRIVEN (HP 12X53)	874.000	LF	
	Engineer's Estimate		**15.00**		**13,110.00**
1	SEWELL BROS., INC.		15.00		13,110.00
2	K & R BUILDERS, INC.		13.80		12,061.20
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.		22.00		19,228.00
4	EARTH BUILDERS, L.P.		35.00		30,590.00

Letting Date: February 16, 2017, 10:30 A.M.
Call Order: 130 **Contract ID:** 170071

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A' - NBI NO. 14096**		
0032	514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000 EA
	Engineer's Estimate	**400.00**	**400.00**
1	SEWELL BROS., INC.	400.00	400.00
2	K & R BUILDERS, INC.	400.00	400.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	400.00	400.00
4	EARTH BUILDERS, L.P.	400.00	400.00
0033	601(B) 1353	TYPE I-A PLAIN RIPRAP	1,170.000 TON
	Engineer's Estimate	**40.00**	**46,800.00**
1	SEWELL BROS., INC.	38.00	44,460.00
2	K & R BUILDERS, INC.	38.47	45,009.90
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	41.07	48,051.90
4	EARTH BUILDERS, L.P.	45.00	52,650.00
0034	601(C) 1355	TYPE I-A FILTER BLANKET	322.000 TON
	Engineer's Estimate	**30.00**	**9,660.00**
1	SEWELL BROS., INC.	29.00	9,338.00
2	K & R BUILDERS, INC.	29.56	9,518.32
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	32.89	10,590.58
4	EARTH BUILDERS, L.P.	32.00	10,304.00
0035	613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	72.000 LF
	Engineer's Estimate	**25.00**	**1,800.00**
1	SEWELL BROS., INC.	25.00	1,800.00
2	K & R BUILDERS, INC.	30.00	2,160.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	31.09	2,238.48
4	EARTH BUILDERS, L.P.	20.00	1,440.00
0036	613(I) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	65.000 LF
	Engineer's Estimate	**25.00**	**1,625.00**
1	SEWELL BROS., INC.	25.00	1,625.00
2	K & R BUILDERS, INC.	30.00	1,950.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	24.77	1,610.05
4	EARTH BUILDERS, L.P.	20.00	1,300.00
0037	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM
	Engineer's Estimate	**10,000.00**	**10,000.00**
1	SEWELL BROS., INC.	15,000.00	15,000.00
2	K & R BUILDERS, INC.	20,000.00	20,000.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	16,500.00	16,500.00
4	EARTH BUILDERS, L.P.	40,000.00	40,000.00
0038	623(A) 1418	BEAM GUARDRAIL W-BEAM SINGLE	55.000 LF
	Engineer's Estimate	**15.00**	**825.00**
1	SEWELL BROS., INC.	27.50	1,512.50
2	K & R BUILDERS, INC.	25.00	1,375.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	24.75	1,361.25
4	EARTH BUILDERS, L.P.	28.00	1,540.00
0039	623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000 EA
	Engineer's Estimate	**1,500.00**	**6,000.00**
1	SEWELL BROS., INC.	1,550.00	6,200.00
2	K & R BUILDERS, INC.	1,600.00	6,400.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	1,595.00	6,380.00
4	EARTH BUILDERS, L.P.	1,800.00	7,200.00

Letting Date: February 16, 2017, 10:30 A.M.
Call Order: 130 **Contract ID:** 170071

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A' - NBI NO. 14096**		
0040	623(F) 6029	GUARDRAIL ANCHOR UNIT (TYPE A)	4.000 EA
	Engineer's Estimate	**1,300.00**	**5,200.00**
1	SEWELL BROS., INC.	2,090.00	8,360.00
2	K & R BUILDERS, INC.	1,700.00	6,800.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	1,705.00	6,820.00
4	EARTH BUILDERS, L.P.	2,400.00	9,600.00
0041	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	SEWELL BROS., INC.	2,000.00	2,000.00
2	K & R BUILDERS, INC.	2,800.00	2,800.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	1,980.00	1,980.00
4	EARTH BUILDERS, L.P.	3,500.00	3,500.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003	**STAKING**		
0042	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**14,226.00**	**14,226.00**
1	SEWELL BROS., INC.	5,950.00	5,950.00
2	K & R BUILDERS, INC.	6,500.00	6,500.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	6,615.00	6,615.00
4	EARTH BUILDERS, L.P.	15,000.00	15,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004	**CONSTRUCTION**		
0043	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	SEWELL BROS., INC.	3,500.00	3,500.00
2	K & R BUILDERS, INC.	3,000.00	3,000.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	2,625.00	2,625.00
4	EARTH BUILDERS, L.P.	5,000.00	5,000.00
0044	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**61,280.00**	**61,280.00**
1	SEWELL BROS., INC.	40,000.00	40,000.00
2	K & R BUILDERS, INC.	44,000.00	44,000.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	66,763.06	66,763.06
4	EARTH BUILDERS, L.P.	70,000.00	70,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0005	**FENCING - NON-PARTICIPATING**		
0045	624(C) 4459	FENCE-STYLE SWF (5 BARBED WIRE)	2,215.000 LF
	Engineer's Estimate	**5.00**	**11,075.00**
1	SEWELL BROS., INC.	4.56	10,100.40
2	K & R BUILDERS, INC.	4.60	10,189.00
3	FRONTIER BRIDGE, INC. / BRIDGECO CONTRACTORS, INC.	4.36	9,657.40
4	EARTH BUILDERS, L.P.	7.00	15,505.00

Letting Date: February 16, 2017, 10:30 A.M.
Call Order: 130 **Contract ID:** 170071