Letting Date: February 15, 2018, 10:30 A.M.
Call Order: 508 **Contract ID:** 180052
J/P No.: 29986(04) **Project No.:** CIRB-248C(034)RB **Contract Time:**
County: MARSHALL
Description: GRADE,DRAIN, SURFACE, AND BRIDGE COUNTY ROAD (ENOS ROAD): FROM 4.0 MILES SOUTH OF SH-32, EXTEND SOUTH NEAR KINGSTON. PROJECT LENGTH = 3.039 MILES

	VENDORNAME	PROPOSALITEMTO		
1	THE CUMMINS CONSTRUCTION CO., INC.	2,563,204.62	90.86	100.00
2	Overland Corporation	2,628,277.93	93.16	102.54
	Engineer's Estimate	2,821,128.81		
3	Silver Star Construction Company, Inc.	2,962,255.25	105.00	115.57

Letting Date: February 15, 2018, 10:30 A.M.
Call Order: 508 **Contract ID:** 180052

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001	**ROADWAY**				
0001	201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM	
	Engineer's Estimate		**28,136.19**		**28,136.19**
1	THE CUMMINS CONSTRUCTION CO., INC.		23,000.00		23,000.00
2	Overland Corporation		87,000.00		87,000.00
3	Silver Star Construction Company, Inc.		23,500.00		23,500.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	28,047.000	CY	
	Engineer's Estimate		**8.77**		**245,972.19**
1	THE CUMMINS CONSTRUCTION CO., INC.		10.43		292,530.21
2	Overland Corporation		15.95		447,349.65
3	Silver Star Construction Company, Inc.		11.35		318,333.45
0003	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM	
	Engineer's Estimate		**38,295.86**		**38,295.86**
1	THE CUMMINS CONSTRUCTION CO., INC.		33,637.50		33,637.50
2	Overland Corporation		40,750.00		40,750.00
3	Silver Star Construction Company, Inc.		36,000.00		36,000.00
0004	221(C) 2801	TEMPORARY SILT FENCE	15,821.000	LF	
	Engineer's Estimate		**1.26**		**19,934.46**
1	THE CUMMINS CONSTRUCTION CO., INC.		3.03		47,937.63
2	Overland Corporation		1.35		21,358.35
3	Silver Star Construction Company, Inc.		3.50		55,373.50
0005	221(F) 0100	TEMPORARY SILT DIKE	800.000	LF	
	Engineer's Estimate		**7.95**		**6,360.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		15.88		12,704.00
2	Overland Corporation		9.50		7,600.00
3	Silver Star Construction Company, Inc.		18.00		14,400.00
0006	230(A) 2806	SOLID SLAB SODDING	14,080.000	SY	
	Engineer's Estimate		**1.62**		**22,809.60**
1	THE CUMMINS CONSTRUCTION CO., INC.		6.83		96,166.40
2	Overland Corporation		2.10		29,568.00
3	Silver Star Construction Company, Inc.		7.80		109,824.00
0007	232(B) 2814	SEEDING METHOD B	12.380	AC	
	Engineer's Estimate		**400.00**		**4,952.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		6,500.00		80,470.00
2	Overland Corporation		400.00		4,952.00
3	Silver Star Construction Company, Inc.		7,430.00		91,983.40
0008	233(A) 2817	VEGETATIVE MULCHING	15.280	AC	
	Engineer's Estimate		**384.43**		**5,874.09**
1	THE CUMMINS CONSTRUCTION CO., INC.		3,700.00		56,536.00
2	Overland Corporation		955.00		14,592.40
3	Silver Star Construction Company, Inc.		4,200.00		64,176.00
0009	234(A) 2824	FERTILIZING (10-20-10)	1.410	TON	
	Engineer's Estimate		**541.56**		**763.60**
1	THE CUMMINS CONSTRUCTION CO., INC.		1,503.00		2,119.23
2	Overland Corporation		530.00		747.30
3	Silver Star Construction Company, Inc.		1,600.00		2,256.00

Letting Date: February 15, 2018, 10:30 A.M.
Call Order: 508 **Contract ID:** 180052

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0010	303(A) 2100	AGGREGATE BASE TYPE A	9,170.000	CY
	Engineer's Estimate		**48.69**	**446,487.30**
1	THE CUMMINS CONSTRUCTION CO., INC.		50.00	458,500.00
2	Overland Corporation		46.00	421,820.00
3	Silver Star Construction Company, Inc.		54.50	499,765.00
0011	325 5271	SEPARATOR FABRIC	17,718.000	SY
	Engineer's Estimate		**1.48**	**26,222.64**
1	THE CUMMINS CONSTRUCTION CO., INC.		0.75	13,288.50
2	Overland Corporation		1.60	28,348.80
3	Silver Star Construction Company, Inc.		0.95	16,832.10
0012	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	2,907.000	TON
	Engineer's Estimate		**26.83**	**77,994.81**
1	THE CUMMINS CONSTRUCTION CO., INC.		25.50	74,128.50
2	Overland Corporation		29.95	87,064.65
3	Silver Star Construction Company, Inc.		27.50	79,942.50
0013	407(B) 0250	TACK COAT	7,628.000	GAL
	Engineer's Estimate		**3.44**	**26,240.32**
1	THE CUMMINS CONSTRUCTION CO., INC.		2.50	19,070.00
2	Overland Corporation		0.01	76.28
3	Silver Star Construction Company, Inc.		2.50	19,070.00
0014	408 5774	PRIME COAT	13,756.000	GAL
	Engineer's Estimate		**3.95**	**54,336.20**
1	THE CUMMINS CONSTRUCTION CO., INC.		3.75	51,585.00
2	Overland Corporation		0.01	137.56
3	Silver Star Construction Company, Inc.		3.00	41,268.00
0015	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	8,448.000	TON
	Engineer's Estimate		**71.29**	**602,257.92**
1	THE CUMMINS CONSTRUCTION CO., INC.		55.00	464,640.00
2	Overland Corporation		63.90	539,827.20
3	Silver Star Construction Company, Inc.		73.00	616,704.00
0016	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	5,951.000	TON
	Engineer's Estimate		**78.08**	**464,654.08**
1	THE CUMMINS CONSTRUCTION CO., INC.		67.25	400,204.75
2	Overland Corporation		73.55	437,696.05
3	Silver Star Construction Company, Inc.		87.50	520,712.50
0017	412 5267	COLD MILLING PAVEMENT	500.000	SY
	Engineer's Estimate		**13.52**	**6,760.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		8.15	4,075.00
2	Overland Corporation		15.00	7,500.00
3	Silver Star Construction Company, Inc.		30.00	15,000.00
0018	601(A) 0297	TYPE I PLAIN RIPRAP	185.000	TON
	Engineer's Estimate		**52.69**	**9,747.65**
1	THE CUMMINS CONSTRUCTION CO., INC.		38.70	7,159.50
2	Overland Corporation		52.15	9,647.75
3	Silver Star Construction Company, Inc.		42.00	7,770.00

Letting Date: February 15, 2018, 10:30 A.M.
Call Order: 508 **Contract ID:** 180052

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001	**ROADWAY**				
0019	611(G) 6002	INLET (SMD-TYPE 2)	1.000	EA	
	Engineer's Estimate		**2,758.90**		**2,758.90**
1	THE CUMMINS CONSTRUCTION CO., INC.		3,400.00		3,400.00
2	Overland Corporation		4,100.00		4,100.00
3	Silver Star Construction Company, Inc.		3,690.00		3,690.00
0020	613(B) 0689	18" CORR. GALV. STEEL PIPE	973.000	LF	
	Engineer's Estimate		**32.28**		**31,408.44**
1	THE CUMMINS CONSTRUCTION CO., INC.		24.00		23,352.00
2	Overland Corporation		52.00		50,596.00
3	Silver Star Construction Company, Inc.		26.00		25,298.00
0021	613(B) 0690	24" CORR. GALV. STEEL PIPE	149.000	LF	
	Engineer's Estimate		**42.19**		**6,286.31**
1	THE CUMMINS CONSTRUCTION CO., INC.		31.00		4,619.00
2	Overland Corporation		40.00		5,960.00
3	Silver Star Construction Company, Inc.		33.00		4,917.00
0022	613(EE) 5610	(SP) 18" CORRUGATED POLYPROPYLENE PIPE	152.000	LF	
	Engineer's Estimate		**38.67**		**5,877.84**
1	THE CUMMINS CONSTRUCTION CO., INC.		32.00		4,864.00
2	Overland Corporation		59.00		8,968.00
3	Silver Star Construction Company, Inc.		34.00		5,168.00
0023	613(EE) 5620	(SP) 24" CORRUGATED POLYPROPYLENE PIPE	566.000	LF	
	Engineer's Estimate		**195.00**		**110,370.00**
1	THE CUMMINS CONSTRUCTION CO., INC.		47.00		26,602.00
2	Overland Corporation		69.00		39,054.00
3	Silver Star Construction Company, Inc.		51.00		28,866.00
0024	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM	
	Engineer's Estimate		**24,924.99**		**24,924.99**
1	THE CUMMINS CONSTRUCTION CO., INC.		9,500.00		9,500.00
2	Overland Corporation		25,000.00		25,000.00
3	Silver Star Construction Company, Inc.		10,000.00		10,000.00
0025	629(A) 4958	MAILBOX INSTALLATION-SINGLE	15.000	EA	
	Engineer's Estimate		**87.12**		**1,306.80**
1	THE CUMMINS CONSTRUCTION CO., INC.		70.00		1,050.00
2	Overland Corporation		70.00		1,050.00
3	Silver Star Construction Company, Inc.		100.00		1,500.00
0026	629(B) 4959	MAILBOX INSTALLATION-MULTIPLE	3.000	EA	
	Engineer's Estimate		**160.13**		**480.39**
1	THE CUMMINS CONSTRUCTION CO., INC.		165.00		495.00
2	Overland Corporation		165.00		495.00
3	Silver Star Construction Company, Inc.		215.00		645.00
0027	629(C) 4960	MAILBOX	21.000	EA	
	Engineer's Estimate		**43.44**		**912.24**
1	THE CUMMINS CONSTRUCTION CO., INC.		38.00		798.00
2	Overland Corporation		40.00		840.00
3	Silver Star Construction Company, Inc.		55.00		1,155.00

Letting Date: February 15, 2018, 10:30 A.M.
Call Order: 508 **Contract ID:** 180052

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002 BRIDGE			
0028	509(A) 1326	CLASS AA CONCRETE	125.000 CY
	Engineer's Estimate	**685.70**	**85,712.50**
1	THE CUMMINS CONSTRUCTION CO., INC.	625.00	78,125.00
2	Overland Corporation	617.50	77,187.50
3	Silver Star Construction Company, Inc.	815.00	101,875.00
0029	511(A) 1332	REINFORCING STEEL	23,594.000 LB
	Engineer's Estimate	**1.04**	**24,537.76**
1	THE CUMMINS CONSTRUCTION CO., INC.	1.50	35,391.00
2	Overland Corporation	1.40	33,031.60
3	Silver Star Construction Company, Inc.	0.55	12,976.70

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 TRAFFIC			
0030	850(A) 8110	SHEET ALUMINUM SIGNS	329.750 SF
	Engineer's Estimate	**17.34**	**5,717.87**
1	THE CUMMINS CONSTRUCTION CO., INC.	12.00	3,957.00
2	Overland Corporation	12.70	4,187.83
3	Silver Star Construction Company, Inc.	15.00	4,946.25
0031	851(C) 8324	2" SQUARE TUBE POST	385.880 LF
	Engineer's Estimate	**9.40**	**3,627.27**
1	THE CUMMINS CONSTRUCTION CO., INC.	15.00	5,788.20
2	Overland Corporation	15.90	6,135.49
3	Silver Star Construction Company, Inc.	9.00	3,472.92
0032	853 9039	DELINEATORS(TYPE 2, CODE 3)	26.000 EA
	Engineer's Estimate	**24.52**	**637.52**
1	THE CUMMINS CONSTRUCTION CO., INC.	23.00	598.00
2	Overland Corporation	24.50	637.00
3	Silver Star Construction Company, Inc.	34.00	884.00
0033	854(A) 8800	TRAFFIC STRIPE(PAINT)(4" WIDE)	63,632.000 LF
	Engineer's Estimate	**0.11**	**6,999.52**
1	THE CUMMINS CONSTRUCTION CO., INC.	0.10	6,363.20
2	Overland Corporation	0.11	6,999.52
3	Silver Star Construction Company, Inc.	0.14	8,908.48
0034	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**11,005.03**	**11,005.03**
1	THE CUMMINS CONSTRUCTION CO., INC.	5,350.00	5,350.00
2	Overland Corporation	6,000.00	6,000.00
3	Silver Star Construction Company, Inc.	10,342.45	10,342.45

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004 STAKING			

Letting Date: February 15, 2018, 10:30 A.M.

Call Order: 508 **Contract ID:** 180052

Line #	Item Number		Item Description	Quantity/Unit	
	Bidder			Unit Price	Ext Amount
Section:	**0004**	**STAKING**			
0035	642(B)	0096	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
	Engineer's Estimate			**36,708.36**	**36,708.36**
1	THE CUMMINS CONSTRUCTION CO., INC.			68,700.00	68,700.00
2	Overland Corporation			20,000.00	20,000.00
3	Silver Star Construction Company, Inc.			48,700.00	48,700.00

Line #	Item Number		Item Description	Quantity/Unit	
	Bidder			Unit Price	Ext Amount
Section:	**0005**	**CONSTRUCTION**			
0036	220	2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	Engineer's Estimate			**4,945.79**	**4,945.79**
1	THE CUMMINS CONSTRUCTION CO., INC.			15,000.00	15,000.00
2	Overland Corporation			2,000.00	2,000.00
3	Silver Star Construction Company, Inc.			8,500.00	8,500.00
0037	641	1552	MOBILIZATION	1.000	LSUM
	Engineer's Estimate			**369,112.37**	**369,112.37**
1	THE CUMMINS CONSTRUCTION CO., INC.			131,500.00	131,500.00
2	Overland Corporation			150,000.00	150,000.00
3	Silver Star Construction Company, Inc.			147,500.00	147,500.00