Letting Date: June 20, 2019, 10:30 A.M.
Call Order: 820 **Contract ID:** 180107
J/P No.: 25528(04) **Project No.:** STP-157C(167)CI **Contract Time:**
County: OSAGE
Description: BRIDGE AND APPROACHES COUNTY ROAD (EW-28): OVER LITTLE DRUM CREEK, 7.8 MILES EAST OF THE NOBLE COUNTY LINE. PROJECT LENGTH = 0.955 MILE

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	2,097,727.85		
1	RRY SERVICES LLC	2,268,477.06	108.14	100.00

Letting Date: June 20, 2019, 10:30 A.M.
Call Order: 820 **Contract ID:** 180107

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM	
	Engineer's Estimate		**10,000.00**		**10,000.00**
1	RRY SERVICES LLC		52,000.00		52,000.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	18,478.000	CY	
	Engineer's Estimate		**10.00**		**184,780.00**
1	RRY SERVICES LLC		10.00		184,780.00
0003	202(D) 0184	UNCLASSIFIED BORROW	2,278.000	CY	
	Engineer's Estimate		**25.00**		**56,950.00**
1	RRY SERVICES LLC		12.00		27,336.00
0004	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM	
	Engineer's Estimate		**10,000.00**		**10,000.00**
1	RRY SERVICES LLC		15,000.00		15,000.00
0005	210 0121	OBLITERATING ABANDONED ROAD	635.000	LF	
	Engineer's Estimate		**10.00**		**6,350.00**
1	RRY SERVICES LLC		6.00		3,810.00
0006	221(C) 2801	TEMPORARY SILT FENCE	6,774.000	LF	
	Engineer's Estimate		**4.00**		**27,096.00**
1	RRY SERVICES LLC		2.99		20,254.26
0007	221(F) 0100	TEMPORARY SILT DIKE	608.000	LF	
	Engineer's Estimate		**10.00**		**6,080.00**
1	RRY SERVICES LLC		18.95		11,521.60
0008	230(A) 2806	SOLID SLAB SODDING	37,446.000	SY	
	Engineer's Estimate		**3.00**		**112,338.00**
1	RRY SERVICES LLC		3.95		147,911.70
0009	233(A) 2817	VEGETATIVE MULCHING	10.200	AC	
	Engineer's Estimate		**700.00**		**7,140.00**
1	RRY SERVICES LLC		2,950.00		30,090.00
0010	303(A) 2100	AGGREGATE BASE TYPE A	2,807.000	CY	
	Engineer's Estimate		**50.00**		**140,350.00**
1	RRY SERVICES LLC		60.00		168,420.00
0011	310(B) 0149	SUBGRADE, METHOD B	14,009.000	SY	
	Engineer's Estimate		**2.00**		**28,018.00**
1	RRY SERVICES LLC		1.50		21,013.50
0012	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	402.000	TON	
	Engineer's Estimate		**40.00**		**16,080.00**
1	RRY SERVICES LLC		30.00		12,060.00
0013	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	2,783.000	TON	
	Engineer's Estimate		**85.00**		**236,555.00**
1	RRY SERVICES LLC		90.00		250,470.00
0014	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,864.000	TON	
	Engineer's Estimate		**90.00**		**167,760.00**
1	RRY SERVICES LLC		105.00		195,720.00

Letting Date: June 20, 2019, 10:30 A.M.
Call Order: 820 **Contract ID:** 180107

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0015	412 5267	COLD MILLING PAVEMENT	4,269.000 SY	
	Engineer's Estimate		**10.00**	**42,690.00**
1	RRY SERVICES LLC		8.00	34,152.00
0016	509(D) 0325	CLASS C CONCRETE	10.000 CY	
	Engineer's Estimate		**400.00**	**4,000.00**
1	RRY SERVICES LLC		250.00	2,500.00
0017	601(B) 0536	TYPE I-A PLAIN RIPRAP	785.000 TON	
	Engineer's Estimate		**45.00**	**35,325.00**
1	RRY SERVICES LLC		40.00	31,400.00
0018	601(C) 0538	TYPE I-A FILTER BLANKET	356.000 TON	
	Engineer's Estimate		**40.00**	**14,240.00**
1	RRY SERVICES LLC		35.00	12,460.00
0019	613(B) 0689	18" CORR. GALV. STEEL PIPE	192.000 LF	
	Engineer's Estimate		**30.00**	**5,760.00**
1	RRY SERVICES LLC		45.00	8,640.00
0020	613(M) 7186	TYPE A4 CULVERT END TREATMENT	6.000 EA	
	Engineer's Estimate		**1,200.00**	**7,200.00**
1	RRY SERVICES LLC		1,400.00	8,400.00
0021	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000 LSUM	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	RRY SERVICES LLC		47,000.00	47,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE				
0022	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	260.000 CY	
	Engineer's Estimate		**30.00**	**7,800.00**
1	RRY SERVICES LLC		15.00	3,900.00
0023	501(G) 6309	CLSM BACKFILL	170.000 CY	
	Engineer's Estimate		**150.00**	**25,500.00**
1	RRY SERVICES LLC		135.00	22,950.00
0024	503(A) 6290	PRESTRESSED CONCRETE BEAMS (TYPE J BT)	578.670 LF	
	Engineer's Estimate		**305.00**	**176,494.35**
1	RRY SERVICES LLC		350.00	202,534.50
0025	504(D) 6239	CONCRETE RAIL (TR3)	384.500 LF	
	Engineer's Estimate		**70.00**	**26,915.00**
1	RRY SERVICES LLC		90.00	34,605.00
0026	506(A) 1322	STRUCTURAL STEEL	1,120.000 LB	
	Engineer's Estimate		**5.00**	**5,600.00**
1	RRY SERVICES LLC		2.30	2,576.00

Letting Date: June 20, 2019, 10:30 A.M.
Call Order: 820 **Contract ID:** 180107

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE					
0027	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	4.000	EA	
	Engineer's Estimate		**1,000.00**		**4,000.00**
1	RRY SERVICES LLC		1,300.00		5,200.00
0028	507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	4.000	EA	
	Engineer's Estimate		**1,200.00**		**4,800.00**
1	RRY SERVICES LLC		1,300.00		5,200.00
0029	509(A) 1326	CLASS AA CONCRETE	160.100	CY	
	Engineer's Estimate		**650.00**		**104,065.00**
1	RRY SERVICES LLC		750.00		120,075.00
0030	509(B) 1328	CLASS A CONCRETE	106.200	CY	
	Engineer's Estimate		**650.00**		**69,030.00**
1	RRY SERVICES LLC		750.00		79,650.00
0031	511(A) 1332	REINFORCING STEEL	50,150.000	LB	
	Engineer's Estimate		**1.05**		**52,657.50**
1	RRY SERVICES LLC		1.15		57,672.50
0032	514(A) 6010	PILES, FURNISHED (HP 10X42)	208.000	LF	
	Engineer's Estimate		**40.00**		**8,320.00**
1	RRY SERVICES LLC		35.00		7,280.00
0033	514(A) 6011	PILES, FURNISHED (HP 12X53)	833.000	LF	
	Engineer's Estimate		**50.00**		**41,650.00**
1	RRY SERVICES LLC		45.00		37,485.00
0034	514(B) 6292	PILES, DRIVEN (HP 10X42)	208.000	LF	
	Engineer's Estimate		**15.00**		**3,120.00**
1	RRY SERVICES LLC		10.00		2,080.00
0035	514(B) 6294	PILES, DRIVEN (HP 12X53)	833.000	LF	
	Engineer's Estimate		**20.00**		**16,660.00**
1	RRY SERVICES LLC		10.00		8,330.00
0036	514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA	
	Engineer's Estimate		**400.00**		**400.00**
1	RRY SERVICES LLC		400.00		400.00
0037	601(B) 1353	TYPE I-A PLAIN RIPRAP	4,264.000	TON	
	Engineer's Estimate		**45.00**		**191,880.00**
1	RRY SERVICES LLC		38.00		162,032.00
0038	601(C) 1355	TYPE I-A FILTER BLANKET	1,033.000	TON	
	Engineer's Estimate		**40.00**		**41,320.00**
1	RRY SERVICES LLC		33.00		34,089.00
0039	613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	72.000	LF	
	Engineer's Estimate		**30.00**		**2,160.00**
1	RRY SERVICES LLC		35.00		2,520.00
0040	613(I) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	40.000	LF	
	Engineer's Estimate		**20.00**		**800.00**
1	RRY SERVICES LLC		35.00		1,400.00

Letting Date: June 20, 2019, 10:30 A.M.
Call Order: 820 **Contract ID:** 180107

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0002**	**BRIDGE**	
0041	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM
	Engineer's Estimate	**10,000.00**	**10,000.00**
1	RRY SERVICES LLC	10,000.00	10,000.00
0042	623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000 EA
	Engineer's Estimate	**2,500.00**	**10,000.00**
1	RRY SERVICES LLC	1,400.00	5,600.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0003**	**TRAFFIC**	
0043	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	40.000 LF
	Engineer's Estimate	**25.00**	**1,000.00**
1	RRY SERVICES LLC	38.00	1,520.00
0044	623(G) 8571	GUARDRAIL END TREATMENT (GET)	4.000 EA
	Engineer's Estimate	**2,600.00**	**10,400.00**
1	RRY SERVICES LLC	2,600.00	10,400.00
0045	850(A) 8110	SHEET ALUMINUM SIGNS	18.000 SF
	Engineer's Estimate	**50.00**	**900.00**
1	RRY SERVICES LLC	20.00	360.00
0046	851(C) 8324	2" SQUARE TUBE POST	28.000 LF
	Engineer's Estimate	**20.00**	**560.00**
1	RRY SERVICES LLC	10.00	280.00
0047	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	20,200.000 LF
	Engineer's Estimate	**0.70**	**14,140.00**
1	RRY SERVICES LLC	0.50	10,100.00
0048	880(C) 8845	BARRICADES(TYPE III)	2.000 EA
	Engineer's Estimate	**1,000.00**	**2,000.00**
1	RRY SERVICES LLC	750.00	1,500.00
0049	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**3,000.00**	**3,000.00**
1	RRY SERVICES LLC	3,500.00	3,500.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0004**	**STAKING**	
0050	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**8,000.00**	**8,000.00**
1	RRY SERVICES LLC	23,599.00	23,599.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0005**	**CONSTRUCTION**	

Letting Date: June 20, 2019, 10:30 A.M.

Call Order: 820 **Contract ID:** 180107

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0005**	**CONSTRUCTION**	
0051	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	RRY SERVICES LLC	500.00	500.00
0052	640(A) 1398	FIELD OFFICE	1.000 EA
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	RRY SERVICES LLC	1,200.00	1,200.00
0053	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**120,844.00**	**120,844.00**
1	RRY SERVICES LLC	125,000.00	125,000.00