Letting Date: March 15, 2018, 10:30 A.M.
Call Order: 800 **Contract ID:** 180140
J/P No.: 32991(04) **Project No.:** TAP-256D(043)TP **Contract Time:**
County: OKMULGEE
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALKS) CITY STREET (OKMULGEE AVENUE): FROM 6TH STREET, EXTEND NORTH IN THE CITY OF OKMULGEE.

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	674,577.66		
1	CROSSLAND HEAVY CONTRACTORS INC.	772,000.00	114.44	100.00
2	EARTH SMART CONSTRUCTION INC.	784,079.25	116.23	101.56

Letting Date: March 15, 2018, 10:30 A.M.
Call Order: 800 **Contract ID:** 180140

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	202(A) 0183	UNCLASSIFIED EXCAVATION	250.000	CY	
	Engineer's Estimate		**18.00**		**4,500.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		24.00		6,000.00
2	EARTH SMART CONSTRUCTION INC.		20.00		5,000.00
0002	202(D) 0184	UNCLASSIFIED BORROW	250.000	CY	
	Engineer's Estimate		**18.00**		**4,500.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		19.00		4,750.00
2	EARTH SMART CONSTRUCTION INC.		20.00		5,000.00
0003	221(C) 2801	TEMPORARY SILT FENCE	7,714.800	LF	
	Engineer's Estimate		**2.25**		**17,358.30**
1	CROSSLAND HEAVY CONTRACTORS INC.		1.10		8,486.28
2	EARTH SMART CONSTRUCTION INC.		3.25		25,073.10
0004	230(A) 2806	SOLID SLAB SODDING	5,402.000	SY	
	Engineer's Estimate		**4.00**		**21,608.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		3.50		18,907.00
2	EARTH SMART CONSTRUCTION INC.		6.00		32,412.00
0005	240(A) 2830	REMOVING TREES 19" TO 24" IN DIAMETER	2.000	EA	
	Engineer's Estimate		**1,100.00**		**2,200.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		2,475.00		4,950.00
2	EARTH SMART CONSTRUCTION INC.		2,000.00		4,000.00
0006	303(A) 2100	AGGREGATE BASE TYPE A	237.300	CY	
	Engineer's Estimate		**48.00**		**11,390.40**
1	CROSSLAND HEAVY CONTRACTORS INC.		90.00		21,357.00
2	EARTH SMART CONSTRUCTION INC.		70.00		16,611.00
0007	325 5271	SEPARATOR FABRIC	250.000	SY	
	Engineer's Estimate		**7.00**		**1,750.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		1.90		475.00
2	EARTH SMART CONSTRUCTION INC.		6.00		1,500.00
0008	326(B) 0100	GEOGRID REINFORCEMENT	250.000	SY	
	Engineer's Estimate		**8.50**		**2,125.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		2.10		525.00
2	EARTH SMART CONSTRUCTION INC.		6.00		1,500.00
0009	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	16.800	TON	
	Engineer's Estimate		**120.00**		**2,016.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		200.00		3,360.00
2	EARTH SMART CONSTRUCTION INC.		400.00		6,720.00
0010	414(E) 0225	FULL DEPTH P.C. CONCRETE PATCHING(PLACEMENT ONLY)	210.400	SY	
	Engineer's Estimate		**42.50**		**8,942.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		52.00		10,940.80
2	EARTH SMART CONSTRUCTION INC.		120.00		25,248.00
0011	414(F) 0230	PARTIAL DEPTH P.C. CONCRETE PATCHING(PLACEMENT ONLY)	100.000	SY	
	Engineer's Estimate		**42.50**		**4,250.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		47.00		4,700.00
2	EARTH SMART CONSTRUCTION INC.		90.00		9,000.00

Letting Date: March 15, 2018, 10:30 A.M.
Call Order: 800 **Contract ID:** 180140

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0012	414(G) 5275	P.C. CONCRETE FOR PAVEMENT	63.400	CY	
	Engineer's Estimate		**130.00**		**8,242.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		200.00		12,680.00
2	EARTH SMART CONSTRUCTION INC.		300.00		19,020.00
0013	609(B) 0383	COMBINED CURB & GUTTER (6" BARRIER)	89.600	LF	
	Engineer's Estimate		**23.00**		**2,060.80**
1	CROSSLAND HEAVY CONTRACTORS INC.		30.00		2,688.00
2	EARTH SMART CONSTRUCTION INC.		60.00		5,376.00
0014	609(C) 4809	CONCRETE HEADER CURB (6"X 16")	497.900	LF	
	Engineer's Estimate		**23.00**		**11,451.70**
1	CROSSLAND HEAVY CONTRACTORS INC.		32.00		15,932.80
2	EARTH SMART CONSTRUCTION INC.		60.00		29,874.00
0015	610(A) 0602	4" CONCRETE SIDEWALK	4,733.300	SY	
	Engineer's Estimate		**49.00**		**231,931.70**
1	CROSSLAND HEAVY CONTRACTORS INC.		63.00		298,197.90
2	EARTH SMART CONSTRUCTION INC.		53.00		250,864.90
0016	610(B) 0399	6" CONCRETE DRIVEWAY (H.E.S.)	1,112.000	SY	
	Engineer's Estimate		**75.00**		**83,400.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		95.00		105,640.00
2	EARTH SMART CONSTRUCTION INC.		70.00		77,840.00
0017	610(I) 4610	TACTILE WARNING DEVICE-NEW	596.300	SF	
	Engineer's Estimate		**45.00**		**26,833.50**
1	CROSSLAND HEAVY CONTRACTORS INC.		18.00		10,733.40
2	EARTH SMART CONSTRUCTION INC.		30.00		17,889.00
0018	612(A) 0641	MANHOLES ADJUST TO GRADE	1.000	EA	
	Engineer's Estimate		**1,200.00**		**1,200.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		1,300.00		1,300.00
2	EARTH SMART CONSTRUCTION INC.		2,200.00		2,200.00
0019	612(D) 0646	INLET REBUILT	4.000	EA	
	Engineer's Estimate		**5,000.00**		**20,000.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		4,200.00		16,800.00
2	EARTH SMART CONSTRUCTION INC.		8,000.00		32,000.00
0020	612(F) 0648	METER BOXES ADJUST TO GRADE	3.000	EA	
	Engineer's Estimate		**1,000.00**		**3,000.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		1,000.00		3,000.00
2	EARTH SMART CONSTRUCTION INC.		1,200.00		3,600.00
0021	612(G) 0650	FIRE HYDRANT RESET	1.000	EA	
	Engineer's Estimate		**3,300.00**		**3,300.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		800.00		800.00
2	EARTH SMART CONSTRUCTION INC.		2,800.00		2,800.00
0022	612(H) 0651	VALVE RESET	2.000	EA	
	Engineer's Estimate		**750.00**		**1,500.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		1,300.00		2,600.00
2	EARTH SMART CONSTRUCTION INC.		2,400.00		4,800.00

Letting Date: March 15, 2018, 10:30 A.M.
Call Order: 800 **Contract ID:** 180140

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0023	613(B) 0689	18" CORR. GALV. STEEL PIPE	16.000 LF	
	Engineer's Estimate		**150.00**	**2,400.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		95.00	1,520.00
2	EARTH SMART CONSTRUCTION INC.		60.00	960.00
0024	613(P) 0760	18" GALV. STEEL CULVERT END SECTION ROUND	3.000 EA	
	Engineer's Estimate		**500.00**	**1,500.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		375.00	1,125.00
2	EARTH SMART CONSTRUCTION INC.		500.00	1,500.00
0025	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000 LSUM	
	Engineer's Estimate		**500.00**	**500.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		35,000.00	35,000.00
2	EARTH SMART CONSTRUCTION INC.		16,000.00	16,000.00
0026	619(B) 4763	REMOVAL OF CONCRETE PAVEMENT W/ASPHALT OVERLAY	380.100 SY	
	Engineer's Estimate		**14.00**	**5,321.40**
1	CROSSLAND HEAVY CONTRACTORS INC.		17.00	6,461.70
2	EARTH SMART CONSTRUCTION INC.		12.00	4,561.20
0027	619(B) 4766	REMOVAL OF CONCRETE DRIVEWAY	749.300 SY	
	Engineer's Estimate		**12.00**	**8,991.60**
1	CROSSLAND HEAVY CONTRACTORS INC.		14.50	10,864.85
2	EARTH SMART CONSTRUCTION INC.		12.00	8,991.60
0028	619(B) 4791	REMOVAL OF CURB	649.600 LF	
	Engineer's Estimate		**10.00**	**6,496.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		4.50	2,923.20
2	EARTH SMART CONSTRUCTION INC.		6.00	3,897.60
0029	619(B) 4792	REMOVAL OF SIDEWALK	2,673.100 SY	
	Engineer's Estimate		**5.00**	**13,365.50**
1	CROSSLAND HEAVY CONTRACTORS INC.		9.00	24,057.90
2	EARTH SMART CONSTRUCTION INC.		8.00	21,384.80
0030	625(B) 1252	REMOVE AND RECONSTRUCT FENCE	8.000 LF	
	Engineer's Estimate		**15.00**	**120.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		40.00	320.00
2	EARTH SMART CONSTRUCTION INC.		150.00	1,200.00
0031	632 0300	(PL) SITESCAPING	1.000 LSUM	
	Engineer's Estimate		**2,700.00**	**2,700.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		2,750.00	2,750.00
2	EARTH SMART CONSTRUCTION INC.		6,500.00	6,500.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE**			
0032	535 6785	PREFABRICATED PEDESTRIAN BRIDGE	1.000 EA	
	Engineer's Estimate		**66,500.00**	**66,500.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		52,000.00	52,000.00
2	EARTH SMART CONSTRUCTION INC.		44,000.00	44,000.00

Letting Date: March 15, 2018, 10:30 A.M.
Call Order: 800 **Contract ID:** 180140

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0003 TRAFFIC					
0033	805(D) 8756	(PL)REMOVE & RESET EXISTING SIGNS	25.000	EA	
	Engineer's Estimate		**100.00**		**2,500.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		120.00		3,000.00
2	EARTH SMART CONSTRUCTION INC.		150.00		3,750.00
0034	850(A) 8110	SHEET ALUMINUM SIGNS	193.500	SF	
	Engineer's Estimate		**25.00**		**4,837.50**
1	CROSSLAND HEAVY CONTRACTORS INC.		30.00		5,805.00
2	EARTH SMART CONSTRUCTION INC.		25.00		4,837.50
0035	851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	276.000	LF	
	Engineer's Estimate		**15.00**		**4,140.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		12.00		3,312.00
2	EARTH SMART CONSTRUCTION INC.		8.50		2,346.00
0036	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	73.500	LF	
	Engineer's Estimate		**1.00**		**73.50**
1	CROSSLAND HEAVY CONTRACTORS INC.		2.50		183.75
2	EARTH SMART CONSTRUCTION INC.		2.50		183.75
0037	856(A) 8555	TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	1,403.000	LF	
	Engineer's Estimate		**4.00**		**5,612.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		12.00		16,836.00
2	EARTH SMART CONSTRUCTION INC.		9.00		12,627.00
0038	856(B) 8870	TRAFFIC STRIPE(MULTI-POLY.)(SYMBOLS)	4.000	EA	
	Engineer's Estimate		**750.00**		**3,000.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		300.00		1,200.00
2	EARTH SMART CONSTRUCTION INC.		2,800.00		11,200.00
0039	857(F) 8006	PAVEMENT MARKING REMOVAL(TRAFFIC STRIPE)	580.400	LF	
	Engineer's Estimate		**1.00**		**580.40**
1	CROSSLAND HEAVY CONTRACTORS INC.		1.20		696.48
2	EARTH SMART CONSTRUCTION INC.		4.00		2,321.60
0040	880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	336.000	SD	
	Engineer's Estimate		**1.00**		**336.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		0.60		201.60
2	EARTH SMART CONSTRUCTION INC.		2.50		840.00
0041	880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	168.000	SD	
	Engineer's Estimate		**1.50**		**252.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		2.50		420.00
2	EARTH SMART CONSTRUCTION INC.		5.50		924.00
0042	880(C) 8836	CONSTRUCTION BARRICADES(TYPE II)	504.000	SD	
	Engineer's Estimate		**2.00**		**1,008.00**
1	CROSSLAND HEAVY CONTRACTORS INC.		0.60		302.40
2	EARTH SMART CONSTRUCTION INC.		0.40		201.60
0043	880(E) 8860	WARNING LIGHTS(TYPE A)	3,654.000	SD	
	Engineer's Estimate		**0.70**		**2,557.80**
1	CROSSLAND HEAVY CONTRACTORS INC.		0.30		1,096.20
2	EARTH SMART CONSTRUCTION INC.		0.15		548.10

Letting Date: March 15, 2018, 10:30 A.M.
Call Order: 800 **Contract ID:** 180140

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 TRAFFIC			
0044	880(F) 8878	DRUMS	3,150.000 SD
	Engineer's Estimate	**0.30**	**945.00**
1	CROSSLAND HEAVY CONTRACTORS INC.	0.70	2,205.00
2	EARTH SMART CONSTRUCTION INC.	0.15	472.50
0045	880(G) 8890	CHANNELIZER CONES	1,680.000 SD
	Engineer's Estimate	**0.50**	**840.00**
1	CROSSLAND HEAVY CONTRACTORS INC.	0.70	1,176.00
2	EARTH SMART CONSTRUCTION INC.	0.30	504.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004 STAKING			
0046	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**15,000.00**	**15,000.00**
1	CROSSLAND HEAVY CONTRACTORS INC.	3,500.00	3,500.00
2	EARTH SMART CONSTRUCTION INC.	17,000.00	17,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0005 CONSTRUCTION			
0047	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**5,000.00**	**5,000.00**
1	CROSSLAND HEAVY CONTRACTORS INC.	500.00	500.00
2	EARTH SMART CONSTRUCTION INC.	4,000.00	4,000.00
0048	641 1552	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**46,441.56**	**46,441.56**
1	CROSSLAND HEAVY CONTRACTORS INC.	39,719.74	39,719.74
2	EARTH SMART CONSTRUCTION INC.	35,000.00	35,000.00