Letting Date: November 15, 2018, 10:30 A.M.
Call Order: 525 **Contract ID:** 180227
J/P No.: 29867(04) **Project No.:** CIRB-252D(019)RB **Contract Time:**
County: NOBLE
Description: BRIDGE AND APPROACHES COUNTY ROAD (NS-330): OVER MULE CREEK, 1.3 MILES NORTH OF THE US-64 JUNCTION NEAR SUMNER. PROJECT LENGTH = 0.170 MILE

	VENDORNAME	PROPOSALITEMTO		
1	B & B BRIDGE COMPANY, LLC	429,155.24	95.44	100.00
	Engineer's Estimate	449,663.96		
2	RRY SERVICES LLC	465,764.84	103.58	108.53
3	Reece Construction Co, Inc.	498,472.94	110.85	116.15

Letting Date: November 15, 2018, 10:30 A.M.
Call Order: 525 **Contract ID:** 180227

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	202(H) 0185	EARTHWORK	1.000 LSUM	
	Engineer's Estimate		**30,000.00**	**30,000.00**
1	B & B BRIDGE COMPANY, LLC		39,053.00	39,053.00
2	RRY SERVICES LLC		18,000.00	18,000.00
3	Reece Construction Co, Inc.		39,053.00	39,053.00
0002	221(C) 2801	TEMPORARY SILT FENCE	2,100.000 LF	
	Engineer's Estimate		**1.90**	**3,990.00**
1	B & B BRIDGE COMPANY, LLC		2.07	4,347.00
2	RRY SERVICES LLC		2.07	4,347.00
3	Reece Construction Co, Inc.		2.07	4,347.00
0003	221(F) 0100	TEMPORARY SILT DIKE	308.000 LF	
	Engineer's Estimate		**11.50**	**3,542.00**
1	B & B BRIDGE COMPANY, LLC		9.48	2,919.84
2	RRY SERVICES LLC		9.48	2,919.84
3	Reece Construction Co, Inc.		9.48	2,919.84
0004	230(A) 2806	SOLID SLAB SODDING	6,100.000 SY	
	Engineer's Estimate		**2.50**	**15,250.00**
1	B & B BRIDGE COMPANY, LLC		2.49	15,189.00
2	RRY SERVICES LLC		2.49	15,189.00
3	Reece Construction Co, Inc.		2.49	15,189.00
0005	233(A) 2817	VEGETATIVE MULCHING	1.260 AC	
	Engineer's Estimate		**650.00**	**819.00**
1	B & B BRIDGE COMPANY, LLC		1,650.00	2,079.00
2	RRY SERVICES LLC		1,650.00	2,079.00
3	Reece Construction Co, Inc.		1,650.00	2,079.00
0006	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	606.000 TON	
	Engineer's Estimate		**39.20**	**23,755.20**
1	B & B BRIDGE COMPANY, LLC		4.65	2,817.90
2	RRY SERVICES LLC		35.00	21,210.00
3	Reece Construction Co, Inc.		4.65	2,817.90
0007	509(D) 0325	CLASS C CONCRETE	10.000 CY	
	Engineer's Estimate		**400.00**	**4,000.00**
1	B & B BRIDGE COMPANY, LLC		300.00	3,000.00
2	RRY SERVICES LLC		250.00	2,500.00
3	Reece Construction Co, Inc.		455.00	4,550.00
0008	613(L) 5732	30" PREFAB. CULVERT END SECTION, ROUND	2.000 EA	
	Engineer's Estimate		**891.10**	**1,782.20**
1	B & B BRIDGE COMPANY, LLC		2,500.00	5,000.00
2	RRY SERVICES LLC		1,000.00	2,000.00
3	Reece Construction Co, Inc.		2,500.00	5,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE**			

Letting Date: November 15, 2018, 10:30 A.M.
Call Order: 525 **Contract ID:** 180227

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE					
0009	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	292.000	CY	
	Engineer's Estimate		**15.00**		**4,380.00**
1	B & B BRIDGE COMPANY, LLC		20.00		5,840.00
2	RRY SERVICES LLC		15.00		4,380.00
3	Reece Construction Co, Inc.		25.00		7,300.00
0010	501(F) 6352	GRANULAR BACKFILL	148.000	CY	
	Engineer's Estimate		**75.10**		**11,114.80**
1	B & B BRIDGE COMPANY, LLC		50.00		7,400.00
2	RRY SERVICES LLC		85.00		12,580.00
3	Reece Construction Co, Inc.		96.00		14,208.00
0011	504(D) 6239	CONCRETE RAIL (TR3)	126.400	LF	
	Engineer's Estimate		**80.00**		**10,112.00**
1	B & B BRIDGE COMPANY, LLC		110.00		13,904.00
2	RRY SERVICES LLC		100.00		12,640.00
3	Reece Construction Co, Inc.		144.00		18,201.60
0012	506(A) 1322	STRUCTURAL STEEL	6,010.000	LB	
	Engineer's Estimate		**7.50**		**45,075.00**
1	B & B BRIDGE COMPANY, LLC		8.50		51,085.00
2	RRY SERVICES LLC		5.00		30,050.00
3	Reece Construction Co, Inc.		10.00		60,100.00
0013	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	5.000	EA	
	Engineer's Estimate		**600.00**		**3,000.00**
1	B & B BRIDGE COMPANY, LLC		750.00		3,750.00
2	RRY SERVICES LLC		1,200.00		6,000.00
3	Reece Construction Co, Inc.		1,206.00		6,030.00
0014	507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	5.000	EA	
	Engineer's Estimate		**600.00**		**3,000.00**
1	B & B BRIDGE COMPANY, LLC		750.00		3,750.00
2	RRY SERVICES LLC		1,200.00		6,000.00
3	Reece Construction Co, Inc.		1,206.00		6,030.00
0015	509(A) 1326	CLASS AA CONCRETE	47.500	CY	
	Engineer's Estimate		**710.20**		**33,734.50**
1	B & B BRIDGE COMPANY, LLC		400.00		19,000.00
2	RRY SERVICES LLC		700.00		33,250.00
3	Reece Construction Co, Inc.		828.00		39,330.00
0016	509(B) 1328	CLASS A CONCRETE	145.400	CY	
	Engineer's Estimate		**576.40**		**83,808.56**
1	B & B BRIDGE COMPANY, LLC		400.00		58,160.00
2	RRY SERVICES LLC		550.00		79,970.00
3	Reece Construction Co, Inc.		549.00		79,824.60
0017	511(A) 1332	REINFORCING STEEL	32,530.000	LB	
	Engineer's Estimate		**1.00**		**32,530.00**
1	B & B BRIDGE COMPANY, LLC		0.85		27,650.50
2	RRY SERVICES LLC		1.00		32,530.00
3	Reece Construction Co, Inc.		0.80		26,024.00

Letting Date: November 15, 2018, 10:30 A.M.
Call Order: 525 **Contract ID:** 180227

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE					
0018	514(A) 6010	PILES, FURNISHED (HP 10X42)	226.000	LF	
	Engineer's Estimate		**28.00**		**6,328.00**
1	B & B BRIDGE COMPANY, LLC		35.00		7,910.00
2	RRY SERVICES LLC		45.00		10,170.00
3	Reece Construction Co, Inc.		42.00		9,492.00
0019	514(A) 6011	PILES, FURNISHED (HP 12X53)	515.000	LF	
	Engineer's Estimate		**34.00**		**17,510.00**
1	B & B BRIDGE COMPANY, LLC		42.00		21,630.00
2	RRY SERVICES LLC		55.00		28,325.00
3	Reece Construction Co, Inc.		53.00		27,295.00
0020	514(B) 6292	PILES, DRIVEN (HP 10X42)	226.000	LF	
	Engineer's Estimate		**13.10**		**2,960.60**
1	B & B BRIDGE COMPANY, LLC		15.00		3,390.00
2	RRY SERVICES LLC		10.00		2,260.00
3	Reece Construction Co, Inc.		14.00		3,164.00
0021	514(B) 6294	PILES, DRIVEN (HP 12X53)	515.000	LF	
	Engineer's Estimate		**14.50**		**7,467.50**
1	B & B BRIDGE COMPANY, LLC		18.00		9,270.00
2	RRY SERVICES LLC		10.00		5,150.00
3	Reece Construction Co, Inc.		14.00		7,210.00
0022	514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA	
	Engineer's Estimate		**400.00**		**400.00**
1	B & B BRIDGE COMPANY, LLC		400.00		400.00
2	RRY SERVICES LLC		400.00		400.00
3	Reece Construction Co, Inc.		400.00		400.00
0023	535 6225	HAUL AND ERECT STEEL BEAMS	1.000	LSUM	
	Engineer's Estimate		**10,000.00**		**10,000.00**
1	B & B BRIDGE COMPANY, LLC		20,000.00		20,000.00
2	RRY SERVICES LLC		15,000.00		15,000.00
3	Reece Construction Co, Inc.		11,228.00		11,228.00
0024	601(B) 1353	TYPE I-A PLAIN RIPRAP	448.000	TON	
	Engineer's Estimate		**50.50**		**22,624.00**
1	B & B BRIDGE COMPANY, LLC		35.00		15,680.00
2	RRY SERVICES LLC		65.00		29,120.00
3	Reece Construction Co, Inc.		50.00		22,400.00
0025	601(C) 1355	TYPE I-A FILTER BLANKET	150.000	TON	
	Engineer's Estimate		**40.30**		**6,045.00**
1	B & B BRIDGE COMPANY, LLC		30.00		4,500.00
2	RRY SERVICES LLC		48.00		7,200.00
3	Reece Construction Co, Inc.		60.00		9,000.00
0026	613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	52.000	LF	
	Engineer's Estimate		**29.30**		**1,523.60**
1	B & B BRIDGE COMPANY, LLC		50.00		2,600.00
2	RRY SERVICES LLC		35.00		1,820.00
3	Reece Construction Co, Inc.		45.00		2,340.00

Letting Date: November 15, 2018, 10:30 A.M.
Call Order: 525 **Contract ID:** 180227

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002	**BRIDGE**		
0027	613(I) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	40.000 LF
	Engineer's Estimate	**25.30**	**1,012.00**
1	B & B BRIDGE COMPANY, LLC	40.00	1,600.00
2	RRY SERVICES LLC	35.00	1,400.00
3	Reece Construction Co, Inc.	29.00	1,160.00
0028	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM
	Engineer's Estimate	**5,500.00**	**5,500.00**
1	B & B BRIDGE COMPANY, LLC	10,000.00	10,000.00
2	RRY SERVICES LLC	9,000.00	9,000.00
3	Reece Construction Co, Inc.	10,000.00	10,000.00
0029	623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000 EA
	Engineer's Estimate	**1,600.00**	**6,400.00**
1	B & B BRIDGE COMPANY, LLC	2,195.00	8,780.00
2	RRY SERVICES LLC	1,500.00	6,000.00
3	Reece Construction Co, Inc.	2,195.00	8,780.00
0030	623(F) 6029	GUARDRAIL ANCHOR UNIT (TYPE A)	4.000 EA
	Engineer's Estimate	**1,500.00**	**6,000.00**
1	B & B BRIDGE COMPANY, LLC	1,100.00	4,400.00
2	RRY SERVICES LLC	1,925.00	7,700.00
3	Reece Construction Co, Inc.	1,100.00	4,400.00
0031	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**3,000.00**	**3,000.00**
1	B & B BRIDGE COMPANY, LLC	2,450.00	2,450.00
2	RRY SERVICES LLC	2,200.00	2,200.00
3	Reece Construction Co, Inc.	2,450.00	2,450.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003	**STAKING**		
0032	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**6,000.00**	**6,000.00**
1	B & B BRIDGE COMPANY, LLC	7,500.00	7,500.00
2	RRY SERVICES LLC	5,100.00	5,100.00
3	Reece Construction Co, Inc.	5,100.00	5,100.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004	**CONSTRUCTION**		
0033	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**2,000.00**	**2,000.00**
1	B & B BRIDGE COMPANY, LLC	2,000.00	2,000.00
2	RRY SERVICES LLC	1,275.00	1,275.00
3	Reece Construction Co, Inc.	2,000.00	2,000.00

Letting Date: November 15, 2018, 10:30 A.M.

Call Order: 525 **Contract ID:** 180227

Line #	Item Number	Item Description	Quantity/Unit
	Bidder		Unit Price / Ext Amount
Section:	**0004**	**CONSTRUCTION**	
0034	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate		**35,000.00** / **35,000.00**
1	B & B BRIDGE COMPANY, LLC		42,100.00 / 42,100.00
2	RRY SERVICES LLC		48,000.00 / 48,000.00
3	Reece Construction Co, Inc.		39,050.00 / 39,050.00