Letting Date: May 16, 2019, 10:30 A.M.
Call Order: 424 **Contract ID:** 190004
J/P No.: 31219(04) **Project No.:** CIRB-212D(044)RB **Contract Time:**
County: CHOCTAW
Description: BRIDGE AND APPROACHES COUNTY ROAD (EW-207): OVER UNNAMED CREEK, 0.6 MILES EAST OF SH-93 NEAR HUGO. PROJECT LENGTH = 0.176 MILE

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	448,481.93		
1	HUB Construction, Inc.	449,234.32	100.17	100.00
2	RRY SERVICES LLC	610,721.20	136.18	135.95

Letting Date: May 16, 2019, 10:30 A.M.
Call Order: 424 **Contract ID:** 190004

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0001	201(A) 0102	CLEARING AND GRUBBING	1.000 LSUM	
	Engineer's Estimate		**8,000.00**	**8,000.00**
1	HUB Construction, Inc.		12,000.00	12,000.00
2	RRY SERVICES LLC		28,000.00	28,000.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	3,483.520 CY	
	Engineer's Estimate		**7.03**	**24,489.15**
1	HUB Construction, Inc.		8.00	27,868.16
2	RRY SERVICES LLC		15.00	52,252.80
0003	202(D) 0184	UNCLASSIFIED BORROW	1,435.560 CY	
	Engineer's Estimate		**9.43**	**13,537.33**
1	HUB Construction, Inc.		12.50	17,944.50
2	RRY SERVICES LLC		15.00	21,533.40
0004	221(C) 2801	TEMPORARY SILT FENCE	1,749.000 LF	
	Engineer's Estimate		**1.69**	**2,955.81**
1	HUB Construction, Inc.		6.00	10,494.00
2	RRY SERVICES LLC		3.79	6,628.71
0005	221(F) 0100	TEMPORARY SILT DIKE	48.000 LF	
	Engineer's Estimate		**6.00**	**288.00**
1	HUB Construction, Inc.		11.00	528.00
2	RRY SERVICES LLC		24.98	1,199.04
0006	230(A) 2806	SOLID SLAB SODDING	6,845.000 SY	
	Engineer's Estimate		**3.50**	**23,957.50**
1	HUB Construction, Inc.		4.00	27,380.00
2	RRY SERVICES LLC		6.85	46,888.25
0007	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	842.000 TON	
	Engineer's Estimate		**21.82**	**18,372.44**
1	HUB Construction, Inc.		24.00	20,208.00
2	RRY SERVICES LLC		35.00	29,470.00
0008	509(D) 0325	CLASS C CONCRETE	8.500 CY	
	Engineer's Estimate		**600.00**	**5,100.00**
1	HUB Construction, Inc.		250.00	2,125.00
2	RRY SERVICES LLC		300.00	2,550.00
0009	613(EE) 5680	(SP) 60" CORRUGATED POLYPROPYLENE PIPE	99.000 LF	
	Engineer's Estimate		**200.00**	**19,800.00**
1	HUB Construction, Inc.		214.34	21,219.66
2	RRY SERVICES LLC		350.00	34,650.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**BRIDGE**			
0010	202(A) 1301	UNCLASSIFIED EXCAVATION	1,050.000 CY	
	Engineer's Estimate		**7.03**	**7,381.50**
1	HUB Construction, Inc.		10.00	10,500.00
2	RRY SERVICES LLC		20.00	21,000.00

Letting Date: May 16, 2019, 10:30 A.M.
Call Order: 424 **Contract ID:** 190004

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**BRIDGE**		
0011	501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	74.000	CY
	Engineer's Estimate		**22.50**	**1,665.00**
1	HUB Construction, Inc.		20.00	1,480.00
2	RRY SERVICES LLC		25.00	1,850.00
0012	509(A) 1326	CLASS AA CONCRETE	272.100	CY
	Engineer's Estimate		**702.00**	**191,014.20**
1	HUB Construction, Inc.		650.00	176,865.00
2	RRY SERVICES LLC		740.00	201,354.00
0013	511(A) 1332	REINFORCING STEEL	47,240.000	LB
	Engineer's Estimate		**0.90**	**42,516.00**
1	HUB Construction, Inc.		1.05	49,602.00
2	RRY SERVICES LLC		1.10	51,964.00
0014	601(B) 1353	TYPE I-A PLAIN RIPRAP	410.000	TON
	Engineer's Estimate		**45.00**	**18,450.00**
1	HUB Construction, Inc.		40.00	16,400.00
2	RRY SERVICES LLC		55.00	22,550.00
0015	601(C) 1355	TYPE I-A FILTER BLANKET	140.000	TON
	Engineer's Estimate		**62.00**	**8,680.00**
1	HUB Construction, Inc.		33.00	4,620.00
2	RRY SERVICES LLC		46.00	6,440.00
0016	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
	Engineer's Estimate		**10,000.00**	**10,000.00**
1	HUB Construction, Inc.		10,000.00	10,000.00
2	RRY SERVICES LLC		20,000.00	20,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0003**	**TRAFFIC**		
0017	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
	Engineer's Estimate		**2,500.00**	**2,500.00**
1	HUB Construction, Inc.		4,000.00	4,000.00
2	RRY SERVICES LLC		2,150.00	2,150.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0004**	**STAKING**		
0018	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
	Engineer's Estimate		**8,500.00**	**8,500.00**
1	HUB Construction, Inc.		6,000.00	6,000.00
2	RRY SERVICES LLC		10,241.00	10,241.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0005**	**CONSTRUCTION**		

Letting Date: May 16, 2019, 10:30 A.M.

Call Order: 424 **Contract ID:** 190004

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0005**	**CONSTRUCTION**		
0019	641 1399	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**41,275.00**	**41,275.00**
1	HUB Construction, Inc.		30,000.00	30,000.00
2	RRY SERVICES LLC		50,000.00	50,000.00