Letting Date: September 19, 2019, 10:30 A.M.
Call Order: 795 **Contract ID:** 190290
J/P No.: 29985(04) **Project No.:** CIRB-248D(039)RB **Contract Time:**
County: MARSHALL
Description: RESURFACE (ASPHALT) COUNTY ROAD (POWELL ROAD): FROM 0.2 MILES SOUTH OF THE SH-32 JUNCTION, EXTEND SOUTH, THEN EAST NEAR LEBANON. PROJECT LENGTH = 4.979 MILES

	VENDORNAME	PROPOSALITEMTO		
1	Overland Corporation	1,628,785.75	86.12	100.00
2	THE CUMMINS CONSTRUCTION CO., INC.	1,889,069.20	99.88	115.98

Letting Date: September 19, 2019, 10:30 A.M.
Call Order: 795 **Contract ID:** 190290

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	202(A) 0183	UNCLASSIFIED EXCAVATION	600.000	CY	
	Engineer's Estimate		**15.00**		**9,000.00**
1	Overland Corporation		36.50		21,900.00
2	THE CUMMINS CONSTRUCTION CO., INC.		10.60		6,360.00
0002	303(A) 2100	AGGREGATE BASE TYPE A	580.000	CY	
	Engineer's Estimate		**46.00**		**26,680.00**
1	Overland Corporation		60.65		35,177.00
2	THE CUMMINS CONSTRUCTION CO., INC.		87.45		50,721.00
0003	307(K) 4300	STABILIZED SUBGRADE	2,700.000	SY	
	Engineer's Estimate		**5.00**		**13,500.00**
1	Overland Corporation		8.50		22,950.00
2	THE CUMMINS CONSTRUCTION CO., INC.		9.50		25,650.00
0004	326(B) 0100	GEOGRID REINFORCEMENT	2,700.000	SY	
	Engineer's Estimate		**1.50**		**4,050.00**
1	Overland Corporation		2.00		5,400.00
2	THE CUMMINS CONSTRUCTION CO., INC.		2.50		6,750.00
0005	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	2,600.000	TON	
	Engineer's Estimate		**24.50**		**63,700.00**
1	Overland Corporation		26.75		69,550.00
2	THE CUMMINS CONSTRUCTION CO., INC.		26.45		68,770.00
0006	407(D) 0401	(SP) NT TACK MATERIAL	10,320.000	GAL	
	Engineer's Estimate		**2.00**		**20,640.00**
1	Overland Corporation		2.00		20,640.00
2	THE CUMMINS CONSTRUCTION CO., INC.		3.60		37,152.00
0007	408 5774	PRIME COAT	620.000	GAL	
	Engineer's Estimate		**3.00**		**1,860.00**
1	Overland Corporation		2.00		1,240.00
2	THE CUMMINS CONSTRUCTION CO., INC.		3.85		2,387.00
0008	411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	550.000	TON	
	Engineer's Estimate		**70.00**		**38,500.00**
1	Overland Corporation		71.05		39,077.50
2	THE CUMMINS CONSTRUCTION CO., INC.		97.85		53,817.50
0009	411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	14,670.000	TON	
	Engineer's Estimate		**85.00**		**1,246,950.00**
1	Overland Corporation		74.70		1,095,849.00
2	THE CUMMINS CONSTRUCTION CO., INC.		84.90		1,245,483.00
0010	411(H) 6210	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,000.000	TON	
	Engineer's Estimate		**105.00**		**105,000.00**
1	Overland Corporation		120.75		120,750.00
2	THE CUMMINS CONSTRUCTION CO., INC.		97.85		97,850.00
0011	412 5267	COLD MILLING PAVEMENT	5,790.000	SY	
	Engineer's Estimate		**10.00**		**57,900.00**
1	Overland Corporation		1.95		11,290.50
2	THE CUMMINS CONSTRUCTION CO., INC.		3.65		21,133.50

Letting Date: September 19, 2019, 10:30 A.M.
Call Order: 795 **Contract ID:** 190290

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0001**	**ROADWAY**		
0012	501(A) 0313	STRUCTURAL EXCAVATION UNCLASSIFIED	50.000 CY	
	Engineer's Estimate		**40.00**	**2,000.00**
1	Overland Corporation		72.20	3,610.00
2	THE CUMMINS CONSTRUCTION CO., INC.		53.00	2,650.00
0013	501(G) 6315	CLSM BACKFILL	50.000 CY	
	Engineer's Estimate		**200.00**	**10,000.00**
1	Overland Corporation		191.60	9,580.00
2	THE CUMMINS CONSTRUCTION CO., INC.		151.00	7,550.00
0014	619(B) 4780	REMOVAL OF GUARDRAIL	800.000 LF	
	Engineer's Estimate		**7.00**	**5,600.00**
1	Overland Corporation		4.25	3,400.00
2	THE CUMMINS CONSTRUCTION CO., INC.		4.00	3,200.00
0015	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	150.000 LF	
	Engineer's Estimate		**26.00**	**3,900.00**
1	Overland Corporation		19.10	2,865.00
2	THE CUMMINS CONSTRUCTION CO., INC.		18.00	2,700.00
0016	623(F) 4446	GUARDRAIL ANCHOR UNIT (TYPE A)	24.000 EA	
	Engineer's Estimate		**2,000.00**	**48,000.00**
1	Overland Corporation		1,590.00	38,160.00
2	THE CUMMINS CONSTRUCTION CO., INC.		1,500.00	36,000.00
0017	623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	12.000 EA	
	Engineer's Estimate		**2,200.00**	**26,400.00**
1	Overland Corporation		1,590.00	19,080.00
2	THE CUMMINS CONSTRUCTION CO., INC.		1,500.00	18,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**BRIDGE**		
0018	504(E) 1381	CONCRETE PARAPET	44.000 LF	
	Engineer's Estimate		**150.00**	**6,600.00**
1	Overland Corporation		272.50	11,990.00
2	THE CUMMINS CONSTRUCTION CO., INC.		300.00	13,200.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0003**	**TRAFFIC**		
0019	850(A) 8110	SHEET ALUMINUM SIGNS	485.000 SF	
	Engineer's Estimate		**18.50**	**8,972.50**
1	Overland Corporation		16.95	8,220.75
2	THE CUMMINS CONSTRUCTION CO., INC.		16.00	7,760.00
0020	851(C) 8324	2" SQUARE TUBE POST	832.000 LF	
	Engineer's Estimate		**10.00**	**8,320.00**
1	Overland Corporation		9.00	7,488.00
2	THE CUMMINS CONSTRUCTION CO., INC.		8.50	7,072.00

Letting Date: September 19, 2019, 10:30 A.M.
Call Order: 795 **Contract ID:** 190290

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003 TRAFFIC			
0021	856(A) 8530	TRAFFIC STRIPE(MULTI-POLYMER)(4" WIDE)	105,480.000 LF
	Engineer's Estimate	**0.50**	**52,740.00**
1	Overland Corporation	0.35	36,918.00
2	THE CUMMINS CONSTRUCTION CO., INC.	0.34	35,863.20
0022	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**2,600.00**	**2,600.00**
1	Overland Corporation	20,200.00	20,200.00
2	THE CUMMINS CONSTRUCTION CO., INC.	24,000.00	24,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004 CONSTRUCTION			
0023	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**3,000.00**	**3,000.00**
1	Overland Corporation	200.00	200.00
2	THE CUMMINS CONSTRUCTION CO., INC.	5,000.00	5,000.00
0024	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**125,372.00**	**125,372.00**
1	Overland Corporation	23,250.00	23,250.00
2	THE CUMMINS CONSTRUCTION CO., INC.	110,000.00	110,000.00