Letting Date: May 14, 2020, 10:30 A.M.
Call Order: 430 **Contract ID:** 190347
J/P No.: 29897(04) **Project No.:** STP-221D(048)CI **Contract Time:**
County: DELAWARE
Description: BRIDGE AND APPROACHES COUNTY ROAD (E550 ROAD): OVER CRAZY CREEK HOLLOW BRIDGE, 3.1 MI WEST OF THE ARKANSAS STATE LINE NEAR WEST SILOAM SPRINGS. PROJECT LENGTH = 0.40 MILE

	VENDORNAME	PROPOSALITEMTO		
1	RRY SERVICES LLC	1,024,867.85	88.68	100.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC	1,124,123.45	97.27	109.68

Letting Date: May 14, 2020, 10:30 A.M.
Call Order: 430 **Contract ID:** 190347

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0001	201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM	
	Engineer's Estimate		**20,000.00**		**20,000.00**
1	RRY SERVICES LLC		10,000.00		10,000.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		50,000.00		50,000.00
0002	202(A) 0183	UNCLASSIFIED EXCAVATION	8,183.000	CY	
	Engineer's Estimate		**15.00**		**122,745.00**
1	RRY SERVICES LLC		11.00		90,013.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		12.00		98,196.00
0003	202(C) 0182	ROCK EXCAVATION	1,000.000	CY	
	Engineer's Estimate		**15.00**		**15,000.00**
1	RRY SERVICES LLC		30.00		30,000.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		60.00		60,000.00
0004	205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM	
	Engineer's Estimate		**5,000.00**		**5,000.00**
1	RRY SERVICES LLC		8,500.00		8,500.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		15,000.00		15,000.00
0005	221(C) 2801	TEMPORARY SILT FENCE	2,047.000	LF	
	Engineer's Estimate		**4.00**		**8,188.00**
1	RRY SERVICES LLC		3.20		6,550.40
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		3.00		6,141.00
0006	221(F) 0100	TEMPORARY SILT DIKE	270.000	LF	
	Engineer's Estimate		**30.00**		**8,100.00**
1	RRY SERVICES LLC		20.50		5,535.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		10.00		2,700.00
0007	230(A) 2806	SOLID SLAB SODDING	9,428.000	SY	
	Engineer's Estimate		**5.00**		**47,140.00**
1	RRY SERVICES LLC		5.35		50,439.80
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		5.25		49,497.00
0008	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	2,031.000	TON	
	Engineer's Estimate		**23.00**		**46,713.00**
1	RRY SERVICES LLC		28.00		56,868.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		25.00		50,775.00
0009	509(D) 0325	CLASS C CONCRETE	10.000	CY	
	Engineer's Estimate		**300.00**		**3,000.00**
1	RRY SERVICES LLC		275.00		2,750.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		300.00		3,000.00
0010	613(B) 0689	18" CORR. GALV. STEEL PIPE	142.000	LF	
	Engineer's Estimate		**35.00**		**4,970.00**
1	RRY SERVICES LLC		45.00		6,390.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		50.00		7,100.00
0011	613(P) 0760	18" GALV. STEEL CULVERT END SECTION ROUND	10.000	EA	
	Engineer's Estimate		**1,500.00**		**15,000.00**
1	RRY SERVICES LLC		375.00		3,750.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		275.00		2,750.00

Letting Date: May 14, 2020, 10:30 A.M.
Call Order: 430 **Contract ID:** 190347

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0012	619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM	
	Engineer's Estimate		**15,000.00**		**15,000.00**
1	RRY SERVICES LLC		5,000.00		5,000.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		20,000.00		20,000.00
0013	623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	150.000	LF	
	Engineer's Estimate		**25.00**		**3,750.00**
1	RRY SERVICES LLC		25.00		3,750.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		35.00		5,250.00
0014	623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA	
	Engineer's Estimate		**1,250.00**		**5,000.00**
1	RRY SERVICES LLC		1,000.00		4,000.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		1,500.00		6,000.00
0015	623(F) 8300	GUARDRAIL TRAIL END TURNDOWN (31")	2.000	EA	
	Engineer's Estimate		**1,500.00**		**3,000.00**
1	RRY SERVICES LLC		1,300.00		2,600.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		1,700.00		3,400.00
0016	623(G) 8571	GUARDRAIL END TREATMENT (GET)	2.000	EA	
	Engineer's Estimate		**3,000.00**		**6,000.00**
1	RRY SERVICES LLC		2,825.00		5,650.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		3,000.00		6,000.00
0017	629(A) 4958	MAILBOX INSTALLATION-SINGLE	1.000	EA	
	Engineer's Estimate		**200.00**		**200.00**
1	RRY SERVICES LLC		100.00		100.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		150.00		150.00
0018	629(C) 4960	MAILBOX	1.000	EA	
	Engineer's Estimate		**75.00**		**75.00**
1	RRY SERVICES LLC		100.00		100.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		150.00		150.00
0019	629(D) 4961	REMOVAL OF MAILBOX INSTALLATION	1.000	EA	
	Engineer's Estimate		**100.00**		**100.00**
1	RRY SERVICES LLC		50.00		50.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		100.00		100.00
0020	850(A) 8110	SHEET ALUMINUM SIGNS	20.360	SF	
	Engineer's Estimate		**35.00**		**712.60**
1	RRY SERVICES LLC		25.00		509.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		30.00		610.80
0021	851(C) 8327	2 1/4" SQUARE TUBE POST	48.000	LF	
	Engineer's Estimate		**12.50**		**600.00**
1	RRY SERVICES LLC		10.00		480.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		15.00		720.00
0022	853 9030	DELINEATORS(TYPE 1, CODE 3)	2.000	EA	
	Engineer's Estimate		**25.00**		**50.00**
1	RRY SERVICES LLC		20.00		40.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		25.00		50.00

Letting Date: May 14, 2020, 10:30 A.M.
Call Order: 430 **Contract ID:** 190347

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0023	853 9033	DELINEATORS(TYPE 2, CODE 1)	8.000 EA	
	Engineer's Estimate		**25.00**	**200.00**
1	RRY SERVICES LLC		20.00	160.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		25.00	200.00
0024	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM	
	Engineer's Estimate		**5,000.00**	**5,000.00**
1	RRY SERVICES LLC		2,400.00	2,400.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		5,000.00	5,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE - NBI NO. 32452				
0025	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	190.000 CY	
	Engineer's Estimate		**30.00**	**5,700.00**
1	RRY SERVICES LLC		15.00	2,850.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		25.00	4,750.00
0026	501(F) 6352	GRANULAR BACKFILL	76.000 CY	
	Engineer's Estimate		**90.00**	**6,840.00**
1	RRY SERVICES LLC		85.00	6,460.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		95.00	7,220.00
0027	503(A) 1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	387.000 LF	
	Engineer's Estimate		**350.00**	**135,450.00**
1	RRY SERVICES LLC		200.00	77,400.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		230.00	89,010.00
0028	504(C) 6250	SEALED EXPANSION JOINT	33.060 LF	
	Engineer's Estimate		**260.00**	**8,595.60**
1	RRY SERVICES LLC		300.00	9,918.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		300.00	9,918.00
0029	504(D) 6239	CONCRETE RAIL (TR3)	328.000 LF	
	Engineer's Estimate		**175.00**	**57,400.00**
1	RRY SERVICES LLC		85.00	27,880.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		112.00	36,736.00
0030	506(A) 1322	STRUCTURAL STEEL	1,220.000 LB	
	Engineer's Estimate		**7.00**	**8,540.00**
1	RRY SERVICES LLC		3.00	3,660.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		5.00	6,100.00
0031	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000 EA	
	Engineer's Estimate		**1,250.00**	**15,000.00**
1	RRY SERVICES LLC		1,000.00	12,000.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		1,000.00	12,000.00
0032	507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	6.000 EA	
	Engineer's Estimate		**1,250.00**	**7,500.00**
1	RRY SERVICES LLC		1,000.00	6,000.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		1,000.00	6,000.00

Letting Date: May 14, 2020, 10:30 A.M.
Call Order: 430 **Contract ID:** 190347

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE - NBI NO. 32452					
0033	509(A) 1326	CLASS AA CONCRETE	106.200	CY	
	Engineer's Estimate		**950.00**		**100,890.00**
1	RRY SERVICES LLC		700.00		74,340.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		825.00		87,615.00
0034	509(B) 1328	CLASS A CONCRETE	114.000	CY	
	Engineer's Estimate		**875.00**		**99,750.00**
1	RRY SERVICES LLC		700.00		79,800.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		825.00		94,050.00
0035	511(A) 1332	REINFORCING STEEL	49,680.000	LB	
	Engineer's Estimate		**1.30**		**64,584.00**
1	RRY SERVICES LLC		1.15		57,132.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		1.00		49,680.00
0036	511(B) 6010	EPOXY COATED REINFORCING STEEL	2,541.000	LB	
	Engineer's Estimate		**2.10**		**5,336.10**
1	RRY SERVICES LLC		1.65		4,192.65
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		1.15		2,922.15
0037	514(A) 6010	PILES, FURNISHED (HP 10X42)	70.000	LF	
	Engineer's Estimate		**40.00**		**2,800.00**
1	RRY SERVICES LLC		45.00		3,150.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		55.00		3,850.00
0038	514(A) 6011	PILES, FURNISHED (HP 12X53)	165.000	LF	
	Engineer's Estimate		**45.00**		**7,425.00**
1	RRY SERVICES LLC		55.00		9,075.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		60.00		9,900.00
0039	514(B) 6292	PILES, DRIVEN (HP 10X42)	70.000	LF	
	Engineer's Estimate		**25.00**		**1,750.00**
1	RRY SERVICES LLC		10.00		700.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		15.00		1,050.00
0040	514(B) 6294	PILES, DRIVEN (HP 12X53)	165.000	LF	
	Engineer's Estimate		**25.00**		**4,125.00**
1	RRY SERVICES LLC		10.00		1,650.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		16.00		2,640.00
0041	514(K) 6260	(PL)PILOT HOLES	221.000	LF	
	Engineer's Estimate		**200.00**		**44,200.00**
1	RRY SERVICES LLC		475.00		104,975.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		285.00		62,985.00
0042	514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA	
	Engineer's Estimate		**400.00**		**400.00**
1	RRY SERVICES LLC		400.00		400.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		400.00		400.00
0043	516(A) 6094	DRILLED SHAFTS 48" DIAMETER	64.000	LF	
	Engineer's Estimate		**1,000.00**		**64,000.00**
1	RRY SERVICES LLC		1,800.00		115,200.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		1,200.00		76,800.00

Letting Date: May 14, 2020, 10:30 A.M.
Call Order: 430 **Contract ID:** 190347

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**BRIDGE - NBI NO. 32452**		
0044	516(C) 6200	CROSSHOLE SONIC LOGGING	1.000 EA	
	Engineer's Estimate		**3,500.00**	**3,500.00**
1	RRY SERVICES LLC		2,500.00	2,500.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		6,000.00	6,000.00
0045	601(B) 1353	TYPE I-A PLAIN RIPRAP	831.900 TON	
	Engineer's Estimate		**45.00**	**37,435.50**
1	RRY SERVICES LLC		45.00	37,435.50
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		35.00	29,116.50
0046	601(C) 1355	TYPE I-A FILTER BLANKET	149.700 TON	
	Engineer's Estimate		**40.00**	**5,988.00**
1	RRY SERVICES LLC		35.00	5,239.50
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		30.00	4,491.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0003**	**STAKING**		
0047	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM	
	Engineer's Estimate		**21,000.00**	**21,000.00**
1	RRY SERVICES LLC		10,000.00	10,000.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		16,500.00	16,500.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0004**	**CONSTRUCTION**		
0048	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM	
	Engineer's Estimate		**7,000.00**	**7,000.00**
1	RRY SERVICES LLC		1,275.00	1,275.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		15,000.00	15,000.00
0049	641 1399	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**104,900.00**	**104,900.00**
1	RRY SERVICES LLC		76,000.00	76,000.00
2	PARADIGM CONSTRUCTION & ENGINEERING, INC		96,600.00	96,600.00