Letting Date: November 14, 2019, 10:30 A.M.
Call Order: 505 **Contract ID:** 190355
J/P No.: 31149(04) **Project No.:** STP-233D(041)CI **Contract Time:**
County: JACKSON
Description: BRIDGE AND APPROACHES COUNTY ROAD (EW-167): OVER BITTER CREEK, 3.1 MILES WEST OF THE US-283 JUNCTION NEAR ALTUS. PROJECT LENGTH = 0.189 MILE

	VENDORNAME	PROPOSALITEMTO		
1	SEWELL BROS., INC.	707,827.55	95.05	100.00
	Engineer's Estimate	744,710.60		
2	EARTH BUILDERS, L.P.	776,501.40	104.27	109.70

Letting Date: November 14, 2019, 10:30 A.M.
Call Order: 505 **Contract ID:** 190355

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0001**	**ROADWAY**		
0001	201(A) 0102	CLEARING AND GRUBBING	1.000 LSUM	
	Engineer's Estimate		**10,000.00**	**10,000.00**
1	SEWELL BROS., INC.		10,000.00	10,000.00
2	EARTH BUILDERS, L.P.		25,000.00	25,000.00
0002	202(H) 0185	EARTHWORK	1.000 LSUM	
	Engineer's Estimate		**80,000.00**	**80,000.00**
1	SEWELL BROS., INC.		65,000.00	65,000.00
2	EARTH BUILDERS, L.P.		65,000.00	65,000.00
0003	221(C) 2801	TEMPORARY SILT FENCE	1,650.000 LF	
	Engineer's Estimate		**2.00**	**3,300.00**
1	SEWELL BROS., INC.		3.60	5,940.00
2	EARTH BUILDERS, L.P.		2.40	3,960.00
0004	221(F) 0100	TEMPORARY SILT DIKE	200.000 LF	
	Engineer's Estimate		**7.00**	**1,400.00**
1	SEWELL BROS., INC.		12.00	2,400.00
2	EARTH BUILDERS, L.P.		9.00	1,800.00
0005	230(A) 2806	SOLID SLAB SODDING	5,950.000 SY	
	Engineer's Estimate		**2.00**	**11,900.00**
1	SEWELL BROS., INC.		4.05	24,097.50
2	EARTH BUILDERS, L.P.		2.40	14,280.00
0006	233(A) 2817	VEGETATIVE MULCHING	1.230 AC	
	Engineer's Estimate		**600.00**	**738.00**
1	SEWELL BROS., INC.		2,035.00	2,503.05
2	EARTH BUILDERS, L.P.		650.00	799.50
0007	402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	530.000 TON	
	Engineer's Estimate		**36.00**	**19,080.00**
1	SEWELL BROS., INC.		30.00	15,900.00
2	EARTH BUILDERS, L.P.		35.00	18,550.00
0008	509(D) 0325	CLASS C CONCRETE	10.000 CY	
	Engineer's Estimate		**325.00**	**3,250.00**
1	SEWELL BROS., INC.		400.00	4,000.00
2	EARTH BUILDERS, L.P.		500.00	5,000.00
0009	613(B) 0690	24" CORR. GALV. STEEL PIPE	57.000 LF	
	Engineer's Estimate		**38.00**	**2,166.00**
1	SEWELL BROS., INC.		40.00	2,280.00
2	EARTH BUILDERS, L.P.		65.00	3,705.00
0010	613(M) 7151	TYPE B3 CULVERT END TREATMENT	2.000 EA	
	Engineer's Estimate		**1,500.00**	**3,000.00**
1	SEWELL BROS., INC.		1,300.00	2,600.00
2	EARTH BUILDERS, L.P.		1,200.00	2,400.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**BRIDGE 'A' - NBI NO. 00356**		

Letting Date: November 14, 2019, 10:30 A.M.
Call Order: 505 **Contract ID:** 190355

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A' - NBI NO. 00356					
0011	501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	230.600	CY	
	Engineer's Estimate		**16.00**		**3,689.60**
1	SEWELL BROS., INC.		15.00		3,459.00
2	EARTH BUILDERS, L.P.		25.00		5,765.00
0012	501(F) 6352	GRANULAR BACKFILL	109.600	CY	
	Engineer's Estimate		**60.00**		**6,576.00**
1	SEWELL BROS., INC.		60.00		6,576.00
2	EARTH BUILDERS, L.P.		65.00		7,124.00
0013	503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	359.000	LF	
	Engineer's Estimate		**260.00**		**93,340.00**
1	SEWELL BROS., INC.		220.00		78,980.00
2	EARTH BUILDERS, L.P.		250.00		89,750.00
0014	504(D) 6239	CONCRETE RAIL (TR3)	261.300	LF	
	Engineer's Estimate		**80.00**		**20,904.00**
1	SEWELL BROS., INC.		75.00		19,597.50
2	EARTH BUILDERS, L.P.		110.00		28,743.00
0015	506(A) 1322	STRUCTURAL STEEL	660.000	LB	
	Engineer's Estimate		**3.00**		**1,980.00**
1	SEWELL BROS., INC.		4.00		2,640.00
2	EARTH BUILDERS, L.P.		5.00		3,300.00
0016	507(A) 6172	WEATHERING STEEL FIXED BEARING ASSEMBLY	4.000	EA	
	Engineer's Estimate		**800.00**		**3,200.00**
1	SEWELL BROS., INC.		800.00		3,200.00
2	EARTH BUILDERS, L.P.		1,000.00		4,000.00
0017	507(B) 6176	WEATHERING STEEL EXPANSION BEARING ASSEMBLY	4.000	EA	
	Engineer's Estimate		**800.00**		**3,200.00**
1	SEWELL BROS., INC.		800.00		3,200.00
2	EARTH BUILDERS, L.P.		1,000.00		4,000.00
0018	509(A) 1326	CLASS AA CONCRETE	81.300	CY	
	Engineer's Estimate		**675.00**		**54,877.50**
1	SEWELL BROS., INC.		700.00		56,910.00
2	EARTH BUILDERS, L.P.		600.00		48,780.00
0019	509(B) 1328	CLASS A CONCRETE	83.200	CY	
	Engineer's Estimate		**685.00**		**56,992.00**
1	SEWELL BROS., INC.		700.00		58,240.00
2	EARTH BUILDERS, L.P.		600.00		49,920.00
0020	511(A) 1332	REINFORCING STEEL	32,852.000	LB	
	Engineer's Estimate		**1.00**		**32,852.00**
1	SEWELL BROS., INC.		1.00		32,852.00
2	EARTH BUILDERS, L.P.		1.20		39,422.40
0021	514(A) 6010	PILES, FURNISHED (HP 10X42)	188.000	LF	
	Engineer's Estimate		**38.00**		**7,144.00**
1	SEWELL BROS., INC.		35.00		6,580.00
2	EARTH BUILDERS, L.P.		25.00		4,700.00

Letting Date: November 14, 2019, 10:30 A.M.
Call Order: 505 **Contract ID:** 190355

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 BRIDGE 'A' - NBI NO. 00356					
0022	514(A) 6011	PILES, FURNISHED (HP 12X53)	616.000	LF	
	Engineer's Estimate		**42.00**		**25,872.00**
1	SEWELL BROS., INC.		45.00		27,720.00
2	EARTH BUILDERS, L.P.		35.00		21,560.00
0023	514(B) 6292	PILES, DRIVEN (HP 10X42)	188.000	LF	
	Engineer's Estimate		**18.00**		**3,384.00**
1	SEWELL BROS., INC.		15.00		2,820.00
2	EARTH BUILDERS, L.P.		35.00		6,580.00
0024	514(B) 6294	PILES, DRIVEN (HP 12X53)	616.000	LF	
	Engineer's Estimate		**18.00**		**11,088.00**
1	SEWELL BROS., INC.		15.00		9,240.00
2	EARTH BUILDERS, L.P.		35.00		21,560.00
0025	514(L) 6220	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA	
	Engineer's Estimate		**400.00**		**400.00**
1	SEWELL BROS., INC.		400.00		400.00
2	EARTH BUILDERS, L.P.		400.00		400.00
0026	601(B) 1353	TYPE I-A PLAIN RIPRAP	2,880.000	TON	
	Engineer's Estimate		**50.00**		**144,000.00**
1	SEWELL BROS., INC.		45.00		129,600.00
2	EARTH BUILDERS, L.P.		52.00		149,760.00
0027	601(C) 1355	TYPE I-A FILTER BLANKET	777.000	TON	
	Engineer's Estimate		**40.00**		**31,080.00**
1	SEWELL BROS., INC.		35.00		27,195.00
2	EARTH BUILDERS, L.P.		40.00		31,080.00
0028	613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	66.000	LF	
	Engineer's Estimate		**25.00**		**1,650.00**
1	SEWELL BROS., INC.		30.00		1,980.00
2	EARTH BUILDERS, L.P.		25.00		1,650.00
0029	613(I) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	32.000	LF	
	Engineer's Estimate		**30.00**		**960.00**
1	SEWELL BROS., INC.		40.00		1,280.00
2	EARTH BUILDERS, L.P.		25.00		800.00
0030	619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM	
	Engineer's Estimate		**10,000.00**		**10,000.00**
1	SEWELL BROS., INC.		30,000.00		30,000.00
2	EARTH BUILDERS, L.P.		25,000.00		25,000.00
0031	623(A) 1418	BEAM GUARDRAIL W-BEAM SINGLE	37.500	LF	
	Engineer's Estimate		**25.00**		**937.50**
1	SEWELL BROS., INC.		33.00		1,237.50
2	EARTH BUILDERS, L.P.		35.00		1,312.50
0032	623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	1.000	EA	
	Engineer's Estimate		**2,400.00**		**2,400.00**
1	SEWELL BROS., INC.		2,200.00		2,200.00
2	EARTH BUILDERS, L.P.		2,200.00		2,200.00

Letting Date: November 14, 2019, 10:30 A.M.
Call Order: 505 **Contract ID:** 190355

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0002	**BRIDGE 'A' - NBI NO. 00356**		
0033	623(F) 6033	GUARDRAIL ANCHOR UNIT (TYPE II)	3.000 EA
	Engineer's Estimate	**3,200.00**	**9,600.00**
1	SEWELL BROS., INC.	3,200.00	9,600.00
2	EARTH BUILDERS, L.P.	3,200.00	9,600.00
0034	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**7,500.00**	**7,500.00**
1	SEWELL BROS., INC.	3,300.00	3,300.00
2	EARTH BUILDERS, L.P.	4,000.00	4,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0003	**STAKING**		
0035	642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000 LSUM
	Engineer's Estimate	**7,500.00**	**7,500.00**
1	SEWELL BROS., INC.	5,300.00	5,300.00
2	EARTH BUILDERS, L.P.	10,000.00	10,000.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section: 0004	**CONSTRUCTION**		
0036	220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM
	Engineer's Estimate	**7,500.00**	**7,500.00**
1	SEWELL BROS., INC.	4,000.00	4,000.00
2	EARTH BUILDERS, L.P.	3,000.00	3,000.00
0037	641 1399	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**61,250.00**	**61,250.00**
1	SEWELL BROS., INC.	45,000.00	45,000.00
2	EARTH BUILDERS, L.P.	62,000.00	62,000.00