Letting Date: February 20, 2020, 10:30 A.M.
Call Order: 565 **Contract ID:** 200071
J/P No.: 33810(04) **Project No.:** SSR-242C(083)SR **Contract Time:**
County: LOGAN
Description: PAVEMENT REHABILITATION (ASPHALT) SH-74: FROM 1.28 MILES NORTH OF THE SH-74F JUNCTION, EXTEND NORTH NEAR CEDAR VALLEY. PROJECT LENGTH = 3.780 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	1,194,300.00		
1	T.J. CAMPBELL CONSTRUCTION COMPANY	1,344,425.00	112.57	100.00
2	HASKELL LEMON CONSTRUCTION CO.	1,543,765.00	129.26	114.83

Letting Date: February 20, 2020, 10:30 A.M.
Call Order: 565 **Contract ID:** 200071

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0001**	**ROADWAY**		
0001	202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1,000.000 CY	
	Engineer's Estimate		**15.00**	**15,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		15.00	15,000.00
2	HASKELL LEMON CONSTRUCTION CO.		135.00	135,000.00
0002	407(B) 0250	TACK COAT	1,000.000 GAL	
	Engineer's Estimate		**3.00**	**3,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		2.15	2,150.00
2	HASKELL LEMON CONSTRUCTION CO.		3.85	3,850.00
0003	407(C) 0301	(SP) POLYMER MODIFIED CATIONIC RAPID SET - 1S	17,000.000 GAL	
	Engineer's Estimate		**3.00**	**51,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		2.25	38,250.00
2	HASKELL LEMON CONSTRUCTION CO.		2.50	42,500.00
0004	411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	7,700.000 TON	
	Engineer's Estimate		**90.00**	**693,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		115.00	885,500.00
2	HASKELL LEMON CONSTRUCTION CO.		107.00	823,900.00
0005	411(H) 6210	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	2,016.000 TON	
	Engineer's Estimate		**100.00**	**201,600.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		100.00	201,600.00
2	HASKELL LEMON CONSTRUCTION CO.		103.00	207,648.00
0006	412 5267	COLD MILLING PAVEMENT	2,000.000 SY	
	Engineer's Estimate		**4.00**	**8,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		5.00	10,000.00
2	HASKELL LEMON CONSTRUCTION CO.		20.00	40,000.00
0007	413(A) 4861	RUMBLE STRIP-METHOD HMA-CON	39,000.000 LF	
	Engineer's Estimate		**0.20**	**7,800.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		0.10	3,900.00
2	HASKELL LEMON CONSTRUCTION CO.		0.12	4,680.00
0008	413(B) 4862	RUMBLE STRIP-METHOD HMA-CYC GROUP	3.000 EAGP	
	Engineer's Estimate		**1,000.00**	**3,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		600.00	1,800.00
2	HASKELL LEMON CONSTRUCTION CO.		1,000.00	3,000.00
0009	619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	9,000.000 SY	
	Engineer's Estimate		**8.00**	**72,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		6.00	54,000.00
2	HASKELL LEMON CONSTRUCTION CO.		9.00	81,000.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**TRAFFIC**		
0010	856(A) 8535	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	66,000.000 LF	
	Engineer's Estimate		**0.60**	**39,600.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY		0.40	26,400.00
2	HASKELL LEMON CONSTRUCTION CO.		0.50	33,000.00

Letting Date: February 20, 2020, 10:30 A.M.
Call Order: 565 **Contract ID:** 200071

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0002**	**TRAFFIC**	
0011	856(A) 8540	TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	400.000 LF
	Engineer's Estimate	**1.50**	**600.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY	1.50	600.00
2	HASKELL LEMON CONSTRUCTION CO.	0.65	260.00
0012	856(A) 8555	TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	50.000 LF
	Engineer's Estimate	**5.00**	**250.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY	5.00	250.00
2	HASKELL LEMON CONSTRUCTION CO.	3.50	175.00
0013	856(B) 8525	TRAFFIC STRIPE (MULTI-POLYMER)(SYMBOLS, WORDS. ETC.)	9.000 EA
	Engineer's Estimate	**250.00**	**2,250.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY	175.00	1,575.00
2	HASKELL LEMON CONSTRUCTION CO.	38.50	346.50
0014	857(E) 8890	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS(FLEX TAB)TYF	6,000.000 EA
	Engineer's Estimate	**1.00**	**6,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY	1.00	6,000.00
2	HASKELL LEMON CONSTRUCTION CO.	1.00	6,000.00
0015	880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000 LSUM
	Engineer's Estimate	**10,000.00**	**10,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY	25,000.00	25,000.00
2	HASKELL LEMON CONSTRUCTION CO.	25,000.00	25,000.00
0016	882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	120.000 SD
	Engineer's Estimate	**10.00**	**1,200.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY	20.00	2,400.00
2	HASKELL LEMON CONSTRUCTION CO.	7.00	840.00

Line #	Item Number	Item Description	Quantity/Unit
	Bidder	Unit Price	Ext Amount
Section:	**0003**	**CONSTRUCTION**	
0017	641 1552	MOBILIZATION	1.000 LSUM
	Engineer's Estimate	**80,000.00**	**80,000.00**
1	T.J. CAMPBELL CONSTRUCTION COMPANY	70,000.00	70,000.00
2	HASKELL LEMON CONSTRUCTION CO.	136,565.50	136,565.50