Letting Date: July 15, 2021, 10:30 A.M.
Call Order: 135 **Contract ID:** 210207
J/P No.: 33475(04) **Project No.:** NHPP-225N(095)AD **Contract Time:**
County: GARVIN
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
SH-19: FROM 0.6 MILES SOUTHWEST OF THE US-77
JUNCTION, EXTEND NORTHEAST IN PAULS VALLEY.
PROJECT LENGTH = 0.700 MILES

	VENDORNAME	PROPOSALITEMTO		
1	RUDY CONSTRUCTION CO.	561,751.00	87.98	100.00
2	SCHIRALLI CONSTRUCTION CORP.	628,809.26	98.48	111.94
	Engineer's Estimate	638,513.00		
3	TOM HUDSON PAVING, INC.	788,699.11	123.52	140.40
4	Silver Star Construction Company, Inc.	1,036,400.00	162.31	184.49
5	DOWNEY CONTRACTING, LLC	1,384,589.32	216.85	246.48

Letting Date: July 15, 2021, 10:30 A.M.
Call Order: 135 **Contract ID:** 210207

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0010	201(A)1200	CLEARING AND GRUBBING	1.000 LSUM	
	Engineer's Estimate		**25,000.00**	**25,000.00**
1	RUDY CONSTRUCTION CO.		20,000.00	20,000.00
2	SCHIRALLI CONSTRUCTION CORP.		31,837.25	31,837.25
3	TOM HUDSON PAVING, INC.		31,150.42	31,150.42
4	Silver Star Construction Company, Inc.		82,988.20	82,988.20
5	DOWNEY CONTRACTING, LLC		225,000.00	225,000.00
0021	221(G)2800	TEMPORARY FIBER LOG	2,950.000 LF	
	Engineer's Estimate		**8.00**	**23,600.00**
1	RUDY CONSTRUCTION CO.		2.50	7,375.00
2	SCHIRALLI CONSTRUCTION CORP.		5.57	16,431.50
3	TOM HUDSON PAVING, INC.		5.96	17,582.00
4	Silver Star Construction Company, Inc.		5.60	16,520.00
5	DOWNEY CONTRACTING, LLC		4.35	12,832.50
0030	230(A)7200	SOLID SLAB SODDING	780.000 SY	
	Engineer's Estimate		**4.00**	**3,120.00**
1	RUDY CONSTRUCTION CO.		5.00	3,900.00
2	SCHIRALLI CONSTRUCTION CORP.		7.63	5,951.40
3	TOM HUDSON PAVING, INC.		7.43	5,795.40
4	Silver Star Construction Company, Inc.		7.60	5,928.00
5	DOWNEY CONTRACTING, LLC		7.25	5,655.00
0040	303(A)1200	AGGREGATE BASE TYPE A	594.000 CY	
	Engineer's Estimate		**50.00**	**29,700.00**
1	RUDY CONSTRUCTION CO.		74.00	43,956.00
2	SCHIRALLI CONSTRUCTION CORP.		65.82	39,097.08
3	TOM HUDSON PAVING, INC.		86.87	51,600.78
4	Silver Star Construction Company, Inc.		103.50	61,479.00
5	DOWNEY CONTRACTING, LLC		53.29	31,654.26
0050	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	424.000 LF	
	Engineer's Estimate		**25.00**	**10,600.00**
1	RUDY CONSTRUCTION CO.		12.00	5,088.00
2	SCHIRALLI CONSTRUCTION CORP.		23.41	9,925.84
3	TOM HUDSON PAVING, INC.		35.45	15,030.80
4	Silver Star Construction Company, Inc.		26.00	11,024.00
5	DOWNEY CONTRACTING, LLC		65.25	27,666.00
0060	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	541.000 LF	
	Engineer's Estimate		**30.00**	**16,230.00**
1	RUDY CONSTRUCTION CO.		33.00	17,853.00
2	SCHIRALLI CONSTRUCTION CORP.		36.67	19,838.47
3	TOM HUDSON PAVING, INC.		36.52	19,757.32
4	Silver Star Construction Company, Inc.		64.00	34,624.00
5	DOWNEY CONTRACTING, LLC		63.80	34,515.80
0070	610(A)5200	4" CONCRETE SIDEWALK	2,826.000 SY	
	Engineer's Estimate		**75.00**	**211,950.00**
1	RUDY CONSTRUCTION CO.		62.00	175,212.00
2	SCHIRALLI CONSTRUCTION CORP.		71.81	202,935.06
3	TOM HUDSON PAVING, INC.		111.45	314,957.70
4	Silver Star Construction Company, Inc.		103.00	291,078.00
5	DOWNEY CONTRACTING, LLC		181.25	512,212.50

Letting Date: July 15, 2021, 10:30 A.M.
Call Order: 135 **Contract ID:** 210207

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0080	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	1,187.000	SY	
	Engineer's Estimate		**85.00**		**100,895.00**
1	RUDY CONSTRUCTION CO.		67.00		79,529.00
2	SCHIRALLI CONSTRUCTION CORP.		91.86		109,037.82
3	TOM HUDSON PAVING, INC.		126.20		149,799.40
4	Silver Star Construction Company, Inc.		170.00		201,790.00
5	DOWNEY CONTRACTING, LLC		181.25		215,143.75
0081	610(I)6000	TACTILE WARNING DEVICE-NEW	636.000	SF	
	Engineer's Estimate		**45.00**		**28,620.00**
1	RUDY CONSTRUCTION CO.		25.00		15,900.00
2	SCHIRALLI CONSTRUCTION CORP.		30.18		19,194.48
3	TOM HUDSON PAVING, INC.		43.70		27,793.20
4	Silver Star Construction Company, Inc.		19.00		12,084.00
5	DOWNEY CONTRACTING, LLC		188.50		119,886.00
0090	612(A)3200	MANHOLES ADJUST TO GRADE	3.000	EA	
	Engineer's Estimate		**1,700.00**		**5,100.00**
1	RUDY CONSTRUCTION CO.		700.00		2,100.00
2	SCHIRALLI CONSTRUCTION CORP.		1,228.87		3,686.61
3	TOM HUDSON PAVING, INC.		851.63		2,554.89
4	Silver Star Construction Company, Inc.		3,050.00		9,150.00
5	DOWNEY CONTRACTING, LLC		1,913.28		5,739.84
0100	619(B)6356	REMOVAL OF CURB AND GUTTER	627.000	LF	
	Engineer's Estimate		**12.00**		**7,524.00**
1	RUDY CONSTRUCTION CO.		10.00		6,270.00
2	SCHIRALLI CONSTRUCTION CORP.		12.58		7,887.66
3	TOM HUDSON PAVING, INC.		9.26		5,806.02
4	Silver Star Construction Company, Inc.		19.00		11,913.00
5	DOWNEY CONTRACTING, LLC		11.28		7,072.56
0110	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	1,279.000	SY	
	Engineer's Estimate		**20.00**		**25,580.00**
1	RUDY CONSTRUCTION CO.		10.00		12,790.00
2	SCHIRALLI CONSTRUCTION CORP.		11.84		15,143.36
3	TOM HUDSON PAVING, INC.		14.12		18,059.48
4	Silver Star Construction Company, Inc.		38.00		48,602.00
5	DOWNEY CONTRACTING, LLC		13.35		17,074.65
0120	619(B)6404	REMOVAL OF SIDEWALK	2,416.000	SY	
	Engineer's Estimate		**13.00**		**31,408.00**
1	RUDY CONSTRUCTION CO.		10.00		24,160.00
2	SCHIRALLI CONSTRUCTION CORP.		10.03		24,232.48
3	TOM HUDSON PAVING, INC.		12.52		30,248.32
4	Silver Star Construction Company, Inc.		24.00		57,984.00
5	DOWNEY CONTRACTING, LLC		11.35		27,421.60
0121	619(C)6600	SAWING PAVEMENT	1,100.000	LF	
	Engineer's Estimate		**4.00**		**4,400.00**
1	RUDY CONSTRUCTION CO.		4.00		4,400.00
2	SCHIRALLI CONSTRUCTION CORP.		5.85		6,435.00
3	TOM HUDSON PAVING, INC.		7.64		8,404.00
4	Silver Star Construction Company, Inc.		7.00		7,700.00
5	DOWNEY CONTRACTING, LLC		7.25		7,975.00

Letting Date: July 15, 2021, 10:30 A.M.
Call Order: 135 **Contract ID:** 210207

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002	**TRAFFIC SIGNING AND STRIPING**			
0130	804(A)2200	STRUCTURAL CONCRETE	1.600 CY	
	Engineer's Estimate		**400.00**	**640.00**
1	RUDY CONSTRUCTION CO.		1,500.00	2,400.00
2	SCHIRALLI CONSTRUCTION CORP.		440.00	704.00
3	TOM HUDSON PAVING, INC.		549.49	879.18
4	Silver Star Construction Company, Inc.		1,100.00	1,760.00
5	DOWNEY CONTRACTING, LLC		2,175.00	3,480.00
0140	804(B)2300	REINFORCING STEEL	192.000 LB	
	Engineer's Estimate		**1.00**	**192.00**
1	RUDY CONSTRUCTION CO.		4.00	768.00
2	SCHIRALLI CONSTRUCTION CORP.		2.48	476.16
3	TOM HUDSON PAVING, INC.		3.66	702.72
4	Silver Star Construction Company, Inc.		5.50	1,056.00
5	DOWNEY CONTRACTING, LLC		3.48	668.16
0150	805(D)3536	(PL)REMOVE & RESET GROUND MOUNTED SIGN	5.000 EA	
	Engineer's Estimate		**400.00**	**2,000.00**
1	RUDY CONSTRUCTION CO.		360.00	1,800.00
2	SCHIRALLI CONSTRUCTION CORP.		357.50	1,787.50
3	TOM HUDSON PAVING, INC.		348.10	1,740.50
4	Silver Star Construction Company, Inc.		356.00	1,780.00
5	DOWNEY CONTRACTING, LLC		471.25	2,356.25
0160	850(A)1200	SHEET ALUMINUM SIGNS	88.000 SF	
	Engineer's Estimate		**40.00**	**3,520.00**
1	RUDY CONSTRUCTION CO.		28.00	2,464.00
2	SCHIRALLI CONSTRUCTION CORP.		27.50	2,420.00
3	TOM HUDSON PAVING, INC.		26.78	2,356.64
4	Silver Star Construction Company, Inc.		27.35	2,406.80
5	DOWNEY CONTRACTING, LLC		36.25	3,190.00
0170	851(B)2310	2 1/2"@5.79 GALV.STL.PIPE POST	104.000 LF	
	Engineer's Estimate		**17.00**	**1,768.00**
1	RUDY CONSTRUCTION CO.		18.00	1,872.00
2	SCHIRALLI CONSTRUCTION CORP.		17.60	1,830.40
3	TOM HUDSON PAVING, INC.		17.14	1,782.56
4	Silver Star Construction Company, Inc.		17.50	1,820.00
5	DOWNEY CONTRACTING, LLC		23.20	2,412.80
0180	856(A)8200	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	500.000 LF	
	Engineer's Estimate		**2.00**	**1,000.00**
1	RUDY CONSTRUCTION CO.		2.50	1,250.00
2	SCHIRALLI CONSTRUCTION CORP.		2.20	1,100.00
3	TOM HUDSON PAVING, INC.		2.14	1,070.00
4	Silver Star Construction Company, Inc.		2.20	1,100.00
5	DOWNEY CONTRACTING, LLC		2.90	1,450.00

Letting Date: July 15, 2021, 10:30 A.M.
Call Order: 135 **Contract ID:** 210207

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002	**TRAFFIC SIGNING AND STRIPING**				
0190	856(A)8216	TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	2,188.000	LF	
	Engineer's Estimate		**12.00**		**26,256.00**
1	RUDY CONSTRUCTION CO.		8.00		17,504.00
2	SCHIRALLI CONSTRUCTION CORP.		7.70		16,847.60
3	TOM HUDSON PAVING, INC.		7.50		16,410.00
4	Silver Star Construction Company, Inc.		7.75		16,957.00
5	DOWNEY CONTRACTING, LLC		10.15		22,208.20
0200	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	500.000	LF	
	Engineer's Estimate		**0.50**		**250.00**
1	RUDY CONSTRUCTION CO.		1.20		600.00
2	SCHIRALLI CONSTRUCTION CORP.		1.10		550.00
3	TOM HUDSON PAVING, INC.		1.07		535.00
4	Silver Star Construction Company, Inc.		3.28		1,640.00
5	DOWNEY CONTRACTING, LLC		1.45		725.00

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0003	**TEMPORARY TRAFFIC CONTROL**				
0210	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,760.000	SD	
	Engineer's Estimate		**1.50**		**2,640.00**
1	RUDY CONSTRUCTION CO.		2.50		4,400.00
2	SCHIRALLI CONSTRUCTION CORP.		2.20		3,872.00
3	TOM HUDSON PAVING, INC.		2.14		3,766.40
4	Silver Star Construction Company, Inc.		5.20		9,152.00
5	DOWNEY CONTRACTING, LLC		2.90		5,104.00
0220	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	440.000	SD	
	Engineer's Estimate		**1.00**		**440.00**
1	RUDY CONSTRUCTION CO.		2.50		1,100.00
2	SCHIRALLI CONSTRUCTION CORP.		2.20		968.00
3	TOM HUDSON PAVING, INC.		2.14		941.60
4	Silver Star Construction Company, Inc.		2.20		968.00
5	DOWNEY CONTRACTING, LLC		2.90		1,276.00
0230	880(E)6600	WARNING LIGHTS(TYPE A)	8,800.000	SD	
	Engineer's Estimate		**0.50**		**4,400.00**
1	RUDY CONSTRUCTION CO.		0.60		5,280.00
2	SCHIRALLI CONSTRUCTION CORP.		0.55		4,840.00
3	TOM HUDSON PAVING, INC.		0.54		4,752.00
4	Silver Star Construction Company, Inc.		0.55		4,840.00
5	DOWNEY CONTRACTING, LLC		0.73		6,424.00
0240	880(F)6700	DRUMS	8,800.000	SD	
	Engineer's Estimate		**0.50**		**4,400.00**
1	RUDY CONSTRUCTION CO.		1.00		8,800.00
2	SCHIRALLI CONSTRUCTION CORP.		0.55		4,840.00
3	TOM HUDSON PAVING, INC.		0.54		4,752.00
4	Silver Star Construction Company, Inc.		0.55		4,840.00
5	DOWNEY CONTRACTING, LLC		0.73		6,424.00

Letting Date: July 15, 2021, 10:30 A.M.
Call Order: 135 **Contract ID:** 210207

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0003**	**TEMPORARY TRAFFIC CONTROL**		
0250	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	440.000	SD
	Engineer's Estimate		**12.00**	**5,280.00**
1	RUDY CONSTRUCTION CO.		17.00	7,480.00
2	SCHIRALLI CONSTRUCTION CORP.		16.50	7,260.00
3	TOM HUDSON PAVING, INC.		16.07	7,070.80
4	Silver Star Construction Company, Inc.		16.40	7,216.00
5	DOWNEY CONTRACTING, LLC		21.75	9,570.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0004**	**STAKING**		
0260	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
	Engineer's Estimate		**10,000.00**	**10,000.00**
1	RUDY CONSTRUCTION CO.		9,000.00	9,000.00
2	SCHIRALLI CONSTRUCTION CORP.		11,844.47	11,844.47
3	TOM HUDSON PAVING, INC.		5,542.82	5,542.82
4	Silver Star Construction Company, Inc.		43,000.00	43,000.00
5	DOWNEY CONTRACTING, LLC		17,400.00	17,400.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0005**	**CONSTRUCTION**		
0270	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	Engineer's Estimate		**2,000.00**	**2,000.00**
1	RUDY CONSTRUCTION CO.		3,500.00	3,500.00
2	SCHIRALLI CONSTRUCTION CORP.		4,539.35	4,539.35
3	TOM HUDSON PAVING, INC.		7,177.78	7,177.78
4	Silver Star Construction Company, Inc.		14,000.00	14,000.00
5	DOWNEY CONTRACTING, LLC		1,087.50	1,087.50
0280	641 2100	MOBILIZATION	1.000	LSUM
	Engineer's Estimate		**50,000.00**	**50,000.00**
1	RUDY CONSTRUCTION CO.		75,000.00	75,000.00
2	SCHIRALLI CONSTRUCTION CORP.		53,295.77	53,295.77
3	TOM HUDSON PAVING, INC.		30,679.38	30,679.38
4	Silver Star Construction Company, Inc.		71,000.00	71,000.00
5	DOWNEY CONTRACTING, LLC		50,963.95	50,963.95