**Proposal:**210239 **Let Date:**July 10, 2025 **Call Order:**535
**J/P Num:**32255(04) **Proj. Num:**SSP-263B(069)PM
**Counties:**POTTAWATOMIE
**Description:**GRADE, DRAIN, AND SURFACE
US-270B/CITY STREET (KICKAPOO STREET): US-270B,
FROM HIGHLAND STREET EXTEND NORTH IN SHAWNEE. KICKAPOO STREET,
FROM THE SH-18 JUNCTION EXTEND NORTH IN SHAWNEE.
PROJECT LENGTH = 1.568 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0010 | 201(A)1200 | CLEARING AND GRUBBING | 1.000 | LSUM |
| 0020 | 202(A)2200 | UNCLASSIFIED EXCAVATION | 21,129.000 | CY |
| 0030 | 202(D)2500 | UNCLASSIFIED BORROW | 2,605.000 | CY |
| 0040 | 205(A)6200 | TYPE A-SALVAGED TOPSOIL | 1.000 | LSUM |
| 0050 | 221(B)2300 | TEMPORARY SILT FENCE | 7,741.000 | LF |
| 0060 | 221(C)2400 | TEMPORARY SEDIMENT FILTER | 16.000 | EA |
| 0070 | 221(E)2600 | TEMPORARY SILT DIKE | 40.000 | LF |
| 0080 | 221(G)2800 | TEMPORARY FIBER LOG | 7,741.000 | LF |
| 0090 | 221(H)2900 | (PL)TEMPORARY INLET SEDIMENT FILTER | 286.000 | EA |
| 0100 | 230(A)7200 | SOLID SLAB SODDING | 19,273.000 | SY |
| 0110 | 232(B)9300 | SEEDING METHOD B | 3.900 | AC |
| 0120 | 233(A)0200 | VEGETATIVE MULCHING | 3.900 | AC |
| 0130 | 241 3100 | MOWING | 7.800 | AC |
| 0140 | 303(A)1200 | AGGREGATE BASE TYPE A | 180.000 | CY |
| 0150 | 307(K)4200 | STABILIZED SUBGRADE | 63,941.000 | SY |
| 0160 | 326(B)1300 | GEOGRID REINFORCEMENT | 808.000 | SY |
| 0170 | 402(A)2200 | TRAFFIC BOUND SURFACE COURSE TYPE A | 1,455.000 | TON |
| 0180 | 407(B)7300 | TACK COAT | 908.000 | GAL |
| 0190 | 408 8100 | PRIME COAT | 22,916.000 | GAL |
| 0200 | 411(B)1330 | SUPERPAVE, TYPE S3(PG 64-22 OK) | 11,494.000 | TON |
| 0210 | 411(C)1420 | SUPERPAVE, TYPE S4(PG 70-28 OK) | 246.000 | TON |
| 0220 | 411(C)1430 | SUPERPAVE, TYPE S4(PG 64-22 OK) | 1,107.000 | TON |
| 0230 | 411(I)2000 | SUPERPAVE, TYPE S4(PATCH)(PG64-22OK) | 168.000 | TON |
| 0240 | 412 3100 | COLD MILLING PAVEMENT | 2,148.000 | SY |
| 0250 | 414(A)5200 | P.C.CONCRETE PAVEMENT(PLACEMENT) | 1,106.000 | SY |
| 0260 | 414(B)5300 | DOWEL JOINTED P.C.C.PAVT.(PLACEMENT) | 51,610.000 | SY |
| 0270 | 414(F)5700 | PARTIAL DEPTH P.C.C. PATCH (PLACEMENT) | 300.000 | SY |
| 0280 | 414(G)5800 | P.C. CONCRETE FOR PAVEMENT | 13,141.000 | CY |
| 0290 | 501(G)1810 | CLSM BACKFILL | 230.000 | CY |
| 0300 | 509(C)0400 | CLASS A CONCRETE, SMALL STRUCTURES | 37.000 | CY |
| 0310 | 509(D)0500 | CLASS C CONCRETE | 15.000 | CY |
| 0320 | 510(A)1230 | BLOCK RETAINING WALL & CAP | 4,932.000 | SF |
| 0330 | 520(A)1200 | PREPARATION OF CRACKS, ABOVE WATER | 50.000 | LF |
| 0340 | 520(C)1400 | EPOXY RESIN, ABOVE WATER | 5.000 | GAL |
| 0350 | 601(A)1100 | TYPE I PLAIN RIPRAP | 106.000 | TON |
| 0360 | 609(A)4220 | CONC.CURB(4" MNTBLE-INTEGRAL) | 206.000 | LF |
| 0370 | 609(A)4230 | CONC.CURB(6" BARRIER-INTEGRAL) | 13,767.000 | LF |
| 0380 | 609(A)4240 | CONC.CURB(6" BARRIER-DOWELLED) | 1,482.000 | LF |
| 0390 | 609(B)4330 | 1'-8" COMB.CRB.& GUT.(6" BARRIER) | 27.000 | LF |
| 0400 | 610(A)5200 | 4" CONCRETE SIDEWALK | 10,570.000 | SY |
| 0410 | 610(A)5220 | 6" CONCRETE SIDEWALK | 152.000 | SY |
| 0420 | 610(B)5300 | 6" CONCRETE DRIVEWAY (H.E.S.) | 8,480.000 | SY |
| 0430 | 610(C)5400 | 4" CONCRETE DIVIDING STRIP | 220.000 | SY |
| 0440 | 610(G)5800 | ASPHALT DRIVEWAY | 43.000 | TON |
| 0450 | 610(I)6000 | TACTILE WARNING DEVICE-NEW | 910.000 | SF |

**Proposal:**210239 **Let Date:**July 10, 2025 **Call Order:**535
**J/P Num:**32255(04) **Proj. Num:**SSP-263B(069)PM
**Counties:**POTTAWATOMIE
**Description:**GRADE, DRAIN, AND SURFACE
US-270B/CITY STREET (KICKAPOO STREET): US-270B,
FROM HIGHLAND STREET EXTEND NORTH IN SHAWNEE. KICKAPOO STREET,
FROM THE SH-18 JUNCTION EXTEND NORTH IN SHAWNEE.
PROJECT LENGTH = 1.568 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0460 | 610(J)6100 | (PL) STAMPED CONCRETE FINISH | 5,666.000 | SY |
| 0470 | 611(A)7210 | MANHOLE (4' DIA.) | 37.000 | EA |
| 0480 | 611(G)0144 | INLET W/LRG. JCT. BOX, CI, DES.2 | 3.000 | EA |
| 0490 | 611(G)0172 | INLET W/LRG. JCT. BOX, CI, DES.3 | 20.000 | EA |
| 0500 | 611(G)0264 | INLET W/SMALL JCT. BOX, CI, DES.2 | 6.000 | EA |
| 0510 | 611(G)0350 | INLET (SMD-TYPE 1) | 14.000 | EA |
| 0520 | 611(G)0354 | INLET (SMD-TYPE 2) | 1.000 | EA |
| 0530 | 611(G)7710 | INLET CI DES. 1 (STD) | 4.000 | EA |
| 0540 | 611(G)7754 | INLET CI DES. 2 (STD) | 20.000 | EA |
| 0550 | 611(G)7786 | INLET CI DES. 3 (STD) | 35.000 | EA |
| 0560 | 611(G)7794 | INLET CI DES. 3 (D) | 1.000 | EA |
| 0570 | 611(G)9012 | INLET CDI RCP DES. 4 | 1.000 | EA |
| 0580 | 611(L)1600 | JUNCTION BOXES | 1,960.000 | CF |
| 0590 | 612(A)3200 | MANHOLES ADJUST TO GRADE | 5.000 | EA |
| 0600 | 612(E)3600 | VALVE BOXES ADJUST TO GRADE | 38.000 | EA |
| 0610 | 613(A)5208 | 18" R.C.PIPE CLASS III | 4,196.000 | LF |
| 0620 | 613(A)5216 | 24" R.C.PIPE CLASS III | 308.000 | LF |
| 0630 | 613(A)5220 | 30" R.C.PIPE CLASS III | 592.000 | LF |
| 0640 | 613(A)5224 | 36" R.C.PIPE CLASS III | 172.000 | LF |
| 0650 | 613(A)5232 | 48" R.C.PIPE CLASS III | 1,688.000 | LF |
| 0660 | 613(A)5350 | 22" X 13" R.C.PIPE ARCH CLASS A-III | 1,516.000 | LF |
| 0670 | 613(A)5358 | 28" X 18" R.C.PIPE ARCH CLASS A-III | 2,156.000 | LF |
| 0680 | 613(A)5366 | 36" X 22" R.C.PIPE ARCH CLASS A-III | 310.000 | LF |
| 0690 | 613(A)5370 | 43" X 26" R.C.PIPE ARCH CLASS A-III | 150.000 | LF |
| 0700 | 613(A)5378 | 58" X 36" R.C.PIPE ARCH CLASS A-III | 1,414.000 | LF |
| 0710 | 613(B)5680 | PVC DRAINAGE STRUCTURE | 11.000 | EA |
| 0720 | 613(H)6200 | 6" PERFORATED PIPE UNDERDRAIN ROUND | 600.000 | LF |
| 0730 | 613(I)6305 | 6" NON-PERF.PIPE UNDERDRAIN RND. | 200.000 | LF |
| 0740 | 613(J)6400 | EDGE DRAIN CONDUIT-PERFORATED | 1,247.000 | LF |
| 0750 | 613(K)6500 | EDGE DRAIN OUTLET LATERAL-NONPERFORATED | 81.000 | LF |
| 0760 | 613(L)6736 | 48" PREFAB. CULVERT END SEC., ROUND | 1.000 | EA |
| 0770 | 613(U)7950 | PIPE UNDERDRAIN COVER MAT'L. | 70.000 | CY |
| 0780 | 616(P)4161 | 18" CORRUGATED HDPE PIPE | 2,627.000 | LF |
| 0790 | 616(P)4162 | 18" CORR HDPE PIPE WITH SLOTTED GRATE RISER | 220.000 | LF |
| 0800 | 619(A)6200 | REMOVAL OF STRUCTURES & OBSTRUCTIONS | 1.000 | LSUM |
| 0810 | 619(B)6352 | REMOVAL OF FENCE | 383.000 | LF |
| 0820 | 619(B)6356 | REMOVAL OF CURB AND GUTTER | 8,987.000 | LF |
| 0830 | 619(B)6360 | REMOVAL OF CONCRETE PAVEMENT | 3,801.000 | SY |
| 0840 | 619(B)6364 | REMOVAL OF ASPHALT PAVEMENT | 38,142.000 | SY |
| 0850 | 619(B)6380 | REMOVAL OF CONCRETE DRIVEWAY | 2,756.000 | SY |
| 0860 | 619(B)6384 | REMOVAL OF ASPHALT DRIVEWAY | 359.000 | SY |
| 0870 | 619(B)6404 | REMOVAL OF SIDEWALK | 4,080.000 | SY |
| 0880 | 619(B)6440 | REMOVAL OF EXISTING PIPE | 2,718.000 | LF |
| 0890 | 619(B)6452 | REMOVAL OF EXISTING RETAINING WALL | 1,402.000 | LF |
| 0900 | 619(C)6600 | SAWING PAVEMENT | 2,239.000 | LF |

**Proposal:**210239 **Let Date:**July 10, 2025 **Call Order:**535
**J/P Num:**32255(04) **Proj. Num:**SSP-263B(069)PM
**Counties:**POTTAWATOMIE
**Description:**GRADE, DRAIN, AND SURFACE
US-270B/CITY STREET (KICKAPOO STREET): US-270B,
FROM HIGHLAND STREET EXTEND NORTH IN SHAWNEE. KICKAPOO STREET,
FROM THE SH-18 JUNCTION EXTEND NORTH IN SHAWNEE.
PROJECT LENGTH = 1.568 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0910 | 620(C)8410 | CONTRACTOR HEALTH SAFETY PLAN | 1.000 | LSUM |
| 0920 | 620(C)8430 | CONTAMINATED MATERIALS MANAGEMENT PLAN | 1.000 | LSUM |
| 0930 | 622(A)0200 | PIPE RAILING | 800.000 | LF |
| 0940 | 624 3100 | (PL) ORNAMENTAL FENCE | 213.000 | LF |
| 0950 | 624(C)3405 | FENCE-STYLE SWF (5 BARBED WIRE) | 140.000 | LF |
| 0960 | 624(E)3600 | FENCE-STYLE CLF (4'HIGH, CLASS A) | 294.000 | LF |
| 0970 | 624(E)3610 | FENCE-STYLE CLF (5'HIGH, CLASS A) | 35.000 | LF |
| 0975 | 624(E)3625 | FENCE-STYLE CLF (6'HIGH, CLASS B) | 352.000 | LF |
| 0980 | 648(A)6210 | (SP)SUBMERSIBLE PUMP | 1.000 | EA |
| **0002** | SIGNING AND STRIPING | | | |
| 0990 | 104 3250 | (SP) RAILROAD FLAGGING(NON-BIDDABLE) | 14.000 | DAY |
| 1000 | 805(D)3528 | (PL)REMOVE & RESET EXISTING SIGNS | 10.000 | EA |
| 1010 | 836 7100 | REGULATORY OR WARNING SIGN ASSEMBLY | 3.000 | EA |
| 1020 | 836 7110 | RECTANGULAR RAPID FLASHING BEACON | 3.000 | EA |
| 1030 | 850(A)1200 | SHEET ALUMINUM SIGNS | 818.000 | SF |
| 1040 | 851(C)2415 | 2" SQUARE TUBE POST | 1,082.000 | LF |
| 1050 | 856(A)8203 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE) | 35,570.000 | LF |
| 1060 | 856(A)8211 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE) | 1,874.000 | LF |
| 1070 | 856(A)8219 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE) | 2,691.000 | LF |
| 1080 | 856(B)8307 | (SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS) | 36.000 | EA |
| 1090 | 856(B)8311 | (SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS) | 3.000 | EA |
| 1100 | 856(B)8315 | (SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS) | 10.000 | EA |
| **0003** | TRAFFIC OPERATIONS | | | |
| 1110 | 857(A)9200 | CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE) | 72,100.000 | LF |
| 1120 | 857(F)9700 | PAVEMENT MRKNG.REMOVAL(TRAF.STRP) | 54,900.000 | LF |
| 1130 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 48,400.000 | SD |
| 1140 | 880(B)6310 | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF | 27,600.000 | SD |
| 1150 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 25,200.000 | SD |
| 1160 | 880(C)6410 | CONSTRUCTION BARRICADES(TYPE III) | 70,400.000 | SD |
| 1170 | 880(E)6607 | WARNING LIGHTS(TYPE B) | 155,200.000 | SD |
| 1180 | 880(F)6700 | DRUMS | 83,600.000 | SD |

**Proposal:**210239 **Let Date:**July 10, 2025 **Call Order:**535
**J/P Num:**32255(04) **Proj. Num:**SSP-263B(069)PM
**Counties:**POTTAWATOMIE
**Description:**GRADE, DRAIN, AND SURFACE
US-270B/CITY STREET (KICKAPOO STREET): US-270B,
FROM HIGHLAND STREET EXTEND NORTH IN SHAWNEE. KICKAPOO STREET,
FROM THE SH-18 JUNCTION EXTEND NORTH IN SHAWNEE.
PROJECT LENGTH = 1.568 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0004** | TRAFFIC SIGNAL | | | |
| 1190 | 802(B)0332 | 3" PVC SCH.40 PLASTIC CONDUIT TRENCHED | 865.000 | LF |
| 1200 | 802(B)0336 | 4" PVC SCH.40 PLASTIC CONDUIT BORED | 815.000 | LF |
| 1210 | 802(B)0340 | 4" PVC SCH.40 PLASTIC CONDUIT TRENCHED | 260.000 | LF |
| 1220 | 803(A)1210 | PULL BOX(SIZE I) | 10.000 | EA |
| 1230 | 803(A)1220 | PULL BOX(SIZE II) | 13.000 | EA |
| 1240 | 804(A)2200 | STRUCTURAL CONCRETE | 60.000 | CY |
| 1250 | 804(B)2300 | REINFORCING STEEL | 8,504.000 | LB |
| 1260 | 805(A)3208 | REMOVAL OF PULL BOX | 1.000 | EA |
| 1270 | 805(A)3256 | (PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT | 1.000 | LSUM |
| 1340 | 806(B)4400 | 6' MTG.HT.TS PED.POLE(G.STL.) | 2.000 | EA |
| 1350 | 806(B)4408 | 10' MTG.HT.TS PED.POLE(G.STL.) | 3.000 | EA |
| 1360 | 806(B)4416 | 12' MTG.HT.TS PED.POLE(ALUMINUM) | 9.000 | EA |
| 1370 | 806(C)4492 | 30' MTG & 8' HLMA(G.STL.) | 2.000 | EA |
| 1371 | 806(C)4536 | POWDER COAT LIGHTING POLE | 2.000 | EA |
| 1372 | 806(E)4700 | DECORATIVE POLE AND MAST ARM | 10.000 | EA |
| 1373 | 806(E)4710 | DECORATIVE POLE AND TWIN MAST ARM | 1.000 | EA |
| 1380 | 809(A)7200 | ROADWAY LUMINAIRE | 6.000 | EA |
| 1390 | 810(A)8200 | SERVICE POLE | 3.000 | EA |
| 1400 | 810(B)8300 | POLE-MOUNTED TRANSFORMER STATION | 1.000 | EA |
| 1410 | 811 9120 | 1/C NO.6 ELECT.COND. | 345.000 | LF |
| 1420 | 811 9130 | 1/C NO.10 ELECT.COND. | 4,715.000 | LF |
| 1430 | 825 8100 | TRAFFIC SIGNAL CONTROLLER ASSEMBLY | 3.000 | EA |
| 1440 | 828 0100 | (PL)DETECTION SYSTEM (VIDEO) | 1.000 | LSUM |
| 1450 | 830 2100 | PEDESTRIAN PUSH BUTTON | 16.000 | EA |
| 1460 | 831 3100 | TRAFFIC SIGNAL HEADS | 2.000 | EA |
| 1470 | 831 3116 | 1WAY2SEC.ADJ.PED.SIG.HD.S-20 | 16.000 | EA |
| 1480 | 831 3120 | 1WAY3SEC.ADJ.SIG.HD.S-6 | 24.000 | EA |
| 1490 | 831 3124 | 1WAY3SEC.ADJ.SIG.HD.S-9 | 2.000 | EA |
| 1500 | 831 3136 | 1WAY3SEC.ADJ.SIG.HD.S-12 | 7.000 | EA |
| 1510 | 831 3144 | 1WAY4SEC.ADJ.SIG.HD.S-13 | 3.000 | EA |
| 1520 | 831 3152 | 1WAY5SEC.ADJ.SIG.HD.S-17 | 1.000 | EA |
| 1530 | 831 3156 | 1WAY5SEC.ADJ.SIG.HD.S-19 | 1.000 | EA |
| 1540 | 833 5100 | BACKPLATE | 38.000 | EA |
| 1550 | 834(A)6205 | 5/C TRAFFIC SIGNAL ELECTRICAL CABLE | 1,495.000 | LF |
| 1560 | 834(A)6210 | 7/C TRAFFIC SIGNAL ELECTRICAL CABLE | 1,730.000 | LF |
| 1570 | 834(A)6225 | 15/C TRAFFIC SIGNAL ELECTRICAL CABLE | 680.000 | LF |
| 1580 | 834(A)6235 | 21/C TRAFFIC SIGNAL ELECTRICAL CABLE | 1,135.000 | LF |
| 1590 | 834(B)6300 | 2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE | 2,165.000 | LF |
| 1600 | 850(C)1410 | INSTALL MAST ARM MOUNTED ALUM SIGNS | 254.000 | SF |

**Proposal:**210239 **Let Date:**July 10, 2025 **Call Order:**535
**J/P Num:**32255(04) **Proj. Num:**SSP-263B(069)PM
**Counties:**POTTAWATOMIE
**Description:**GRADE, DRAIN, AND SURFACE
US-270B/CITY STREET (KICKAPOO STREET): US-270B,
FROM HIGHLAND STREET EXTEND NORTH IN SHAWNEE. KICKAPOO STREET,
FROM THE SH-18 JUNCTION EXTEND NORTH IN SHAWNEE.
PROJECT LENGTH = 1.568 MILES

| | Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|---|
| **0005** | LIGHTING | | | | |
| | 1610 | 802(B)0320 | 2" PVC SCH.40 PLASTIC CONDUIT BORED | 85.000 | LF |
| | 1620 | 802(B)0324 | 2" PVC SCH.40 PLASTIC CONDUIT TRENCHED | 15,805.000 | LF |
| | 1630 | 803(A)1210 | PULL BOX(SIZE I) | 150.000 | EA |
| | 1640 | 804(A)2200 | STRUCTURAL CONCRETE | 96.000 | CY |
| | 1650 | 804(B)2300 | REINFORCING STEEL | 16,472.000 | LB |
| | 1660 | 806(E)4700 | DECORATIVE POLE AND MAST ARM | 58.000 | EA |
| | 1670 | 810(A)8200 | SERVICE POLE | 2.000 | EA |
| | 1680 | 811 9115 | 1/C NO.4 ELECT.COND. | 48,050.000 | LF |
| | 1690 | 811 9130 | 1/C NO.10 ELECT.COND. | 5,220.000 | LF |
| **0006** | STAKING | | | | |
| | 1700 | 642(B)3300 | CONSTRUCTION STAKING LEVEL II | 1.000 | LSUM |
| **0007** | CONSTRUCTION | | | | |
| | 1710 | 220 1100 | SWPPP DOCUMENTATION AND MANAGEMENT | 1.000 | LSUM |
| | 1720 | 640(A)1210 | FIELD OFFICE | 1.000 | EA |
| | 1730 | 641 2110 | MOBILIZATION | 1.000 | LSUM |

**Proposal:**210239 **Let Date:**July 10, 2025 **Call Order:**535
**J/P Num:**32255(04) **Proj. Num:**SSP-263B(069)PM
**Counties:**POTTAWATOMIE
**Description:**GRADE, DRAIN, AND SURFACE
US-270B/CITY STREET (KICKAPOO STREET): US-270B,
FROM HIGHLAND STREET EXTEND NORTH IN SHAWNEE. KICKAPOO STREET,
FROM THE SH-18 JUNCTION EXTEND NORTH IN SHAWNEE.
PROJECT LENGTH = 1.568 MILES

| | Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|---|
| **0008** | WATERLINE RELOCATION (FARRELL ST. TO ST. BENEDICT ST.) - (NON-PARTICIPATI | | | | |
| | 1740 | 612(I)4000 | WATER METER RESET | 71.000 | EA |
| | 1750 | 613(U)7925 | BORE & JACK 33" CASING | 165.000 | LF |
| | 1760 | 616(A)2236 | 24" DUCTILE IRON PIPE | 590.000 | LF |
| | 1770 | 616(A)2292 | DUCTILE IRON FITTINGS | 4.000 | LB |
| | 1780 | 616(B)2332 | 4" POLYVINYL CHLORIDE (PVC) PIPE | 40.000 | LF |
| | 1790 | 616(B)2336 | 6" POLYVINYL CHLORIDE (PVC) PIPE | 257.000 | LF |
| | 1800 | 616(B)2340 | 8" POLYVINYL CHLORIDE (PVC) PIPE | 70.000 | LF |
| | 1810 | 616(B)2344 | 10" POLYVINYL CHLORIDE (PVC) PIPE | 25.000 | LF |
| | 1820 | 616(B)2352 | 12" POLYVINYL CHLORIDE (PVC) PIPE | 55.000 | LF |
| | 1830 | 616(D)2538 | 2" COMB.AIR RELEASE ASSEMBLY AND VAULT | 2.000 | EA |
| | 1840 | 616(D)2646 | 6" GATE VALVE | 17.000 | EA |
| | 1850 | 616(D)2650 | 8" GATE VALVE | 3.000 | EA |
| | 1860 | 616(D)2654 | 10" GATE VALVE | 1.000 | EA |
| | 1870 | 616(D)2658 | 12" GATE VALVE | 2.000 | EA |
| | 1880 | 616(D)2688 | 24" BUTTERFLY VALVE | 8.000 | EA |
| | 1890 | 616(D)2828 | 14" TAPPING VALVE AND BOX | 1.000 | EA |
| | 1900 | 616(G)3111 | FIRE HYDRANT AND ASSEMBLY | 12.000 | EA |
| | 1910 | 616(I)3336 | 33" STEEL CASING | 150.000 | LF |
| | 1920 | 616(K)3508 | 4" SOLID SLEEVE | 1.000 | EA |
| | 1930 | 616(K)3512 | 6" SOLID SLEEVE | 8.000 | EA |
| | 1940 | 616(K)3516 | 8" SOLID SLEEVE | 3.000 | EA |
| | 1950 | 616(K)3520 | 10" SOLID SLEEVE | 1.000 | EA |
| | 1960 | 616(K)3524 | 12" SOLID SLEEVE | 2.000 | EA |
| | 1970 | 616(K)3526 | 14" SOLID SLEEVE | 1.000 | EA |
| | 1980 | 616(K)3536 | 24" SOLID SLEEVE | 1.000 | EA |
| | 1990 | 616(N)3800 | SERVICE CONNECTION (SHORT) | 41.000 | EA |
| | 2000 | 616(N)3805 | SERVICE CONNECTION (LONG) | 45.000 | EA |
| | 2010 | 616(O)3985 | 6" 45 DEGREE FITTING | 11.000 | EA |
| | 2020 | 616(O)4010 | 8" 45 DEGREE FITTING | 4.000 | EA |
| | 2030 | 616(O)4025 | 10" 45 DEGREE FITTING | 2.000 | EA |
| | 2040 | 616(O)4045 | 12" 45 DEGREE FITTING | 3.000 | EA |
| | 2050 | 616(O)4076 | 24" 11 1/4 DEGREE FITTING | 4.000 | EA |
| | 2060 | 616(O)4078 | 24" 45 DEGREE FITTING | 5.000 | EA |
| | 2070 | 616(O)4079 | 24" 90 DEGREE FITTING | 4.000 | EA |
| | 2080 | 616(P)4164 | 24" HDPE PIPE | 4,481.000 | LF |
| | 2090 | 616(R)4324 | 6" X 4" REDUCER | 1.000 | EA |
| | 2100 | 616(R)4352 | 12" X 10" REDUCER | 1.000 | EA |
| | 2110 | 616(R)4370 | 24" X 6" REDUCER | 1.000 | EA |
| | 2120 | 616(R)4373 | 24" X 14" REDUCER | 1.000 | EA |
| | 2130 | 616(S)4405 | 6" PLUG | 1.000 | EA |
| | 2140 | 616(S)4410 | 8" PLUG | 2.000 | EA |
| | 2150 | 616(S)4420 | 12" PLUG | 1.000 | EA |
| | 2160 | 616(S)4422 | 14" PLUG | 1.000 | EA |
| | 2170 | 616(T)4648 | 24" X 24" X 6" TEE | 18.000 | EA |
| | 2180 | 616(T)4650 | 24" X 24" X 8" TEE | 2.000 | EA |

**Proposal:**210239 **Let Date:**July 10, 2025 **Call Order:**535
**J/P Num:**32255(04) **Proj. Num:**SSP-263B(069)PM
**Counties:**POTTAWATOMIE
**Description:**GRADE, DRAIN, AND SURFACE
US-270B/CITY STREET (KICKAPOO STREET): US-270B,
FROM HIGHLAND STREET EXTEND NORTH IN SHAWNEE. KICKAPOO STREET,
FROM THE SH-18 JUNCTION EXTEND NORTH IN SHAWNEE.
PROJECT LENGTH = 1.568 MILES

| | Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|---|
| **0008** | WATERLINE RELOCATION (FARRELL ST. TO ST. BENEDICT ST.) - (NON-PARTICIPATI | | | | |
| | 2190 | 616(T)4655 | 24" X 24" X 12" TEE | 3.000 | EA |
| | 2200 | 616(T)4657 | 24" X 24" X 16" TEE | 1.000 | EA |
| | 2210 | 616(V)4800 | HYDROSTATIC PRESSURE TESTING & DISINFECT | 1.000 | LSUM |
| **0009** | (EXIST 24" WATERLINE IMPROVEMENTS) - (NON-PARTICIPATING) | | | | |
| | 2220 | 612(I)4000 | WATER METER RESET | 46.000 | EA |
| | 2230 | 616(B)2336 | 6" POLYVINYL CHLORIDE (PVC) PIPE | 113.000 | LF |
| | 2240 | 616(B)2340 | 8" POLYVINYL CHLORIDE (PVC) PIPE | 20.000 | LF |
| | 2250 | 616(D)2790 | 24" X 6" TAPPING SLEEVE | 11.000 | EA |
| | 2260 | 616(D)2791 | 24" X 8" TAPPING SLEEVE | 2.000 | EA |
| | 2270 | 616(D)2812 | 6" TAPPING VALVE AND BOX | 11.000 | EA |
| | 2280 | 616(D)2816 | 8" TAPPING VALVE AND BOX | 2.000 | EA |
| | 2290 | 616(G)3111 | FIRE HYDRANT AND ASSEMBLY | 5.000 | EA |
| | 2300 | 616(K)3512 | 6" SOLID SLEEVE | 6.000 | EA |
| | 2310 | 616(K)3516 | 8" SOLID SLEEVE | 2.000 | EA |
| | 2320 | 616(N)3800 | SERVICE CONNECTION (SHORT) | 30.000 | EA |
| | 2330 | 616(N)3805 | SERVICE CONNECTION (LONG) | 9.000 | EA |
| | 2340 | 616(O)3985 | 6" 45 DEGREE FITTING | 12.000 | EA |
| | 2350 | 616(O)4010 | 8" 45 DEGREE FITTING | 4.000 | EA |