Letting Date: February 17, 2022, 10:30 A.M.
Call Order: 440 **Contract ID:** 220060
J/P No.: 34373(04) **Project No.:** SSR-231C(047)SR **Contract Time:**
County: HASKELL
Description: RESURFACE (ASPHALT)
SH-82: FROM THE LATIMER COUNTY LINE, EXTEND NORTH.
PROJECT LENGTH = 3.200 MILES

	VENDORNAME	PROPOSALITEMTO		
1	APAC-CENTRAL, INC.	1,171,784.23	94.45	100.00
2	Rosscon, LLC	1,220,132.22	98.35	104.13
	Engineer's Estimate	1,240,655.10		
3	Robinson Construction, LLC	1,326,908.59	106.95	113.24

Letting Date: February 17, 2022, 10:30 A.M.
Call Order: 440 **Contract ID:** 220060

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0010	407(B)7300	TACK COAT	7,563.000	GAL
	Engineer's Estimate		**2.00**	**15,126.00**
1	APAC-CENTRAL, INC.		2.55	19,285.65
2	Rosscon, LLC		2.50	18,907.50
3	Robinson Construction, LLC		4.00	30,252.00
0020	411(C)1431	SUPERPAVE, TYPE B4(PG 64-22 OK)	9,787.000	TON
	Engineer's Estimate		**100.00**	**978,700.00**
1	APAC-CENTRAL, INC.		96.10	940,530.70
2	Rosscon, LLC		102.00	998,274.00
3	Robinson Construction, LLC		108.55	1,062,378.85
0030	412 3100	COLD MILLING PAVEMENT	88,966.000	SY
	Engineer's Estimate		**2.00**	**177,932.00**
1	APAC-CENTRAL, INC.		1.73	153,911.18
2	Rosscon, LLC		1.50	133,449.00
3	Robinson Construction, LLC		1.85	164,587.10
0040	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	16,280.000	LF
	Engineer's Estimate		**0.45**	**7,326.00**
1	APAC-CENTRAL, INC.		0.16	2,604.80
2	Rosscon, LLC		0.17	2,767.60
3	Robinson Construction, LLC		0.18	2,930.40
0050	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	32,560.000	LF
	Engineer's Estimate		**0.45**	**14,652.00**
1	APAC-CENTRAL, INC.		0.16	5,209.60
2	Rosscon, LLC		0.17	5,535.20
3	Robinson Construction, LLC		0.18	5,860.80

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 TRAFFIC				
0060	856(A)8200	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	66,498.000	LF
	Engineer's Estimate		**0.40**	**26,599.20**
1	APAC-CENTRAL, INC.		0.45	29,924.10
2	Rosscon, LLC		0.49	32,584.02
3	Robinson Construction, LLC		0.53	35,243.94
0070	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	780.000	SD
	Engineer's Estimate		**1.25**	**975.00**
1	APAC-CENTRAL, INC.		0.26	202.80
2	Rosscon, LLC		0.28	218.40
3	Robinson Construction, LLC		0.30	234.00
0080	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	630.000	SD
	Engineer's Estimate		**1.35**	**850.50**
1	APAC-CENTRAL, INC.		0.26	163.80
2	Rosscon, LLC		0.28	176.40
3	Robinson Construction, LLC		0.30	189.00

Letting Date: February 17, 2022, 10:30 A.M.
Call Order: 440 **Contract ID:** 220060

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 TRAFFIC					
0090	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,080.000	SD	
	Engineer's Estimate		**2.10**		**2,268.00**
1	APAC-CENTRAL, INC.		1.04		1,123.20
2	Rosscon, LLC		1.10		1,188.00
3	Robinson Construction, LLC		1.20		1,296.00
0100	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	300.000	SD	
	Engineer's Estimate		**1.05**		**315.00**
1	APAC-CENTRAL, INC.		0.26		78.00
2	Rosscon, LLC		0.28		84.00
3	Robinson Construction, LLC		0.30		90.00
0110	880(C)6420	WING BARRICADES	150.000	SD	
	Engineer's Estimate		**1.42**		**213.00**
1	APAC-CENTRAL, INC.		0.02		3.00
2	Rosscon, LLC		0.03		4.50
3	Robinson Construction, LLC		0.03		4.50
0120	880(E)6600	WARNING LIGHTS(TYPE A)	450.000	SD	
	Engineer's Estimate		**0.20**		**90.00**
1	APAC-CENTRAL, INC.		3.10		1,395.00
2	Rosscon, LLC		3.30		1,485.00
3	Robinson Construction, LLC		3.60		1,620.00
0130	880(F)6700	DRUMS	1,020.000	SD	
	Engineer's Estimate		**0.12**		**122.40**
1	APAC-CENTRAL, INC.		0.26		265.20
2	Rosscon, LLC		0.28		285.60
3	Robinson Construction, LLC		0.30		306.00
0140	880(G)6805	CHANNELIZER CONES	4,860.000	SD	
	Engineer's Estimate		**0.10**		**486.00**
1	APAC-CENTRAL, INC.		0.52		2,527.20
2	Rosscon, LLC		0.55		2,673.00
3	Robinson Construction, LLC		0.60		2,916.00
0150	880(I)7000	FLAGGER	60.000	SD	
	Engineer's Estimate		**150.00**		**9,000.00**
1	APAC-CENTRAL, INC.		1.00		60.00
2	Rosscon, LLC		300.00		18,000.00
3	Robinson Construction, LLC		150.00		9,000.00
0160	880(W)7700	PILOT CAR	1.000	LSUM	
	Engineer's Estimate		**6,000.00**		**6,000.00**
1	APAC-CENTRAL, INC.		14,500.00		14,500.00
2	Rosscon, LLC		4,500.00		4,500.00
3	Robinson Construction, LLC		10,000.00		10,000.00