Letting Date: March 17, 2022, 10:30 A.M.
Call Order: 870 **Contract ID:** 220108
J/P No.: 33835(04) **Project No.:** STP-268C(077)3P **Contract Time:**
County: SEQUOYAH
Description: PAVEMENT REHABILITATION (P.C. CONCRETE)
US-64: FROM THE SH-10 JUNCTION, EXTEND EAST NEAR GORE.
PROJECT LENGTH = 3.250 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	1,982,196.50		
1	Diamond Surface, Inc.	2,819,609.27	142.25	100.00
2	EMERY SAPP & SONS, INC.	2,944,300.27	148.54	104.42

Letting Date: March 17, 2022, 10:30 A.M.
Call Order: 870 **Contract ID:** 220108

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0010	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	50.000 TON	
	Engineer's Estimate		**26.00**	**1,300.00**
1	Diamond Surface, Inc.		101.50	5,075.00
2	EMERY SAPP & SONS, INC.		31.00	1,550.00
0020	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	17,160.000 LF	
	Engineer's Estimate		**0.50**	**8,580.00**
1	Diamond Surface, Inc.		0.73	12,526.80
2	EMERY SAPP & SONS, INC.		0.52	8,923.20
0030	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	1,042.000 SY	
	Engineer's Estimate		**120.00**	**125,040.00**
1	Diamond Surface, Inc.		227.00	236,534.00
2	EMERY SAPP & SONS, INC.		223.00	232,366.00
0040	414(G)5800	P.C. CONCRETE FOR PAVEMENT	232.000 CY	
	Engineer's Estimate		**175.00**	**40,600.00**
1	Diamond Surface, Inc.		681.00	157,992.00
2	EMERY SAPP & SONS, INC.		712.00	165,184.00
0050	415 7100	CONCRETE JOINT SEALING	44,616.000 LF	
	Engineer's Estimate		**2.50**	**111,540.00**
1	Diamond Surface, Inc.		2.95	131,617.20
2	EMERY SAPP & SONS, INC.		2.53	112,878.48
0060	416 8100	DOWEL BAR RETROFIT	13,728.000 EA	
	Engineer's Estimate		**40.00**	**549,120.00**
1	Diamond Surface, Inc.		47.15	647,275.20
2	EMERY SAPP & SONS, INC.		55.00	755,040.00
0070	425 0100	DIAMOND GRINDING CONCRETE PAVEMENT	45,760.000 SY	
	Engineer's Estimate		**6.00**	**274,560.00**
1	Diamond Surface, Inc.		5.51	252,137.60
2	EMERY SAPP & SONS, INC.		6.05	276,848.00
0080	509(A)0200	CLASS AA CONCRETE	15.000 CY	
	Engineer's Estimate		**400.00**	**6,000.00**
1	Diamond Surface, Inc.		437.50	6,562.50
2	EMERY SAPP & SONS, INC.		1,368.00	20,520.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 TRAFFIC				
0090	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	1,800.000 LF	
	Engineer's Estimate		**25.00**	**45,000.00**
1	Diamond Surface, Inc.		74.25	133,650.00
2	EMERY SAPP & SONS, INC.		19.00	34,200.00
0100	628(C)7400	END ANCHORS	18.000 EA	
	Engineer's Estimate		**2,500.00**	**45,000.00**
1	Diamond Surface, Inc.		6,500.00	117,000.00
2	EMERY SAPP & SONS, INC.		16,527.00	297,486.00

Letting Date: March 17, 2022, 10:30 A.M.
Call Order: 870 **Contract ID:** 220108

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 TRAFFIC					
0110	628(E)7600	CABLE BARRIER TENSION METER	1.000	EA	
	Engineer's Estimate		**4,000.00**		**4,000.00**
1	Diamond Surface, Inc.		7,415.00		7,415.00
2	EMERY SAPP & SONS, INC.		4,788.00		4,788.00
0120	805(A)3204	REMOVAL OF CLASS C PAVEMENT MARKERS	110.000	EA	
	Engineer's Estimate		**7.50**		**825.00**
1	Diamond Surface, Inc.		25.00		2,750.00
2	EMERY SAPP & SONS, INC.		54.00		5,940.00
0130	856(A)8200	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	57,495.000	LF	
	Engineer's Estimate		**0.75**		**43,121.25**
1	Diamond Surface, Inc.		0.49		28,172.55
2	EMERY SAPP & SONS, INC.		0.44		25,297.80
0140	880(A)6220	ARROW DISPLAY(TYPE C)	120.000	SD	
	Engineer's Estimate		**10.00**		**1,200.00**
1	Diamond Surface, Inc.		1.25		150.00
2	EMERY SAPP & SONS, INC.		1.14		136.80
0150	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,380.000	SD	
	Engineer's Estimate		**0.50**		**690.00**
1	Diamond Surface, Inc.		1.25		1,725.00
2	EMERY SAPP & SONS, INC.		1.14		1,573.20
0160	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,080.000	SD	
	Engineer's Estimate		**1.00**		**1,080.00**
1	Diamond Surface, Inc.		1.25		1,350.00
2	EMERY SAPP & SONS, INC.		1.14		1,231.20
0170	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,920.000	SD	
	Engineer's Estimate		**3.00**		**5,760.00**
1	Diamond Surface, Inc.		1.25		2,400.00
2	EMERY SAPP & SONS, INC.		1.14		2,188.80
0180	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	600.000	SD	
	Engineer's Estimate		**1.00**		**600.00**
1	Diamond Surface, Inc.		0.63		378.00
2	EMERY SAPP & SONS, INC.		0.57		342.00
0190	880(C)6420	WING BARRICADES	300.000	SD	
	Engineer's Estimate		**1.50**		**450.00**
1	Diamond Surface, Inc.		1.25		375.00
2	EMERY SAPP & SONS, INC.		1.14		342.00
0200	880(E)6600	WARNING LIGHTS(TYPE A)	900.000	SD	
	Engineer's Estimate		**1.00**		**900.00**
1	Diamond Surface, Inc.		1.25		1,125.00
2	EMERY SAPP & SONS, INC.		1.14		1,026.00
0210	880(F)6700	DRUMS	2,040.000	SD	
	Engineer's Estimate		**0.75**		**1,530.00**
1	Diamond Surface, Inc.		0.63		1,285.20
2	EMERY SAPP & SONS, INC.		0.57		1,162.80

Letting Date: March 17, 2022, 10:30 A.M.
Call Order: 870 **Contract ID:** 220108

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0002**	**TRAFFIC**		
0220	880(G)6805	CHANNELIZER CONES	9,720.000	SD
	Engineer's Estimate		**0.75**	**7,290.00**
1	Diamond Surface, Inc.		0.32	3,110.40
2	EMERY SAPP & SONS, INC.		0.28	2,721.60
0230	880(I)7000	FLAGGER	60.000	SD
	Engineer's Estimate		**200.00**	**12,000.00**
1	Diamond Surface, Inc.		2,105.00	126,300.00
2	EMERY SAPP & SONS, INC.		1,360.00	81,600.00
0240	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	148.000	SD
	Engineer's Estimate		**12.00**	**1,776.00**
1	Diamond Surface, Inc.		31.25	4,625.00
2	EMERY SAPP & SONS, INC.		29.00	4,292.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0003**	**ROADWAY - ADD ALTERNATE 1**		
0250	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	9,762.000	LF
	Engineer's Estimate		**0.50**	**4,881.00**
1	Diamond Surface, Inc.		0.75	7,321.50
2	EMERY SAPP & SONS, INC.		0.63	6,150.06
0260	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	875.000	SY
	Engineer's Estimate		**120.00**	**105,000.00**
1	Diamond Surface, Inc.		227.00	198,625.00
2	EMERY SAPP & SONS, INC.		165.00	144,375.00
0270	414(G)5800	P.C. CONCRETE FOR PAVEMENT	195.000	CY
	Engineer's Estimate		**175.00**	**34,125.00**
1	Diamond Surface, Inc.		681.00	132,795.00
2	EMERY SAPP & SONS, INC.		712.00	138,840.00
0280	415 7100	CONCRETE JOINT SEALING	25,381.000	LF
	Engineer's Estimate		**2.50**	**63,452.50**
1	Diamond Surface, Inc.		2.95	74,873.95
2	EMERY SAPP & SONS, INC.		2.53	64,213.93
0290	416 8100	DOWEL BAR RETROFIT	7,810.000	EA
	Engineer's Estimate		**40.00**	**312,400.00**
1	Diamond Surface, Inc.		47.15	368,241.50
2	EMERY SAPP & SONS, INC.		49.00	382,690.00
0300	425 0100	DIAMOND GRINDING CONCRETE PAVEMENT	26,032.000	SY
	Engineer's Estimate		**6.00**	**156,192.00**
1	Diamond Surface, Inc.		5.51	143,436.32
2	EMERY SAPP & SONS, INC.		6.05	157,493.60

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section:	**0004**	**TRAFFIC - ADD ALTERNATE 1**		

Letting Date: March 17, 2022, 10:30 A.M.
Call Order: 870 **Contract ID:** 220108

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0004	**TRAFFIC - ADD ALTERNATE 1**				
0310	805(A)3204	REMOVAL OF CLASS C PAVEMENT MARKERS	45.000	EA	
	Engineer's Estimate		**7.50**		**337.50**
1	Diamond Surface, Inc.		25.00		1,125.00
2	EMERY SAPP & SONS, INC.		54.00		2,430.00
0320	856(A)8200	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	23,795.000	LF	
	Engineer's Estimate		**0.75**		**17,846.25**
1	Diamond Surface, Inc.		0.49		11,659.55
2	EMERY SAPP & SONS, INC.		0.44		10,469.80