**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127
**J/P No.:** 31985(04) **Project No.:** STP-237C(092)CI **Contract Time:**
**County:** KINGFISHER
**Description:** BRIDGE AND APPROACHES
COUNTY ROAD (EW-72): OVER TREATY CREEK,
4.1 MILES WEST OF US-81 NEAR DOVER.
PROJECT LENGTH = 0.208 MILE

| | VENDORNAME | PROPOSALITEMTO | | |
|---|---|---|---|---|
| | Engineer's Estimate | 888,617.30 | | |
| 1 | RRY SERVICES LLC | 922,368.27 | 103.80 | 100.00 |
| 2 | K & R BUILDERS, INC. | 942,214.11 | 106.03 | 102.15 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | 969,839.75 | 109.14 | 105.15 |
| 4 | BRIDGECO CONTRACTORS, INC. | 1,072,902.34 | 120.74 | 116.32 |

**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127

| Line # | Item Number | Item Description | Quantity/Unit | | |
|---|---|---|---|---|---|
| | Bidder | | Unit Price | | Ext Amount |
| **Section: 0001** | **ROADWAY** | | | | |
| 0010 | 201(A)1200 | CLEARING AND GRUBBING | 1.000 | LSUM | |
| | **Engineer's Estimate** | | **8,000.00** | | **8,000.00** |
| 1 | RRY SERVICES LLC | | 10,000.00 | | 10,000.00 |
| 2 | K & R BUILDERS, INC. | | 9,000.00 | | 9,000.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 16,260.00 | | 16,260.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 33,495.00 | | 33,495.00 |
| 0020 | 202(A)2200 | UNCLASSIFIED EXCAVATION | 3,427.000 | CY | |
| | **Engineer's Estimate** | | **7.50** | | **25,702.50** |
| 1 | RRY SERVICES LLC | | 6.50 | | 22,275.50 |
| 2 | K & R BUILDERS, INC. | | 9.00 | | 30,843.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 7.90 | | 27,073.30 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 8.25 | | 28,272.75 |
| 0030 | 202(D)2500 | UNCLASSIFIED BORROW | 400.000 | CY | |
| | **Engineer's Estimate** | | **12.00** | | **4,800.00** |
| 1 | RRY SERVICES LLC | | 8.00 | | 3,200.00 |
| 2 | K & R BUILDERS, INC. | | 1.02 | | 408.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 12.70 | | 5,080.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 18.00 | | 7,200.00 |
| 0040 | 205(A)6200 | TYPE A-SALVAGED TOPSOIL | 1.000 | LSUM | |
| | **Engineer's Estimate** | | **7,500.00** | | **7,500.00** |
| 1 | RRY SERVICES LLC | | 9,500.00 | | 9,500.00 |
| 2 | K & R BUILDERS, INC. | | 7,750.00 | | 7,750.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 13,935.00 | | 13,935.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 12,650.00 | | 12,650.00 |
| 0050 | 221(B)2300 | TEMPORARY SILT FENCE | 1,400.000 | LF | |
| | **Engineer's Estimate** | | **2.75** | | **3,850.00** |
| 1 | RRY SERVICES LLC | | 2.42 | | 3,388.00 |
| 2 | K & R BUILDERS, INC. | | 2.00 | | 2,800.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 2.35 | | 3,290.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 2.50 | | 3,500.00 |
| 0060 | 221(E)2600 | TEMPORARY SILT DIKE | 448.000 | LF | |
| | **Engineer's Estimate** | | **12.50** | | **5,600.00** |
| 1 | RRY SERVICES LLC | | 14.50 | | 6,496.00 |
| 2 | K & R BUILDERS, INC. | | 10.00 | | 4,480.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 13.20 | | 5,913.60 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 14.50 | | 6,496.00 |
| 0070 | 230(A)7200 | SOLID SLAB SODDING | 10,299.000 | SY | |
| | **Engineer's Estimate** | | **3.50** | | **36,046.50** |
| 1 | RRY SERVICES LLC | | 2.32 | | 23,893.68 |
| 2 | K & R BUILDERS, INC. | | 3.30 | | 33,986.70 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 2.35 | | 24,202.65 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 2.50 | | 25,747.50 |
| 0080 | 233(A)0200 | VEGETATIVE MULCHING | 2.130 | AC | |
| | **Engineer's Estimate** | | **800.00** | | **1,704.00** |
| 1 | RRY SERVICES LLC | | 200.00 | | 426.00 |
| 2 | K & R BUILDERS, INC. | | 500.00 | | 1,065.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 844.50 | | 1,798.79 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 1,200.00 | | 2,556.00 |

**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127

| Line # | Item Number | Item Description | Quantity/Unit |
|---|---|---|---|
| | Bidder | | Unit Price / Ext Amount |

**Section: 0001 ROADWAY**

| | | | | |
|---|---|---|---|---|
| 0090 | 307(K)4200 | STABILIZED SUBGRADE | 3,164.000 | SY |
| | **Engineer's Estimate** | | **10.00** | **31,640.00** |
| 1 | RRY SERVICES LLC | | 7.50 | 23,730.00 |
| 2 | K & R BUILDERS, INC. | | 8.25 | 26,103.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 18.90 | 59,799.60 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 9.00 | 28,476.00 |
| 0100 | 402(E)2600 | TRAFFIC BOUND SURFACE COURSE TYPE E | 186.000 | TON |
| | **Engineer's Estimate** | | **50.00** | **9,300.00** |
| 1 | RRY SERVICES LLC | | 60.00 | 11,160.00 |
| 2 | K & R BUILDERS, INC. | | 55.70 | 10,360.20 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 47.30 | 8,797.80 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 52.50 | 9,765.00 |
| 0110 | 408 8100 | PRIME COAT | 1,108.000 | GAL |
| | **Engineer's Estimate** | | **5.85** | **6,481.80** |
| 1 | RRY SERVICES LLC | | 6.00 | 6,648.00 |
| 2 | K & R BUILDERS, INC. | | 6.00 | 6,648.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 8.20 | 9,085.60 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 7.15 | 7,922.20 |
| 0120 | 411(B)1330 | SUPERPAVE, TYPE S3(PG 64-22 OK) | 999.000 | TON |
| | **Engineer's Estimate** | | **125.00** | **124,875.00** |
| 1 | RRY SERVICES LLC | | 113.00 | 112,887.00 |
| 2 | K & R BUILDERS, INC. | | 124.30 | 124,175.70 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 104.50 | 104,395.50 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 140.00 | 139,860.00 |
| 0130 | 411(C)1430 | SUPERPAVE, TYPE S4(PG 64-22 OK) | 338.000 | TON |
| | **Engineer's Estimate** | | **140.00** | **47,320.00** |
| 1 | RRY SERVICES LLC | | 150.00 | 50,700.00 |
| 2 | K & R BUILDERS, INC. | | 165.00 | 55,770.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 135.00 | 45,630.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 170.00 | 57,460.00 |
| 0140 | 509(B)0300 | CLASS A CONCRETE | 10.800 | CY |
| | **Engineer's Estimate** | | **575.00** | **6,210.00** |
| 1 | RRY SERVICES LLC | | 700.00 | 7,560.00 |
| 2 | K & R BUILDERS, INC. | | 650.00 | 7,020.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 537.50 | 5,805.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 700.00 | 7,560.00 |
| 0150 | 509(D)0500 | CLASS C CONCRETE | 10.000 | CY |
| | **Engineer's Estimate** | | **325.00** | **3,250.00** |
| 1 | RRY SERVICES LLC | | 300.00 | 3,000.00 |
| 2 | K & R BUILDERS, INC. | | 375.00 | 3,750.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 572.50 | 5,725.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 375.00 | 3,750.00 |
| 0160 | 511(A)2200 | REINFORCING STEEL | 142.000 | LB |
| | **Engineer's Estimate** | | **1.50** | **213.00** |
| 1 | RRY SERVICES LLC | | 2.00 | 284.00 |
| 2 | K & R BUILDERS, INC. | | 4.00 | 568.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 5.10 | 724.20 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 5.00 | 710.00 |

**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127

| Line # | Item Number | Item Description | Quantity/Unit | | |
|---|---|---|---|---|---|
| | Bidder | | Unit Price | | Ext Amount |
| **Section: 0001** | **ROADWAY** | | | | |
| 0170 | 601(B)1220 | TYPE I-A PLAIN RIPRAP | 217.000 | TON | |
| | **Engineer's Estimate** | | **62.00** | | **13,454.00** |
| 1 | RRY SERVICES LLC | | 70.00 | | 15,190.00 |
| 2 | K & R BUILDERS, INC. | | 74.25 | | 16,112.25 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 65.30 | | 14,170.10 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 63.50 | | 13,779.50 |
| 0180 | 601(C)1300 | TYPE I-A FILTER BLANKET | 72.000 | TON | |
| | **Engineer's Estimate** | | **55.00** | | **3,960.00** |
| 1 | RRY SERVICES LLC | | 50.00 | | 3,600.00 |
| 2 | K & R BUILDERS, INC. | | 61.00 | | 4,392.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 52.60 | | 3,787.20 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 61.00 | | 4,392.00 |
| 0190 | 613(EE)5972 | (SP) 24" CORRUGATED POLYPROPYLENE PIPE | 112.000 | LF | |
| | **Engineer's Estimate** | | **130.00** | | **14,560.00** |
| 1 | RRY SERVICES LLC | | 120.00 | | 13,440.00 |
| 2 | K & R BUILDERS, INC. | | 72.00 | | 8,064.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 99.00 | | 11,088.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 112.82 | | 12,635.84 |
| 0200 | 613(EE)5988 | (SP) 48" CORRUGATED POLYPROPYLENE PIPE | 70.000 | LF | |
| | **Engineer's Estimate** | | **162.75** | | **11,392.50** |
| 1 | RRY SERVICES LLC | | 275.00 | | 19,250.00 |
| 2 | K & R BUILDERS, INC. | | 166.00 | | 11,620.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 206.50 | | 14,455.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 241.66 | | 16,916.20 |
| 0210 | 613(EE)5996 | (SP) 60" CORRUGATED POLYPROPYLENE PIPE | 80.000 | LF | |
| | **Engineer's Estimate** | | **211.50** | | **16,920.00** |
| 1 | RRY SERVICES LLC | | 325.00 | | 26,000.00 |
| 2 | K & R BUILDERS, INC. | | 210.00 | | 16,800.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 286.00 | | 22,880.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 331.50 | | 26,520.00 |
| 0220 | 613(M)6904 | TYPE B3 CULVERT END TREATMENT | 4.000 | EA | |
| | **Engineer's Estimate** | | **1,600.00** | | **6,400.00** |
| 1 | RRY SERVICES LLC | | 1,850.00 | | 7,400.00 |
| 2 | K & R BUILDERS, INC. | | 1,150.00 | | 4,600.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 1,753.00 | | 7,012.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 3,100.00 | | 12,400.00 |
| 0230 | 613(M)6916 | TYPE E3 CULVERT END TREATMENT | 2.000 | EA | |
| | **Engineer's Estimate** | | **2,400.00** | | **4,800.00** |
| 1 | RRY SERVICES LLC | | 3,000.00 | | 6,000.00 |
| 2 | K & R BUILDERS, INC. | | 2,600.00 | | 5,200.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 2,630.00 | | 5,260.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 6,000.00 | | 12,000.00 |
| 0240 | 619(A)6200 | REMOVAL OF STRUCTURES & OBSTRUCTIONS | 1.000 | LSUM | |
| | **Engineer's Estimate** | | **4,000.00** | | **4,000.00** |
| 1 | RRY SERVICES LLC | | 2,000.00 | | 2,000.00 |
| 2 | K & R BUILDERS, INC. | | 8,000.00 | | 8,000.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 18,690.00 | | 18,690.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 17,600.00 | | 17,600.00 |

**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127

| Line # | Item Number | Item Description | Quantity/Unit | | |
|---|---|---|---|---|---|
| | Bidder | | Unit Price | | Ext Amount |
| **Section: 0001 ROADWAY** | | | | | |
| 0250 | 619(B)6364 | REMOVAL OF ASPHALT PAVEMENT | 2,491.000 | SY | |
| | **Engineer's Estimate** | | **7.25** | | **18,059.75** |
| 1 | RRY SERVICES LLC | | 4.00 | | 9,964.00 |
| 2 | K & R BUILDERS, INC. | | 3.75 | | 9,341.25 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 4.65 | | 11,583.15 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 9.00 | | 22,419.00 |
| 0260 | 619(C)6600 | SAWING PAVEMENT | 44.000 | LF | |
| | **Engineer's Estimate** | | **10.35** | | **455.40** |
| 1 | RRY SERVICES LLC | | 5.00 | | 220.00 |
| 2 | K & R BUILDERS, INC. | | 15.00 | | 660.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 6.55 | | 288.20 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 8.00 | | 352.00 |
| 0270 | 623(A)1200 | BEAM GUARDRAIL W-BEAM SINGLE | 75.000 | LF | |
| | **Engineer's Estimate** | | **28.00** | | **2,100.00** |
| 1 | RRY SERVICES LLC | | 42.00 | | 3,150.00 |
| 2 | K & R BUILDERS, INC. | | 46.20 | | 3,465.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 44.40 | | 3,330.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 46.20 | | 3,465.00 |
| 0280 | 623(F)1724 | GUARDRAIL ANCHOR UNIT (TYPE D-BF) | 4.000 | EA | |
| | **Engineer's Estimate** | | **3,500.00** | | **14,000.00** |
| 1 | RRY SERVICES LLC | | 2,400.00 | | 9,600.00 |
| 2 | K & R BUILDERS, INC. | | 2,640.00 | | 10,560.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 2,640.00 | | 10,560.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 2,650.00 | | 10,600.00 |
| 0290 | 623(G)1820 | GUARDRAIL END TREATMENT (31") | 4.000 | EA | |
| | **Engineer's Estimate** | | **3,000.00** | | **12,000.00** |
| 1 | RRY SERVICES LLC | | 2,400.00 | | 9,600.00 |
| 2 | K & R BUILDERS, INC. | | 2,640.00 | | 10,560.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 3,431.00 | | 13,724.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 2,650.00 | | 10,600.00 |

| Line # | Item Number | Item Description | Quantity/Unit | | |
|---|---|---|---|---|---|
| | Bidder | | Unit Price | | Ext Amount |
| **Section: 0002 BRIDGE 'A' - NBI NO. 32964** | | | | | |
| 0300 | 501(B)1300 | SUBSTRUCTURE EXCAVATION COMMON | 180.000 | CY | |
| | **Engineer's Estimate** | | **13.00** | | **2,340.00** |
| 1 | RRY SERVICES LLC | | 15.00 | | 2,700.00 |
| 2 | K & R BUILDERS, INC. | | 11.50 | | 2,070.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 17.90 | | 3,222.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 15.00 | | 2,700.00 |
| 0310 | 501(G)1800 | CLSM BACKFILL | 84.000 | CY | |
| | **Engineer's Estimate** | | **209.00** | | **17,556.00** |
| 1 | RRY SERVICES LLC | | 165.00 | | 13,860.00 |
| 2 | K & R BUILDERS, INC. | | 195.00 | | 16,380.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 212.00 | | 17,808.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 284.00 | | 23,856.00 |

**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127

| Line # | Item Number / Bidder | Item Description | Unit Price | Quantity/Unit | Ext Amount |
|---|---|---|---|---|---|
| **Section: 0002 BRIDGE 'A' - NBI NO. 32964** | | | | | |
| 0320 | 503(A)4230 | PRESTRESSED CONCRETE BEAMS (TYPE III) | | 254.000 LF | |
| | **Engineer's Estimate** | | **270.00** | | **68,580.00** |
| 1 | RRY SERVICES LLC | | 280.00 | | 71,120.00 |
| 2 | K & R BUILDERS, INC. | | 308.00 | | 78,232.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 309.00 | | 78,486.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 386.00 | | 98,044.00 |
| 0330 | 504(B)5300 | SAW-CUT GROOVING | | 213.100 SY | |
| | **Engineer's Estimate** | | **9.50** | | **2,024.45** |
| 1 | RRY SERVICES LLC | | 13.90 | | 2,962.09 |
| 2 | K & R BUILDERS, INC. | | 15.30 | | 3,260.43 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 14.70 | | 3,132.57 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 15.50 | | 3,303.05 |
| 0340 | 504(D)5410 | CONCRETE RAIL (TR3) | | 231.200 LF | |
| | **Engineer's Estimate** | | **82.00** | | **18,958.40** |
| 1 | RRY SERVICES LLC | | 105.00 | | 24,276.00 |
| 2 | K & R BUILDERS, INC. | | 91.00 | | 21,039.20 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 109.00 | | 25,200.80 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 84.00 | | 19,420.80 |
| 0350 | 506(A)7200 | STRUCTURAL STEEL | | 290.000 LB | |
| | **Engineer's Estimate** | | **4.50** | | **1,305.00** |
| 1 | RRY SERVICES LLC | | 2.50 | | 725.00 |
| 2 | K & R BUILDERS, INC. | | 3.80 | | 1,102.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 13.60 | | 3,944.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 4.50 | | 1,305.00 |
| 0360 | 507(A)8210 | WEATHERING STEEL FIXED BEARING ASSEMBLY | | 3.000 EA | |
| | **Engineer's Estimate** | | **1,200.00** | | **3,600.00** |
| 1 | RRY SERVICES LLC | | 1,650.00 | | 4,950.00 |
| 2 | K & R BUILDERS, INC. | | 1,450.00 | | 4,350.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 2,130.00 | | 6,390.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 1,295.70 | | 3,887.10 |
| 0370 | 507(B)8310 | WEATHERING STL EXP. BEARING ASSEMBLY | | 3.000 EA | |
| | **Engineer's Estimate** | | **1,200.00** | | **3,600.00** |
| 1 | RRY SERVICES LLC | | 1,650.00 | | 4,950.00 |
| 2 | K & R BUILDERS, INC. | | 1,450.00 | | 4,350.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 2,130.00 | | 6,390.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 1,295.70 | | 3,887.10 |
| 0380 | 509(A)0210 | CLASS AA CONCRETE | | 67.200 CY | |
| | **Engineer's Estimate** | | **675.00** | | **45,360.00** |
| 1 | RRY SERVICES LLC | | 765.00 | | 51,408.00 |
| 2 | K & R BUILDERS, INC. | | 722.50 | | 48,552.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 658.50 | | 44,251.20 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 850.00 | | 57,120.00 |
| 0390 | 509(B)0320 | CLASS A CONCRETE | | 66.200 CY | |
| | **Engineer's Estimate** | | **675.00** | | **44,685.00** |
| 1 | RRY SERVICES LLC | | 765.00 | | 50,643.00 |
| 2 | K & R BUILDERS, INC. | | 735.00 | | 48,657.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 789.50 | | 52,264.90 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 850.00 | | 56,270.00 |

**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127

| Line # | Item Number | Item Description | Quantity/Unit | |
|---|---|---|---|---|
| | Bidder | | Unit Price | Ext Amount |
| **Section: 0002** | **BRIDGE 'A' - NBI NO. 32964** | | | |
| 0400 | 511(A)2210 | REINFORCING STEEL | 24,960.000 LB | |
| | **Engineer's Estimate** | | **1.40** | **34,944.00** |
| 1 | RRY SERVICES LLC | | 1.50 | 37,440.00 |
| 2 | K & R BUILDERS, INC. | | 1.39 | 34,694.40 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 1.70 | 42,432.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 1.42 | 35,443.20 |
| 0410 | 514(A)5210 | PILES, FURNISHED (HP 10X42) | 128.000 LF | |
| | **Engineer's Estimate** | | **52.00** | **6,656.00** |
| 1 | RRY SERVICES LLC | | 65.00 | 8,320.00 |
| 2 | K & R BUILDERS, INC. | | 51.50 | 6,592.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 61.40 | 7,859.20 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 47.45 | 6,073.60 |
| 0420 | 514(A)5220 | PILES, FURNISHED (HP 12X53) | 290.000 LF | |
| | **Engineer's Estimate** | | **60.00** | **17,400.00** |
| 1 | RRY SERVICES LLC | | 80.00 | 23,200.00 |
| 2 | K & R BUILDERS, INC. | | 62.30 | 18,067.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 82.90 | 24,041.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 60.79 | 17,629.10 |
| 0430 | 514(B)5310 | PILES, DRIVEN (HP 10X42) | 128.000 LF | |
| | **Engineer's Estimate** | | **16.00** | **2,048.00** |
| 1 | RRY SERVICES LLC | | 10.00 | 1,280.00 |
| 2 | K & R BUILDERS, INC. | | 21.50 | 2,752.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 27.50 | 3,520.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 20.00 | 2,560.00 |
| 0440 | 514(B)5320 | PILES, DRIVEN (HP 12X53) | 290.000 LF | |
| | **Engineer's Estimate** | | **16.00** | **4,640.00** |
| 1 | RRY SERVICES LLC | | 10.00 | 2,900.00 |
| 2 | K & R BUILDERS, INC. | | 26.70 | 7,743.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 24.30 | 7,047.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 20.00 | 5,800.00 |
| 0450 | 514(L)6300 | PILE SPLICE, H-PILE (NON-BIDDABLE) | 1.000 EA | |
| | **Engineer's Estimate** | | **400.00** | **400.00** |
| 1 | RRY SERVICES LLC | | 400.00 | 400.00 |
| 2 | K & R BUILDERS, INC. | | 400.00 | 400.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 400.00 | 400.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 400.00 | 400.00 |
| 0460 | 601(B)1230 | TYPE I-A PLAIN RIPRAP | 850.000 TON | |
| | **Engineer's Estimate** | | **61.00** | **51,850.00** |
| 1 | RRY SERVICES LLC | | 65.00 | 55,250.00 |
| 2 | K & R BUILDERS, INC. | | 71.85 | 61,072.50 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 65.50 | 55,675.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 63.50 | 53,975.00 |
| 0470 | 601(C)1310 | TYPE I-A FILTER BLANKET | 284.000 TON | |
| | **Engineer's Estimate** | | **51.00** | **14,484.00** |
| 1 | RRY SERVICES LLC | | 52.00 | 14,768.00 |
| 2 | K & R BUILDERS, INC. | | 58.62 | 16,648.08 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 52.70 | 14,966.80 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 61.00 | 17,324.00 |

**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127

| Line # | Item Number | Item Description | Quantity/Unit |
|---|---|---|---|
| | Bidder | Unit Price | Ext Amount |
| **Section: 0002** | **BRIDGE 'A' - NBI NO. 32964** | | |
| 0480 | 613(H)6205 | 6" PERFORATED PIPE UNDERDRAIN ROUND | 52.000 LF |
| | **Engineer's Estimate** | **32.00** | **1,664.00** |
| 1 | RRY SERVICES LLC | 45.00 | 2,340.00 |
| 2 | K & R BUILDERS, INC. | 42.00 | 2,184.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | 57.30 | 2,979.60 |
| 4 | BRIDGECO CONTRACTORS, INC. | 45.00 | 2,340.00 |
| 0490 | 613(I)6310 | 6" NON-PERF.PIPE UNDERDRAIN RND. | 60.000 LF |
| | **Engineer's Estimate** | **32.00** | **1,920.00** |
| 1 | RRY SERVICES LLC | 45.00 | 2,700.00 |
| 2 | K & R BUILDERS, INC. | 34.00 | 2,040.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | 23.90 | 1,434.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | 45.00 | 2,700.00 |
| 0500 | 619(D)6700 | REMOVAL OF EXISTING BRIDGE STRUCTURE | 1.000 LSUM |
| | **Engineer's Estimate** | **12,000.00** | **12,000.00** |
| 1 | RRY SERVICES LLC | 20,000.00 | 20,000.00 |
| 2 | K & R BUILDERS, INC. | 29,000.00 | 29,000.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | 13,620.00 | 13,620.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | 19,000.00 | 19,000.00 |

| Line # | Item Number | Item Description | Quantity/Unit |
|---|---|---|---|
| | Bidder | Unit Price | Ext Amount |
| **Section: 0003** | **TRAFFIC** | | |
| 0510 | 856(A)8200 | TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE) | 2,200.000 LF |
| | **Engineer's Estimate** | **2.00** | **4,400.00** |
| 1 | RRY SERVICES LLC | 4.00 | 8,800.00 |
| 2 | K & R BUILDERS, INC. | 4.12 | 9,064.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | 2.10 | 4,620.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | 4.15 | 9,130.00 |
| 0520 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 9,360.000 SD |
| | **Engineer's Estimate** | **0.32** | **2,995.20** |
| 1 | RRY SERVICES LLC | 0.80 | 7,488.00 |
| 2 | K & R BUILDERS, INC. | 0.83 | 7,768.80 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | 0.69 | 6,458.40 |
| 4 | BRIDGECO CONTRACTORS, INC. | 0.83 | 7,768.80 |
| 0530 | 880(B)6310 | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF | 2,400.000 SD |
| | **Engineer's Estimate** | **0.32** | **768.00** |
| 1 | RRY SERVICES LLC | 0.10 | 240.00 |
| 2 | K & R BUILDERS, INC. | 0.11 | 264.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | 1.60 | 3,840.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | 0.12 | 288.00 |
| 0540 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 240.000 SD |
| | **Engineer's Estimate** | **0.32** | **76.80** |
| 1 | RRY SERVICES LLC | 1.15 | 276.00 |
| 2 | K & R BUILDERS, INC. | 1.10 | 264.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | 3.15 | 756.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | 1.10 | 264.00 |

**Letting Date:** April 14, 2022, 10:30 A.M.
**Call Order:** 150 **Contract ID:** 220127

| Line # | Item Number | Item Description | Quantity/Unit | |
|---|---|---|---|---|
| | Bidder | | Unit Price | Ext Amount |
| **Section: 0003 TRAFFIC** | | | | |
| 0550 | 880(C)6410 | CONSTRUCTION BARRICADES(TYPE III) | 1,920.000 SD | |
| | **Engineer's Estimate** | | **0.35** | **672.00** |
| 1 | RRY SERVICES LLC | | 0.25 | 480.00 |
| 2 | K & R BUILDERS, INC. | | 0.28 | 537.60 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 1.30 | 2,496.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 0.28 | 537.60 |
| 0560 | 880(E)6600 | WARNING LIGHTS(TYPE A) | 4,800.000 SD | |
| | **Engineer's Estimate** | | **0.02** | **96.00** |
| 1 | RRY SERVICES LLC | | 0.10 | 480.00 |
| 2 | K & R BUILDERS, INC. | | 0.11 | 528.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 0.53 | 2,544.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 0.12 | 576.00 |

| Line # | Item Number | Item Description | Quantity/Unit | |
|---|---|---|---|---|
| | Bidder | | Unit Price | Ext Amount |
| **Section: 0004 STAKING** | | | | |
| 0570 | 642(B)3300 | CONSTRUCTION STAKING LEVEL II | 1.000 LSUM | |
| | **Engineer's Estimate** | | **6,500.00** | **6,500.00** |
| 1 | RRY SERVICES LLC | | 9,500.00 | 9,500.00 |
| 2 | K & R BUILDERS, INC. | | 7,500.00 | 7,500.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 11,540.00 | 11,540.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 9,900.00 | 9,900.00 |

| Line # | Item Number | Item Description | Quantity/Unit | |
|---|---|---|---|---|
| | Bidder | | Unit Price | Ext Amount |
| **Section: 0005 CONSTRUCTION** | | | | |
| 0580 | 220 1100 | SWPPP DOCUMENTATION AND MANAGEMENT | 1.000 LSUM | |
| | **Engineer's Estimate** | | **2,500.00** | **2,500.00** |
| 1 | RRY SERVICES LLC | | 1,350.00 | 1,350.00 |
| 2 | K & R BUILDERS, INC. | | 3,000.00 | 3,000.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 2,722.59 | 2,722.59 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 5,500.00 | 5,500.00 |
| 0590 | 641 2100 | MOBILIZATION | 1.000 LSUM | |
| | **Engineer's Estimate** | | **70,000.00** | **70,000.00** |
| 1 | RRY SERVICES LLC | | 77,000.00 | 77,000.00 |
| 2 | K & R BUILDERS, INC. | | 70,000.00 | 70,000.00 |
| 3 | HASKELL LEMON CONSTRUCTION CO. | | 45,455.00 | 45,455.00 |
| 4 | BRIDGECO CONTRACTORS, INC. | | 66,800.00 | 66,800.00 |