Letting Date: August 18, 2022, 10:30 A.M.
Call Order: 405 **Contract ID:** 220189
J/P No.: 30436(04) **Project No.:** CIRB-202D(065)RB **Contract Time:**
County: ALFALFA
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-29): OVER WEST CLAY CREEK,
1.4 MILES EAST OF THE SH-8 JUNCTION NEAR CARMEN.
PROJECT LENGTH = 0.312 MILE

	VENDORNAME	PROPOSALITEMTO		
1	SEWELL BROS., INC.	774,393.34	94.44	100.00
2	K & R BUILDERS, INC.	791,184.18	96.49	102.17
	Engineer's Estimate	819,976.60		
3	RRY SERVICES LLC	918,168.66	111.97	118.57
4	BRIDGECO CONTRACTORS, INC.	919,612.44	112.15	118.75
5	Wyatt Contracting	976,706.02	119.11	126.13

Letting Date: August 18, 2022, 10:30 A.M.
Call Order: 405 **Contract ID:** 220189

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001	**ROADWAY**			
0010	201(A)1200	CLEARING AND GRUBBING	1.000 LSUM	
	Engineer's Estimate		**7,500.00**	**7,500.00**
1	SEWELL BROS., INC.		5,000.00	5,000.00
2	K & R BUILDERS, INC.		10,500.00	10,500.00
3	RRY SERVICES LLC		10,500.00	10,500.00
4	BRIDGECO CONTRACTORS, INC.		26,000.00	26,000.00
5	Wyatt Contracting		16,000.00	16,000.00
0020	202(A)2200	UNCLASSIFIED EXCAVATION	3,306.000 CY	
	Engineer's Estimate		**11.00**	**36,366.00**
1	SEWELL BROS., INC.		10.00	33,060.00
2	K & R BUILDERS, INC.		8.50	28,101.00
3	RRY SERVICES LLC		13.00	42,978.00
4	BRIDGECO CONTRACTORS, INC.		11.00	36,366.00
5	Wyatt Contracting		10.00	33,060.00
0030	202(D)2500	UNCLASSIFIED BORROW	1,990.000 CY	
	Engineer's Estimate		**12.00**	**23,880.00**
1	SEWELL BROS., INC.		12.00	23,880.00
2	K & R BUILDERS, INC.		8.00	15,920.00
3	RRY SERVICES LLC		16.00	31,840.00
4	BRIDGECO CONTRACTORS, INC.		15.00	29,850.00
5	Wyatt Contracting		25.75	51,242.50
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000 LSUM	
	Engineer's Estimate		**7,000.00**	**7,000.00**
1	SEWELL BROS., INC.		10,000.00	10,000.00
2	K & R BUILDERS, INC.		7,500.00	7,500.00
3	RRY SERVICES LLC		9,500.00	9,500.00
4	BRIDGECO CONTRACTORS, INC.		9,000.00	9,000.00
5	Wyatt Contracting		10,000.00	10,000.00
0050	221(B)2300	TEMPORARY SILT FENCE	1,300.000 LF	
	Engineer's Estimate		**3.25**	**4,225.00**
1	SEWELL BROS., INC.		2.90	3,770.00
2	K & R BUILDERS, INC.		2.75	3,575.00
3	RRY SERVICES LLC		3.00	3,900.00
4	BRIDGECO CONTRACTORS, INC.		3.00	3,900.00
5	Wyatt Contracting		2.75	3,575.00
0060	221(E)2600	TEMPORARY SILT DIKE	504.000 LF	
	Engineer's Estimate		**12.25**	**6,174.00**
1	SEWELL BROS., INC.		13.50	6,804.00
2	K & R BUILDERS, INC.		6.00	3,024.00
3	RRY SERVICES LLC		13.50	6,804.00
4	BRIDGECO CONTRACTORS, INC.		13.75	6,930.00
5	Wyatt Contracting		12.75	6,426.00
0070	230(A)7200	SOLID SLAB SODDING	10,326.000 SY	
	Engineer's Estimate		**4.00**	**41,304.00**
1	SEWELL BROS., INC.		3.70	38,206.20
2	K & R BUILDERS, INC.		3.35	34,592.10
3	RRY SERVICES LLC		3.30	34,075.80
4	BRIDGECO CONTRACTORS, INC.		5.45	56,276.70
5	Wyatt Contracting		3.05	31,494.30

Letting Date: August 18, 2022, 10:30 A.M.
Call Order: 405 **Contract ID:** 220189

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0080	233(A)0200	VEGETATIVE MULCHING	2.130 AC	
	Engineer's Estimate		**1,540.00**	**3,280.20**
1	SEWELL BROS., INC.		1,300.00	2,769.00
2	K & R BUILDERS, INC.		250.00	532.50
3	RRY SERVICES LLC		1,250.00	2,662.50
4	BRIDGECO CONTRACTORS, INC.		1,450.00	3,088.50
5	Wyatt Contracting		1,250.00	2,662.50
0090	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,105.000 TON	
	Engineer's Estimate		**42.00**	**46,410.00**
1	SEWELL BROS., INC.		55.50	61,327.50
2	K & R BUILDERS, INC.		56.00	61,880.00
3	RRY SERVICES LLC		70.00	77,350.00
4	BRIDGECO CONTRACTORS, INC.		63.40	70,057.00
5	Wyatt Contracting		42.00	46,410.00
0100	509(D)0500	CLASS C CONCRETE	10.000 CY	
	Engineer's Estimate		**350.00**	**3,500.00**
1	SEWELL BROS., INC.		400.00	4,000.00
2	K & R BUILDERS, INC.		300.00	3,000.00
3	RRY SERVICES LLC		350.00	3,500.00
4	BRIDGECO CONTRACTORS, INC.		350.00	3,500.00
5	Wyatt Contracting		720.00	7,200.00
0110	601(B)1220	TYPE I-A PLAIN RIPRAP	860.000 TON	
	Engineer's Estimate		**58.00**	**49,880.00**
1	SEWELL BROS., INC.		72.00	61,920.00
2	K & R BUILDERS, INC.		74.00	63,640.00
3	RRY SERVICES LLC		90.00	77,400.00
4	BRIDGECO CONTRACTORS, INC.		78.00	67,080.00
5	Wyatt Contracting		170.00	146,200.00
0120	601(C)1300	TYPE I-A FILTER BLANKET	288.000 TON	
	Engineer's Estimate		**48.00**	**13,824.00**
1	SEWELL BROS., INC.		58.00	16,704.00
2	K & R BUILDERS, INC.		60.00	17,280.00
3	RRY SERVICES LLC		80.00	23,040.00
4	BRIDGECO CONTRACTORS, INC.		75.00	21,600.00
5	Wyatt Contracting		120.00	34,560.00
0130	613(B)5508	18" CORR. GALV. STEEL PIPE	130.000 LF	
	Engineer's Estimate		**38.00**	**4,940.00**
1	SEWELL BROS., INC.		53.00	6,890.00
2	K & R BUILDERS, INC.		45.00	5,850.00
3	RRY SERVICES LLC		90.00	11,700.00
4	BRIDGECO CONTRACTORS, INC.		58.10	7,553.00
5	Wyatt Contracting		60.00	7,800.00
0140	613(M)6900	TYPE A3 CULVERT END TREATMENT	4.000 EA	
	Engineer's Estimate		**1,050.00**	**4,200.00**
1	SEWELL BROS., INC.		1,200.00	4,800.00
2	K & R BUILDERS, INC.		1,400.00	5,600.00
3	RRY SERVICES LLC		900.00	3,600.00
4	BRIDGECO CONTRACTORS, INC.		3,500.00	14,000.00
5	Wyatt Contracting		1,960.00	7,840.00

Letting Date: August 18, 2022, 10:30 A.M.
Call Order: 405 **Contract ID:** 220189

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0001 ROADWAY				
0150	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000 LSUM	
	Engineer's Estimate		**4,000.00**	**4,000.00**
1	SEWELL BROS., INC.		3,300.00	3,300.00
2	K & R BUILDERS, INC.		1,000.00	1,000.00
3	RRY SERVICES LLC		3,000.00	3,000.00
4	BRIDGECO CONTRACTORS, INC.		4,000.00	4,000.00
5	Wyatt Contracting		8,500.00	8,500.00
0160	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	802.000 LF	
	Engineer's Estimate		**9.25**	**7,418.50**
1	SEWELL BROS., INC.		11.00	8,822.00
2	K & R BUILDERS, INC.		20.00	16,040.00
3	RRY SERVICES LLC		14.50	11,629.00
4	BRIDGECO CONTRACTORS, INC.		36.00	28,872.00
5	Wyatt Contracting		13.00	10,426.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE				
0170	202(A)2210	UNCLASSIFIED EXCAVATION	1,778.000 CY	
	Engineer's Estimate		**8.00**	**14,224.00**
1	SEWELL BROS., INC.		10.00	17,780.00
2	K & R BUILDERS, INC.		7.75	13,779.50
3	RRY SERVICES LLC		13.00	23,114.00
4	BRIDGECO CONTRACTORS, INC.		15.00	26,670.00
5	Wyatt Contracting		12.00	21,336.00
0180	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	246.000 CY	
	Engineer's Estimate		**18.00**	**4,428.00**
1	SEWELL BROS., INC.		15.00	3,690.00
2	K & R BUILDERS, INC.		14.75	3,628.50
3	RRY SERVICES LLC		18.00	4,428.00
4	BRIDGECO CONTRACTORS, INC.		18.00	4,428.00
5	Wyatt Contracting		30.00	7,380.00
0190	509(A)0210	CLASS AA CONCRETE	527.560 CY	
	Engineer's Estimate		**600.00**	**316,536.00**
1	SEWELL BROS., INC.		500.00	263,780.00
2	K & R BUILDERS, INC.		496.00	261,669.76
3	RRY SERVICES LLC		585.00	308,622.60
4	BRIDGECO CONTRACTORS, INC.		550.00	290,158.00
5	Wyatt Contracting		530.00	279,606.80
0200	511(A)2210	REINFORCING STEEL	88,501.600 LB	
	Engineer's Estimate		**1.50**	**132,752.40**
1	SEWELL BROS., INC.		1.40	123,902.24
2	K & R BUILDERS, INC.		1.39	123,017.22
3	RRY SERVICES LLC		1.35	119,477.16
4	BRIDGECO CONTRACTORS, INC.		1.40	123,902.24
5	Wyatt Contracting		1.45	128,327.32

Letting Date: August 18, 2022, 10:30 A.M.
Call Order: 405 **Contract ID:** 220189

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0002 BRIDGE				
0210	601(B)1230	TYPE I-A PLAIN RIPRAP	139.000 TON	
	Engineer's Estimate		**58.00**	**8,062.00**
1	SEWELL BROS., INC.		72.00	10,008.00
2	K & R BUILDERS, INC.		75.00	10,425.00
3	RRY SERVICES LLC		90.00	12,510.00
4	BRIDGECO CONTRACTORS, INC.		78.00	10,842.00
5	Wyatt Contracting		170.00	23,630.00
0220	601(C)1310	TYPE I-A FILTER BLANKET	47.000 TON	
	Engineer's Estimate		**41.50**	**1,950.50**
1	SEWELL BROS., INC.		58.00	2,726.00
2	K & R BUILDERS, INC.		60.00	2,820.00
3	RRY SERVICES LLC		80.00	3,760.00
4	BRIDGECO CONTRACTORS, INC.		75.00	3,525.00
5	Wyatt Contracting		120.00	5,640.00
0230	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000 LSUM	
	Engineer's Estimate		**7,500.00**	**7,500.00**
1	SEWELL BROS., INC.		5,000.00	5,000.00
2	K & R BUILDERS, INC.		20,000.00	20,000.00
3	RRY SERVICES LLC		11,500.00	11,500.00
4	BRIDGECO CONTRACTORS, INC.		15,000.00	15,000.00
5	Wyatt Contracting		7,500.00	7,500.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003 TRAFFIC				
0240	853 5110	DELINEATORS(TYPE 1, CODE 3)	4.000 EA	
	Engineer's Estimate		**27.00**	**108.00**
1	SEWELL BROS., INC.		35.00	140.00
2	K & R BUILDERS, INC.		30.00	120.00
3	RRY SERVICES LLC		32.00	128.00
4	BRIDGECO CONTRACTORS, INC.		33.00	132.00
5	Wyatt Contracting		30.00	120.00
0250	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,600.000 SD	
	Engineer's Estimate		**0.10**	**360.00**
1	SEWELL BROS., INC.		0.04	144.00
2	K & R BUILDERS, INC.		0.02	72.00
3	RRY SERVICES LLC		0.02	72.00
4	BRIDGECO CONTRACTORS, INC.		0.05	180.00
5	Wyatt Contracting		0.02	72.00
0260	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	360.000 SD	
	Engineer's Estimate		**2.00**	**720.00**
1	SEWELL BROS., INC.		15.00	5,400.00
2	K & R BUILDERS, INC.		8.00	2,880.00
3	RRY SERVICES LLC		6.50	2,340.00
4	BRIDGECO CONTRACTORS, INC.		6.50	2,340.00
5	Wyatt Contracting		6.00	2,160.00

Letting Date: August 18, 2022, 10:30 A.M.
Call Order: 405 **Contract ID:** 220189

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0003 TRAFFIC				
0270	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,400.000 SD	
	Engineer's Estimate		**0.10**	**240.00**
1	SEWELL BROS., INC.		0.06	144.00
2	K & R BUILDERS, INC.		0.05	120.00
3	RRY SERVICES LLC		0.05	120.00
4	BRIDGECO CONTRACTORS, INC.		0.07	168.00
5	Wyatt Contracting		0.05	120.00
0280	880(E)6600	WARNING LIGHTS(TYPE A)	5,880.000 SD	
	Engineer's Estimate		**0.05**	**294.00**
1	SEWELL BROS., INC.		0.03	176.40
2	K & R BUILDERS, INC.		0.02	117.60
3	RRY SERVICES LLC		0.02	117.60
4	BRIDGECO CONTRACTORS, INC.		0.05	294.00
5	Wyatt Contracting		0.02	117.60

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0004 STAKING				
0290	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000 LSUM	
	Engineer's Estimate		**6,400.00**	**6,400.00**
1	SEWELL BROS., INC.		5,750.00	5,750.00
2	K & R BUILDERS, INC.		6,500.00	6,500.00
3	RRY SERVICES LLC		6,500.00	6,500.00
4	BRIDGECO CONTRACTORS, INC.		7,400.00	7,400.00
5	Wyatt Contracting		4,800.00	4,800.00

Line #	Item Number	Item Description	Quantity/Unit	
	Bidder		Unit Price	Ext Amount
Section: 0005 CONSTRUCTION				
0300	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000 LSUM	
	Engineer's Estimate		**2,500.00**	**2,500.00**
1	SEWELL BROS., INC.		2,000.00	2,000.00
2	K & R BUILDERS, INC.		5,000.00	5,000.00
3	RRY SERVICES LLC		2,000.00	2,000.00
4	BRIDGECO CONTRACTORS, INC.		3,500.00	3,500.00
5	Wyatt Contracting		2,500.00	2,500.00
0310	641 2100	MOBILIZATION	1.000 LSUM	
	Engineer's Estimate		**60,000.00**	**60,000.00**
1	SEWELL BROS., INC.		42,500.00	42,500.00
2	K & R BUILDERS, INC.		63,000.00	63,000.00
3	RRY SERVICES LLC		70,000.00	70,000.00
4	BRIDGECO CONTRACTORS, INC.		43,000.00	43,000.00
5	Wyatt Contracting		70,000.00	70,000.00