Letting Date: June 16, 2022, 10:30 A.M.
Call Order: 810 **Contract ID:** 220202
J/P No.: 34356(04) **Project No.:** STP-252C(068)3P **Contract Time:**
County: NOBLE
Description: RESURFACE (ASPHALT)
SH-15: FROM THE I-35 RAMPS,
EXTEND EAST NEAR BILLINGS.
PROJECT LENGTH = 3.190 MILES

	VENDORNAME	PROPOSALITEMTO		
	Engineer's Estimate	1,201,886.00		
1	Evans & Associates Construction Co., Inc.	1,387,971.86	115.48	100.00
2	HASKELL LEMON CONSTRUCTION CO.	1,899,650.00	158.06	136.87

Letting Date: June 16, 2022, 10:30 A.M.
Call Order: 810 **Contract ID:** 220202

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0010	202(D)2520	UNCLASSIFIED BORROW (TOPSOIL)	1,000.000	CY	
	Engineer's Estimate		**23.00**		**23,000.00**
1	Evans & Associates Construction Co., Inc.		12.78		12,780.00
2	HASKELL LEMON CONSTRUCTION CO.		80.70		80,700.00
0020	202(H)2900	EARTHWORK	1.000	LSUM	
	Engineer's Estimate		**5,000.00**		**5,000.00**
1	Evans & Associates Construction Co., Inc.		5,143.86		5,143.86
2	HASKELL LEMON CONSTRUCTION CO.		21,455.00		21,455.00
0030	303(A)1200	AGGREGATE BASE TYPE A	100.000	CY	
	Engineer's Estimate		**80.00**		**8,000.00**
1	Evans & Associates Construction Co., Inc.		191.00		19,100.00
2	HASKELL LEMON CONSTRUCTION CO.		520.00		52,000.00
0040	407(C)7500	NT TACK MATERIAL	4,500.000	GAL	
	Engineer's Estimate		**3.30**		**14,850.00**
1	Evans & Associates Construction Co., Inc.		3.86		17,370.00
2	HASKELL LEMON CONSTRUCTION CO.		5.00		22,500.00
0050	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	4,400.000	TON	
	Engineer's Estimate		**100.00**		**440,000.00**
1	Evans & Associates Construction Co., Inc.		123.32		542,608.00
2	HASKELL LEMON CONSTRUCTION CO.		165.00		726,000.00
0060	411(E)1620	SUPERPAVE, TYPE S6(PG 64-22 OK)	1,800.000	TON	
	Engineer's Estimate		**100.00**		**180,000.00**
1	Evans & Associates Construction Co., Inc.		111.83		201,294.00
2	HASKELL LEMON CONSTRUCTION CO.		175.00		315,000.00
0070	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,400.000	TON	
	Engineer's Estimate		**120.00**		**168,000.00**
1	Evans & Associates Construction Co., Inc.		147.33		206,262.00
2	HASKELL LEMON CONSTRUCTION CO.		150.50		210,700.00
0080	412 3100	COLD MILLING PAVEMENT	2,800.000	SY	
	Engineer's Estimate		**11.00**		**30,800.00**
1	Evans & Associates Construction Co., Inc.		21.15		59,220.00
2	HASKELL LEMON CONSTRUCTION CO.		14.20		39,760.00
0090	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,500.000	SY	
	Engineer's Estimate		**25.00**		**37,500.00**
1	Evans & Associates Construction Co., Inc.		8.00		12,000.00
2	HASKELL LEMON CONSTRUCTION CO.		27.40		41,100.00
0100	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	1,200.000	SY	
	Engineer's Estimate		**35.00**		**42,000.00**
1	Evans & Associates Construction Co., Inc.		21.00		25,200.00
2	HASKELL LEMON CONSTRUCTION CO.		56.70		68,040.00
0110	619(C)6600	SAWING PAVEMENT	5,600.000	LF	
	Engineer's Estimate		**5.00**		**28,000.00**
1	Evans & Associates Construction Co., Inc.		8.00		44,800.00
2	HASKELL LEMON CONSTRUCTION CO.		2.35		13,160.00

Letting Date: June 16, 2022, 10:30 A.M.
Call Order: 810 **Contract ID:** 220202

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0001 ROADWAY					
0120	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF	
	Engineer's Estimate		**30.00**		**6,000.00**
1	Evans & Associates Construction Co., Inc.		45.00		9,000.00
2	HASKELL LEMON CONSTRUCTION CO.		53.10		10,620.00
0130	623(C)1400	BEAM GUARDRAIL THRIE-BEAM SINGLE	175.000	LF	
	Engineer's Estimate		**60.00**		**10,500.00**
1	Evans & Associates Construction Co., Inc.		75.00		13,125.00
2	HASKELL LEMON CONSTRUCTION CO.		88.50		15,487.50
0140	623(D)1500	BEAM GUARDRAIL THRIE-BEAM DOUBLE	100.000	LF	
	Engineer's Estimate		**100.00**		**10,000.00**
1	Evans & Associates Construction Co., Inc.		100.00		10,000.00
2	HASKELL LEMON CONSTRUCTION CO.		118.00		11,800.00
0150	623(E)1600	BEAM GUARDRAIL TRANSITION SECTION	8.000	EA	
	Engineer's Estimate		**1,100.00**		**8,800.00**
1	Evans & Associates Construction Co., Inc.		1,000.00		8,000.00
2	HASKELL LEMON CONSTRUCTION CO.		1,180.00		9,440.00
0160	623(G)1800	GUARDRAIL END TREATMENT (GET)	8.000	EA	
	Engineer's Estimate		**4,000.00**		**32,000.00**
1	Evans & Associates Construction Co., Inc.		3,400.00		27,200.00
2	HASKELL LEMON CONSTRUCTION CO.		4,011.00		32,088.00

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 TRAFFIC					
0170	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	42.000	EA	
	Engineer's Estimate		**28.00**		**1,176.00**
1	Evans & Associates Construction Co., Inc.		50.00		2,100.00
2	HASKELL LEMON CONSTRUCTION CO.		59.00		2,478.00
0180	856(A)8204	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	50,000.000	LF	
	Engineer's Estimate		**0.65**		**32,500.00**
1	Evans & Associates Construction Co., Inc.		1.10		55,000.00
2	HASKELL LEMON CONSTRUCTION CO.		0.83		41,500.00
0190	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	5,500.000	EA	
	Engineer's Estimate		**1.00**		**5,500.00**
1	Evans & Associates Construction Co., Inc.		0.55		3,025.00
2	HASKELL LEMON CONSTRUCTION CO.		0.77		4,235.00
0200	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,800.000	SD	
	Engineer's Estimate		**0.50**		**900.00**
1	Evans & Associates Construction Co., Inc.		1.10		1,980.00
2	HASKELL LEMON CONSTRUCTION CO.		2.35		4,230.00
0210	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,440.000	SD	
	Engineer's Estimate		**0.50**		**720.00**
1	Evans & Associates Construction Co., Inc.		2.20		3,168.00
2	HASKELL LEMON CONSTRUCTION CO.		3.55		5,112.00

Letting Date: June 16, 2022, 10:30 A.M.
Call Order: 810 **Contract ID:** 220202

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0002 TRAFFIC					
0220	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,320.000	SD	
	Engineer's Estimate		**1.00**		**4,320.00**
1	Evans & Associates Construction Co., Inc.		2.20		9,504.00
2	HASKELL LEMON CONSTRUCTION CO.		1.20		5,184.00
0230	880(C)6420	WING BARRICADES	480.000	SD	
	Engineer's Estimate		**5.00**		**2,400.00**
1	Evans & Associates Construction Co., Inc.		5.50		2,640.00
2	HASKELL LEMON CONSTRUCTION CO.		1.20		576.00
0240	880(E)6600	WARNING LIGHTS(TYPE A)	2,640.000	SD	
	Engineer's Estimate		**0.50**		**1,320.00**
1	Evans & Associates Construction Co., Inc.		0.55		1,452.00
2	HASKELL LEMON CONSTRUCTION CO.		0.29		765.60
0250	880(F)6700	DRUMS	6,000.000	SD	
	Engineer's Estimate		**1.00**		**6,000.00**
1	Evans & Associates Construction Co., Inc.		0.30		1,800.00
2	HASKELL LEMON CONSTRUCTION CO.		0.88		5,280.00
0260	880(G)6805	CHANNELIZER CONES	6,000.000	SD	
	Engineer's Estimate		**1.00**		**6,000.00**
1	Evans & Associates Construction Co., Inc.		0.30		1,800.00
2	HASKELL LEMON CONSTRUCTION CO.		0.88		5,280.00
0270	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	480.000	SD	
	Engineer's Estimate		**20.00**		**9,600.00**
1	Evans & Associates Construction Co., Inc.		30.00		14,400.00
2	HASKELL LEMON CONSTRUCTION CO.		29.50		14,160.00
0280	884(C)9405	REMOVE BRIDGE RAIL & POSTS(STEEL)	200.000	LF	
	Engineer's Estimate		**10.00**		**2,000.00**
1	Evans & Associates Construction Co., Inc.		10.00		2,000.00
2	HASKELL LEMON CONSTRUCTION CO.		110.00		22,000.00

Line #	Item Number	Item Description	Quantity/Unit		
	Bidder		Unit Price		Ext Amount
Section: 0003 CONSTRUCTION					
0290	641 2110	MOBILIZATION	1.000	LSUM	
	Engineer's Estimate		**85,000.00**		**85,000.00**
1	Evans & Associates Construction Co., Inc.		76,000.00		76,000.00
2	HASKELL LEMON CONSTRUCTION CO.		118,998.90		118,998.90