Proposal:240129 **Let Date:**June 18, 2026 **Call Order:**220
J/P Num:24868(09) **Proj. Num:**CIRB-224C(062)RB
Counties:GARFIELD
Description:GRADE, DRAIN, AND SURFACE
COUNTY ROAD (EW-40): FROM THE SH-15 JUNCTION, EXTEND EAST IN GARBER.
PROJECT LENGTH = 0.819 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	1,853.560	CY
0020	202(D)2500	UNCLASSIFIED BORROW	1,000.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	1,000.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	140.000	LF
0060	227 4100	(SP)TURF REINFORCEMENT MAT	310.000	SY
0070	230(A)7200	SOLID SLAB SODDING	19,332.240	SY
0080	233(A)0200	VEGETATIVE MULCHING	3.990	AC
0090	240(A)2230	REMOVING TREES 25" & MORE IN DIAMETER	1.000	EA
0100	303(A)1200	AGGREGATE BASE TYPE A	100.000	CY
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	200.000	TON
0120	407(A)7200	FOG SEAL	1,031.910	GAL
0130	407(B)7300	TACK COAT	1,381.940	GAL
0140	408 8100	PRIME COAT	1,002.280	GAL
0150	411(B)1340	SUPERPAVE, TYPE S3(PG 58-28 OK)	2,796.170	TON
0160	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,457.760	TON
0170	411(H)1902	SUPERPAVE, TYPE S3(PATCH)(PG58-28)	100.000	TON
0180	412 3100	COLD MILLING PAVEMENT	10,319.070	SY
0190	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	1,611.670	SY
0200	414(G)5800	P.C. CONCRETE FOR PAVEMENT	359.080	CY
0210	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	216.260	CY
0220	501(G)1810	CLSM BACKFILL	10.000	CY
0230	509(A)0200	CLASS AA CONCRETE	72.390	CY
0240	509(D)0500	CLASS C CONCRETE	50.000	CY
0250	511(A)2200	REINFORCING STEEL	11,544.690	LB
0260	609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	198.000	LF
0270	610(A)5220	6" CONCRETE SIDEWALK	262.000	SY
0280	610(B)5310	6" CONCRETE DRIVEWAY	658.330	SY
0290	610(I)6000	TACTILE WARNING DEVICE-NEW	100.000	SF
0300	611(G)7700	SPECIAL INLET DRAIN	1.000	EA
0310	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	102.000	LF
0320	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	80.000	LF
0330	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	637.000	LF
0340	613(B)5680	PVC DRAINAGE STRUCTURE	14.000	EA
0350	613(EE)5961	12" CORRUGATED POLYPROPYLENE PIPE	49.000	LF
0360	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	457.000	LF
0370	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	1,275.000	LF
0380	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	77.000	LF
0390	613(EE)5977	30" CORRUGATED POLYPROPYLENE PIPE	108.000	LF
0400	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	250.000	LF
0410	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	100.000	LF
0420	613(L)6608	21" X 15" PREFAB. CULVERT END SEC., ARCH	24.000	EA
0430	613(L)6612	22" X 13" PREFAB. CULVERT END SEC., ARCH	4.000	EA
0440	613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	4.000	EA
0450	613(L)6700	12" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0460	613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0470	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	30.000	EA

Proposal:240129 **Let Date:**June 18, 2026 **Call Order:**220
J/P Num:24868(09) **Proj. Num:**CIRB-224C(062)RB
Counties:GARFIELD
Description:GRADE, DRAIN, AND SURFACE
COUNTY ROAD (EW-40): FROM THE SH-15 JUNCTION, EXTEND EAST IN GARBER.
PROJECT LENGTH = 0.819 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0480	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0490	613(M)6928	TYPE CC3 CULVERT END TREATMENT	2.000	EA
0500	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0510	613(U)7950	PIPE UNDERDRAIN COVER MAT'L.	150.000	CY
0520	613(V)8000	TRENCH EXCAVATION	150.000	CY
0530	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0540	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,645.560	SY
0550	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	618.670	SY
0560	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	221.330	SY
0570	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	1,319.780	SY
0580	619(B)6404	REMOVAL OF SIDEWALK	200.000	SY
0590	619(B)6508	REMOVE AND RESET CATTLE GUARD	1.000	EA
0600	619(C)6600	SAWING PAVEMENT	531.000	LF
0002	TRAFFIC			
0610	836 7110	RECTANGULAR RAPID FLASHING BEACON	4.000	EA
0620	850(A)1200	SHEET ALUMINUM SIGNS	101.700	SF
0630	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	8,168.000	LF
0640	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	193.000	LF
0650	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	45.000	LF
0660	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	1.000	EA
0670	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	4.000	EA
0680	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,780.000	SD
0690	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	960.000	SD
0700	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	240.000	SD
0710	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,440.000	SD
0720	880(E)6600	WARNING LIGHTS(TYPE A)	10,320.000	SD
0730	880(I)7000	FLAGGER	120.000	SD
0740	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	60.000	SD

Proposal:240129 **Let Date:**June 18, 2026 **Call Order:**220
J/P Num:24868(09) **Proj. Num:**CIRB-224C(062)RB
Counties:GARFIELD
Description:GRADE, DRAIN, AND SURFACE
COUNTY ROAD (EW-40): FROM THE SH-15 JUNCTION, EXTEND EAST IN GARBER.
PROJECT LENGTH = 0.819 MILES

Line #		Item Description	Quantity	Unit
0003	UTILITIES			
0750	611(A)7252	PRECAST CONC RND 4' DIA MANHOLE	2.000	EA
0760	611(B)7242	ADD'L DEPTH PRECAST RND 4' MANHOLE	6.000	VF
0770	612(A)3200	MANHOLES ADJUST TO GRADE	6.000	EA
0780	612(E)3600	VALVE BOXES ADJUST TO GRADE	5.000	EA
0790	616(B)2336	6" POLYVINYL CHLORIDE (PVC) PIPE	228.000	LF
0800	616(D)2646	6" GATE VALVE	2.000	EA
0810	616(D)2904	6" INSERTION VALVE	3.000	EA
0820	616(G)3111	FIRE HYDRANT AND ASSEMBLY	2.000	EA
0830	616(O)3975	6" 11 1/4 DEGREE FITTING	2.000	EA
0840	616(O)3980	6" 22 1/2 DEGREE FITTING	2.000	EA
0850	616(O)3985	6" 45 DEGREE FITTING	8.000	EA
0860	616(T)4535	6" X 6" X 6" TEE	2.000	EA
0870	616(V)4800	HYDROSTATIC PRESSURE TESTING & DISINFECT	1.000	LSUM
0880	619(B)6372	REMOVAL OF MANHOLES	2.000	EA
0890	619(B)6448	REMOVAL OF FIRE HYDRANT	2.000	EA
0900	619(B)6496	REMOVAL OF GATE VALVE AND BOX	2.000	EA
0910	619(B)6500	REMOVAL OF WATER LINE	52.000	LF
0920	619(B)6536	CUT & PLUG 6" WATER LINE	2.000	EA
0004	STAKING			
0930	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0940	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0950	641 2110	MOBILIZATION	1.000	LSUM