Proposal: 240160 **Let Date:** January 16, 2025 **Call Order:** 195
J/P Num: 35446(04) **Proj. Num:** TAP-273D(099)IG
Counties: WAGONER
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALK)
CITY STREET (E. PECAN STREET): FROM SH-72, EXTEND EAST IN COWETA.
PROJECT LENGTH = 0.830 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	137.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	195.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	3,367.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	33.000	LF
0060	221(G)2800	TEMPORARY FIBER LOG	112.000	LF
0070	230(A)7200	SOLID SLAB SODDING	2,246.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	0.200	AC
0090	303(A)1200	AGGREGATE BASE TYPE A	187.000	CY
0100	407(B)7300	TACK COAT	43.000	GAL
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	95.000	TON
0120	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	64.000	TON
0130	509(D)0500	CLASS C CONCRETE	20.000	CY
0140	609(C)4400	CONCRETE HEADER CURB (6"X 16")	155.000	LF
0150	610(A)5200	4" CONCRETE SIDEWALK	2,433.000	SY
0160	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	189.000	SY
0170	610(I)6000	TACTILE WARNING DEVICE-NEW	160.000	SF
0180	611(G)7700	SPECIAL INLET DRAIN	8.000	EA
0190	613(A)5216	24" R.C.PIPE CLASS III	20.000	LF
0200	613(A)5236	54" R.C.PIPE CLASS III	18.000	LF
0210	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0220	613(L)6740	54" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0230	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0240	619(B)6356	REMOVAL OF CURB AND GUTTER	7.000	LF
0250	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	71.000	SY
0260	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	518.000	SY
0270	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	124.000	SY
0280	619(B)6404	REMOVAL OF SIDEWALK	486.000	SY
0290	619(C)6600	SAWING PAVEMENT	993.000	LF
0300	622(A)0200	PIPE RAILING	10.000	LF
0310	625(B)4300	REMOVE AND RECONSTRUCT FENCE	8.000	LF
0002	TRAFFIC CONTROL			
0320	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	10.000	DAY
0330	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,140.000	SD
0340	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,623.000	SD
0350	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,450.000	SD
0370	880(E)6607	WARNING LIGHTS(TYPE B)	6,210.000	SD
0380	880(G)6805	CHANNELIZER CONES	30,533.000	SD
0390	880(I)7000	FLAGGER	75.000	SD
0400	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	300.000	SD

Proposal: 240160 **Let Date:** January 16, 2025 **Call Order:** 195
J/P Num: 35446(04) **Proj. Num:** TAP-273D(099)IG
Counties: WAGONER
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALK)
CITY STREET (E. PECAN STREET): FROM SH-72, EXTEND EAST IN COWETA.
PROJECT LENGTH = 0.830 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC			
0410	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
0420	836 7100	REGULATORY OR WARNING SIGN ASSEMBLY	2.000	EA
0430	850(A)1200	SHEET ALUMINUM SIGNS	33.000	SF
0440	851(C)2415	2" SQUARE TUBE POST	12.000	LF
0450	856(A)8218	(SP) TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	412.000	LF
0004	STAKING			
0460	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0470	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0480	641 2110	MOBILIZATION	1.000	LSUM