Proposal:240192 **Let Date:**January 15, 2026 **Call Order:**780
J/P Num:34066(04) **Proj. Num:**TAP-272C(363)IG
Counties:TULSA
Description:PEDESTRIAN AND BIKE IMPROVEMENTS
BROKEN ARROW CREEK TRAIL (S 1ST PL/S MAIN ST/W BOSTON ST): FROM WASHINGTON ST (E 91ST ST), EXTEND SOUTH AND WEST IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 1.18 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	1,317.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	905.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	5,112.000	LF
0050	230(A)7200	SOLID SLAB SODDING	4,807.000	SY
0060	240(A)2210	REMOVING TREES 13" TO 18" IN DIAMETER	1.000	EA
0070	303(A)1200	AGGREGATE BASE TYPE A	649.000	CY
0080	310(B)5300	SUBGRADE, METHOD B	5,256.000	SY
0090	325 0100	SEPARATOR FABRIC	500.000	SY
0100	326(B)1300	GEOGRID REINFORCEMENT	500.000	SY
0110	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	38.300	TON
0120	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	403.800	TON
0130	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	2.900	TON
0140	411(I)2000	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	8.500	TON
0150	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	114.000	SY
0160	414(G)5800	P.C. CONCRETE FOR PAVEMENT	28.000	CY
0170	509(A)0200	CLASS AA CONCRETE	77.000	CY
0180	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	9.000	CY
0190	601(A)1100	TYPE I PLAIN RIPRAP	73.000	TON
0200	609 4100	(PL) PARKING BLOCK	12.000	EA
0210	609(A)4250	CONC.CURB(6" MNTBLE-INTEGRAL)	10.000	LF
0220	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	830.000	LF
0230	609(C)4410	CONCRETE HEADER CURB (8"X 18")	176.000	LF
0240	610(A)5210	5" CONCRETE SIDEWALK	1,457.000	SY
0250	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	404.000	SY
0260	610(B)5320	8" CONCRETE DRIVEWAY	153.000	SY
0270	610(I)6000	TACTILE WARNING DEVICE-NEW	342.000	SF
0280	611(A)7215	MANHOLE (5' DIA.)	3.000	EA
0290	611(A)7220	MANHOLE (6' DIA.)	1.000	EA
0300	611(B)7305	ADD'L.DEPTH IN MANHOLE (5' DIA.)	4.000	VF
0310	611(G)0362	INLET (SMD-TYPE 2B)	2.000	EA
0320	611(G)7700	SPECIAL INLET DRAIN	1.000	EA
0330	612(G)3800	FIRE HYDRANT RESET	2.000	EA
0340	612(H)3900	VALVE RESET	3.000	EA
0350	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	253.000	LF
0360	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	92.000	LF
0370	613(EE)5961	12" CORRUGATED POLYPROPYLENE PIPE	11.000	LF
0380	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	40.000	LF
0390	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	45.400	LF
0400	613(EE)5977	30" CORRUGATED POLYPROPYLENE PIPE	410.000	LF
0410	613(L)6620	28" X 18" PREFAB. CULVERT END SEC., ARCH	4.000	EA
0420	613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	1.000	EA
0430	613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0440	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0450	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0460	619(B)6300	REMOVAL OF HEADWALL	4.000	EA

Proposal:240192 **Let Date:**January 15, 2026 **Call Order:**780
J/P Num:34066(04) **Proj. Num:**TAP-272C(363)IG
Counties:TULSA
Description:PEDESTRIAN AND BIKE IMPROVEMENTS
BROKEN ARROW CREEK TRAIL (S 1ST PL/S MAIN ST/W BOSTON ST): FROM WASHINGTON ST (E 91ST ST), EXTEND SOUTH AND WEST IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 1.18 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	619(B)6352	REMOVAL OF FENCE	269.000	LF
0480	619(B)6356	REMOVAL OF CURB AND GUTTER	144.000	LF
0490	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	111.000	SY
0500	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	153.000	SY
0510	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	225.000	SY
0520	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	454.000	SY
0530	619(B)6400	REMOVAL OF CURB	132.000	LF
0540	619(B)6404	REMOVAL OF SIDEWALK	518.000	SY
0550	619(B)6436	REMOVAL OF CONCRETE DITCH LINER	45.000	LF
0560	619(B)6440	REMOVAL OF EXISTING PIPE	106.000	LF
0570	619(B)6500	REMOVAL OF WATER LINE	781.000	LF
0580	622(A)0200	PIPE RAILING	485.000	LF
0590	624 3100	(PL) ORNAMENTAL FENCE	52.000	LF
0600	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	253.000	LF
0610	631(A)9210	(SP)REMOVABLE BOLLARD	3.000	EA
0620	632 0100	(PL) SITESCAPING	1.000	LSUM
0002	BRIDGE			
0630	509(A)0210	CLASS AA CONCRETE	18.200	CY
0640	509(B)0300	CLASS A CONCRETE	29.700	CY
0650	510(D)1510	MSE RETAINING WALL	210.300	SY
0660	511(A)2210	REINFORCING STEEL	1,064.700	LB
0670	516(A)8210	DRILLED SHAFTS 24" DIAMETER	60.000	LF
0680	535 7170	PREFABRICATED PEDESTRIAN BRIDGE	1.000	EA
0690	601(A)1110	TYPE I PLAIN RIPRAP	218.000	TON
0003	TRAFFIC			
0700	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
0710	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	10.000	SD
0720	823 6116	LIGHTED CROSSWALK WARNING SYSTEM	1.000	LSUM
0730	850(A)1200	SHEET ALUMINUM SIGNS	241.000	SF
0740	851(C)2415	2" SQUARE TUBE POST	410.000	LF
0750	855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	1,054.000	LF
0760	855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	282.000	LF
0770	855(B)7313	(SP) TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	24.000	EA
0780	857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	100.000	LF
0790	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	480.000	SD
0800	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,095.000	SD
0810	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,050.000	SD
0820	880(E)6600	WARNING LIGHTS(TYPE A)	2,100.000	SD
0830	880(E)6610	WARNING LIGHTS(TYPE C)	7,490.000	SD
0840	880(F)6700	DRUMS	7,490.000	SD
0850	880(I)7000	FLAGGER	320.000	SD
0860	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	10.000	SD

Proposal: 240192 **Let Date:** January 15, 2026 **Call Order:** 780
J/P Num: 34066(04) **Proj. Num:** TAP-272C(363)IG
Counties: TULSA
Description: PEDESTRIAN AND BIKE IMPROVEMENTS
BROKEN ARROW CREEK TRAIL (S 1ST PL/S MAIN ST/W BOSTON ST): FROM WASHINGTON ST (E 91ST ST), EXTEND SOUTH AND WEST IN THE CITY OF BROKEN ARROW.
PROJECT LENGTH = 1.18 MILES

Line #		Item Description	Quantity	Unit
0004	STAKING			
0870	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0880	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0890	641 2110	MOBILIZATION	1.000	LSUM