Proposal:240197 **Let Date:**September 12, 2024 **Call Order:**100
J/P Num:38465(04) **Proj. Num:**STP-208F(121)3B
Counties:CADDO
Description:JOINT SEAL/REPAIR
US-281/SH-152: OVER SUGAR CREEK AND O'FLOW,
HONEY CREEK, UNNAMED CREEK, AND COBB CREEK,
AT MULTIPLE LOCATIONS IN DISTRICT VII.
PROJECT LENGTH = 0.00 MILES

	Line #		Item Description	Quantity	Unit
0001	BRIDGE 'A' NBI: 19996				
	0010	425 0100	DIAMOND GRINDING CONCRETE PAVEMENT	400.000	SY
	0020	505(C)6400	MULTIPLE LAYER POLYMER CONCRETE OVERLAY	1,500.000	SY
	0030	513(B)4300	CLASS B BRIDGE DECK REPAIR	150.000	SY
	0040	518(C)0400	RAPID CURE JOINT SEALANT	42.000	LF
	0050	521(A)2200	PNEUMATICALLY PLACED MORTAR	40.000	SY
	0060	601(A)1110	TYPE I PLAIN RIPRAP	500.000	TON
0002	BRIDGE 'B' NBI: 25817				
	0070	505(C)6400	MULTIPLE LAYER POLYMER CONCRETE OVERLAY	690.000	SY
	0080	513(B)4300	CLASS B BRIDGE DECK REPAIR	30.000	SY
	0090	518(C)0400	RAPID CURE JOINT SEALANT	265.000	LF
	0100	540 8100	(PL)REPAIR BRIDGE ITEMS	1.000	LSUM
0003	BRIDGE 'C' NBI: 26287				
	0110	425 0100	DIAMOND GRINDING CONCRETE PAVEMENT	200.000	SY
	0120	505(C)6400	MULTIPLE LAYER POLYMER CONCRETE OVERLAY	470.000	SY
	0130	513(B)4300	CLASS B BRIDGE DECK REPAIR	30.000	SY
	0140	518(C)0400	RAPID CURE JOINT SEALANT	150.000	LF
0004	BRIDGE 'D' NBI: 26288				
	0150	505(C)6400	MULTIPLE LAYER POLYMER CONCRETE OVERLAY	450.000	SY
	0160	513(B)4300	CLASS B BRIDGE DECK REPAIR	30.000	SY
	0170	518(C)0400	RAPID CURE JOINT SEALANT	150.000	LF
0005	BRIDGE 'E' NBI: 26289				
	0180	501(G)1800	CLSM BACKFILL	5.000	CY
	0190	505(C)6400	MULTIPLE LAYER POLYMER CONCRETE OVERLAY	1,670.000	SY
	0200	513(B)4300	CLASS B BRIDGE DECK REPAIR	70.000	SY
	0210	517 9110	ELASTOMERIC COATING	1,262.000	SF
	0220	518(C)0400	RAPID CURE JOINT SEALANT	370.000	LF
	0230	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	2.000	EA

Proposal:240197 **Let Date:**September 12, 2024 **Call Order:**100
J/P Num:38465(04) **Proj. Num:**STP-208F(121)3B
Counties:CADDO
Description:JOINT SEAL/REPAIR
US-281/SH-152: OVER SUGAR CREEK AND O'FLOW,
HONEY CREEK, UNNAMED CREEK, AND COBB CREEK,
AT MULTIPLE LOCATIONS IN DISTRICT VII.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0006	TRAFFIC CONTROL			
0240	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	120.000	SD
0250	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	31,540.000	LF
0260	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	3,000.000	EA
0270	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	15,000.000	LF
0280	871(B)2300	CONST.ZONE IMPACT ATTEN.	240.000	SD
0290	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,850.000	LF
0300	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	3,900.000	LF
0310	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	670.000	SD
0320	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	270.000	SD
0330	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,730.000	SD
0340	880(E)6607	WARNING LIGHTS(TYPE B)	1,200.000	SD
0350	880(E)6616	WARNING LIGHTS(TYPE D)	2,130.000	SD
0360	880(F)6700	DRUMS	670.000	SD
0370	880(G)6805	CHANNELIZER CONES	1,470.000	SD
0380	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	268.000	SD
0007	TRAFFIC SIGNING AND STRIPING			
0390	856(A)8204	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	15,000.000	LF
0008	CONSTRUCTION			
0400	641 2100	MOBILIZATION	1.000	LSUM