Proposal:240198 **Let Date:**October 10, 2024 **Call Order:**310
J/P Num:36148(04) **Proj. Num:**STP-214B(165)AG
Counties:CLEVELAND
Description:GRADE, DRAIN, AND SURFACE
CITY STREET (JENKINS AVENUE):
FROM 0.1 MILES SOUTH OF IMHOFF ROAD, EXTEND NORTH IN NORMAN.
PROJECT LENGTH = 1.650 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	33,363.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	5,701.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	9,333.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	144.000	LF
0070	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	63.000	EA
0080	230(A)7200	SOLID SLAB SODDING	24,557.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	15.000	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	1,594.000	CY
0110	307(K)4200	STABILIZED SUBGRADE	58,915.000	SY
0120	408 8100	PRIME COAT	3,882.000	GAL
0130	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,981.000	TON
0140	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	78.000	TON
0150	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	44,597.000	SY
0160	414(G)5800	P.C. CONCRETE FOR PAVEMENT	10,492.000	CY
0170	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	182.000	CY
0180	509(A)0200	CLASS AA CONCRETE	498.000	CY
0190	509(B)0300	CLASS A CONCRETE	96.000	CY
0200	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	34.000	CY
0210	509(D)0500	CLASS C CONCRETE	7.000	CY
0220	511(A)2200	REINFORCING STEEL	118,067.000	LB
0230	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	28,803.000	LF
0240	609(B)4300	COMBINED CURB & GUTTER(4" MOUNTABLE)	460.000	LF
0250	610(A)5210	5" CONCRETE SIDEWALK	9,887.000	SY
0260	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	2,805.000	SY
0270	610(I)6000	TACTILE WARNING DEVICE-NEW	603.000	SF
0280	610(J)6100	(PL) STAMPED CONCRETE FINISH	116.000	SY
0290	611(A)7211	(PL) MANHOLE (4' DIA.)	24.000	EA
0300	611(A)7216	(PL) MANHOLE (5' DIA.)	2.000	EA
0310	611(A)7221	(PL) MANHOLE (6' DIA.)	2.000	EA
0320	611(G)7754	INLET CI DES. 2 (STD)	20.000	EA
0330	611(G)7758	INLET CI DES. 2 (B)	16.000	EA
0340	611(G)7762	INLET CI DES. 2 (C)	5.000	EA
0350	611(G)7766	INLET CI DES. 2 (D)	1.000	EA
0360	611(G)7770	INLET CI DES. 2 (2B)	2.000	EA
0370	611(G)7786	INLET CI DES. 3 (STD)	4.000	EA
0380	611(G)7790	INLET CI DES. 3 (B)	4.000	EA
0390	611(G)7794	INLET CI DES. 3 (D)	2.000	EA
0400	611(G)7802	INLET CI DES. 3 (B-D)	3.000	EA
0410	611(G)9000	INLET CDI RCP DES. 1	1.000	EA
0420	611(G)9012	INLET CDI RCP DES. 4	1.000	EA
0430	611(L)1600	JUNCTION BOXES	599.000	CF
0440	612(A)3201	(PL) MANHOLES ADJUST TO GRADE	6.000	EA
0450	612(E)3600	VALVE BOXES ADJUST TO GRADE	6.000	EA
0460	613(A)5204	15" R.C.PIPE CLASS III	45.000	LF

Proposal:240198 **Let Date:**October 10, 2024 **Call Order:**310
J/P Num:36148(04) **Proj. Num:**STP-214B(165)AG
Counties:CLEVELAND
Description:GRADE, DRAIN, AND SURFACE
CITY STREET (JENKINS AVENUE):
FROM 0.1 MILES SOUTH OF IMHOFF ROAD, EXTEND NORTH IN NORMAN.
PROJECT LENGTH = 1.650 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	613(A)5208	18" R.C.PIPE CLASS III	2,995.000	LF
0480	613(A)5216	24" R.C.PIPE CLASS III	1,816.000	LF
0490	613(A)5220	30" R.C.PIPE CLASS III	39.000	LF
0500	613(A)5224	36" R.C.PIPE CLASS III	571.000	LF
0510	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	157.000	LF
0520	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	122.000	LF
0530	613(M)6964	TYPE B4 CULVERT END TREATMENT	1.000	EA
0540	613(M)6972	TYPE D4 CULVERT END TREATMENT	1.000	EA
0550	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0560	619(B)6300	REMOVAL OF HEADWALL	26.000	EA
0570	619(B)6352	REMOVAL OF FENCE	175.000	LF
0580	619(B)6356	REMOVAL OF CURB AND GUTTER	13,683.000	LF
0590	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	3,536.000	SY
0600	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	32,548.000	SY
0610	619(B)6368	REMOVAL OF DRAINAGE INLETS	34.000	EA
0620	619(B)6372	REMOVAL OF MANHOLES	10.000	EA
0630	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	1,938.000	SY
0640	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	598.000	SY
0650	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	29.000	SY
0660	619(B)6404	REMOVAL OF SIDEWALK	5,439.000	SY
0670	619(B)6440	REMOVAL OF EXISTING PIPE	4,038.000	LF
0680	619(C)6600	SAWING PAVEMENT	1,409.000	LF
0002	LANDSCAPING AND IRRIGATION			
0690	231(A)8200	TREES	93.000	EA
0700	231(B)8300	SHRUBS	3,839.000	EA
0710	231(E)8600	(PL) LANDSCAPING	1.000	LSUM
0720	602(C)2410	FILTER FABRIC	1,050.000	SY
0730	616 2110	(PL) IRRIGATION SYSTEM	1.000	LSUM
0740	616(F)3015	METER INSTALLATION 1 1/2"	1.000	EA
0750	632 0100	(PL) SITESCAPING	1.000	LSUM

Proposal:240198 **Let Date:**October 10, 2024 **Call Order:**310
J/P Num:36148(04) **Proj. Num:**STP-214B(165)AG
Counties:CLEVELAND
Description:GRADE, DRAIN, AND SURFACE
CITY STREET (JENKINS AVENUE):
FROM 0.1 MILES SOUTH OF IMHOFF ROAD, EXTEND NORTH IN NORMAN.
PROJECT LENGTH = 1.650 MILES

Line #		Item Description	Quantity	Unit
0003	BASE BID - WATER LINE IMPROVEMENTS			
0760	509(B)0300	CLASS A CONCRETE	10.000	CY
0770	612(I)4000	WATER METER RESET	15.000	EA
0780	612(J)4100	WATER LINE LOWERED	100.000	LF
0790	616(A)2292	DUCTILE IRON FITTINGS	22,000.000	LB
0800	616(B)2340	8" POLYVINYL CHLORIDE (PVC) PIPE	60.000	LF
0810	616(B)2352	12" POLYVINYL CHLORIDE (PVC) PIPE	2,400.000	LF
0820	616(B)2372	24" POLYVINYL CHLORIDE (PVC) PIPE	890.000	LF
0830	616(D)2650	8" GATE VALVE	1.000	EA
0840	616(D)2658	12" GATE VALVE	6.000	EA
0850	616(D)2688	24" BUTTERFLY VALVE	4.000	EA
0860	616(D)2874	6" MASTER METER VAULT	1.000	EA
0870	616(G)3111	FIRE HYDRANT AND ASSEMBLY	20.000	EA
0880	616(I)3339	36" STEEL CASING	340.000	LF
0890	616(N)3820	WET CONNECTION (8")	3.000	EA
0900	616(N)3825	WET CONNECTION (6")	1.000	EA
0910	616(N)3835	WET CONNECTION (12")	3.000	EA
0920	619(B)6536	CUT & PLUG 6" WATER LINE	4.000	EA
0930	619(B)6546	ABANDON 12" WATER LINE	1.000	EA

Proposal:240198 **Let Date:**October 10, 2024 **Call Order:**310
J/P Num:36148(04) **Proj. Num:**STP-214B(165)AG
Counties:CLEVELAND
Description:GRADE, DRAIN, AND SURFACE
CITY STREET (JENKINS AVENUE):
FROM 0.1 MILES SOUTH OF IMHOFF ROAD, EXTEND NORTH IN NORMAN.
PROJECT LENGTH = 1.650 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC SIGNAL			
0940	616(P)4132	4" HDPE PIPE (BORED)	553.000	LF
0950	802(B)0340	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
0960	802(C)0430	2" HIGH DENSITY PE PIPE - TRENCHED	925.000	LF
0970	802(C)0440	3" HIGH DENSITY PE PIPE - TRENCHED	100.000	LF
0980	803(A)1210	PULL BOX(SIZE I)	2.000	EA
0990	803(A)1220	PULL BOX(SIZE II)	10.000	EA
1000	804(A)2200	STRUCTURAL CONCRETE	53.000	CY
1010	804(B)2300	REINFORCING STEEL	7,350.000	LB
1020	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
1030	806(A)4248	32'MH POLE 35'TS & 10'LMA(G.STL.)	4.000	EA
1040	806(A)4260	32'MH POLE 50'TS & 10'LMA(G.STL.)	3.000	EA
1050	806(A)4264	32'MH POLE,55'TS & 10'LMA(G.STL.)	1.000	EA
1060	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	13.000	EA
1070	809(A)7200	ROADWAY LUMINAIRE	8.000	EA
1080	811 9120	1/C NO.6 ELECT.COND.	2,047.000	LF
1090	811 9130	1/C NO.10 ELECT.COND.	1,190.000	LF
1100	818(A)4225	(SP) FIBER OPTIC CABLE, 216 SMF	350.000	LF
1110	818(B)4300	(SP)FIBER OPTIC PATCH PANEL, 12 PORT	2.000	EA
1120	818(C)4400	(SP)FIBER OPTIC CABLE SPLICE	8.000	EA
1130	818(D)4500	(SP)FIBER OPTIC CABLE TERMINATION	24.000	EA
1140	818(F)4600	(SP) SHIELD ISOLATION PEDESTAL	1.000	EA
1150	819 5100	(PL)FIBER OPTIC & COMMUNICATION EQUIP.	1.000	LSUM
1160	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
1170	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
1180	830 2100	PEDESTRIAN PUSH BUTTON	16.000	EA
1190	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	16.000	EA
1200	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	16.000	EA
1210	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	8.000	EA
1220	833 5100	BACKPLATE	24.000	EA
1230	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	5,400.000	LF
1240	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	660.000	LF
1250	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	940.000	LF
1260	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	100.000	LF
1270	840(B)0300	E.P.S. OPTICAL DETECTOR	2.000	EA
1280	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	100.000	LF
1290	840(D)0510	E.P.S. 4 CHANNEL PHASE SELECTOR	2.000	EA
1300	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	145.000	SF

Proposal:240198 **Let Date:**October 10, 2024 **Call Order:**310
J/P Num:36148(04) **Proj. Num:**STP-214B(165)AG
Counties:CLEVELAND
Description:GRADE, DRAIN, AND SURFACE
CITY STREET (JENKINS AVENUE):
FROM 0.1 MILES SOUTH OF IMHOFF ROAD, EXTEND NORTH IN NORMAN.
PROJECT LENGTH = 1.650 MILES

Line #		Item Description	Quantity	Unit
0005	TRAFFIC SIGNING AND STRIPING			
1310	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	10.000	EA
1320	850(A)1200	SHEET ALUMINUM SIGNS	993.000	SF
1330	851(C)2430	2 1/2" SQUARE TUBE POST	931.000	LF
1340	856(A)8200	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	16,794.000	LF
1350	856(A)8204	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	11,322.000	LF
1360	856(A)8208	TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	1,059.000	LF
1370	856(A)8212	TRAFFIC STRIPE(MULTI-POLY)(12" WIDE)	355.000	LF
1380	856(A)8216	TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	1,715.000	LF
1390	856(B)8304	TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	68.000	EA
1400	856(B)8308	TRAFFIC STRIPE(MULTI-POLY.)(SYMBOLS)	63.000	EA
1410	856(B)8312	TRAFFIC STRIPE(MULTI-POLY.)(WORDS)	3.000	EA
0006	TRAFFIC CONTROL			
1420	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	87,077.000	LF
1430	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	46,561.000	LF
1440	871(B)2300	CONST.ZONE IMPACT ATTEN.	540.000	SD
1450	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,082.000	LF
1460	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,710.000	SD
1470	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	35,310.000	SD
1480	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	12,900.000	SD
1490	880(E)6607	WARNING LIGHTS(TYPE B)	29,130.000	SD
1500	880(F)6700	DRUMS	88,260.000	SD
1510	880(I)7000	FLAGGER	80.000	SD
0007	TRAFFIC LIGHTING			
1520	802(C)0425	2" HIGH DENSITY PE PIPE - BORED	1,605.000	LF
1530	802(C)0430	2" HIGH DENSITY PE PIPE - TRENCHED	3,675.000	LF
1540	803(A)1210	PULL BOX(SIZE I)	35.000	EA
1550	804(A)2200	STRUCTURAL CONCRETE	30.000	CY
1560	804(B)2300	REINFORCING STEEL	1,768.000	LB
1570	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	11.000	EA
1580	806(C)4492	30' MTG & 8' HLMA(G.STL.)	25.000	EA
1590	811 9115	1/C NO.4 ELECT.COND.	11,570.000	LF
0008	STAKING			
1600	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0009	CONSTRUCTION			
1610	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1620	641 2110	MOBILIZATION	1.000	LSUM
0010	ADD ALT. 1 - WATER LINE IMPROVEMENTS			
1630	616(A)2292	DUCTILE IRON FITTINGS	4,000.000	LB
1640	616(B)2356	16" POLYVINYL CHLORIDE (PVC) PIPE	840.000	LF
1650	616(D)2666	16" GATE VALVE	1.000	EA
1660	616(I)3335	30" STEEL CASING	280.000	LF
1670	616(N)3837	WET CONNECTION (16")	1.000	EA

Proposal:240198 **Let Date:**October 10, 2024 **Call Order:**310
J/P Num:36148(04) **Proj. Num:**STP-214B(165)AG
Counties:CLEVELAND
Description:GRADE, DRAIN, AND SURFACE
CITY STREET (JENKINS AVENUE):
FROM 0.1 MILES SOUTH OF IMHOFF ROAD, EXTEND NORTH IN NORMAN.
PROJECT LENGTH = 1.650 MILES

Line #		Item Description	Quantity	Unit
0011	ADD ALT. 2 - WATER LINE IMPROVEMENTS			
1680	619(B)6531	ABANDON 8" WATER LINE	1.000	EA
1690	619(B)6537	ABANDON 6" WATER LINE	1.000	EA