Proposal:240201 **Let Date:**November 21, 2024 **Call Order:**520
J/P Num:38466(04) **Proj. Num:**STP-220F(098)3B
Counties:CUSTER
Description:JOINT SEAL/REPAIR
SH-34: OVER WASHITA RIVER AND O'FLOWS,
AND QUARTER MASTER CREEK, AT MULTIPLE LOCATIONS IN DISTRICT V.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0001	BRIDGE 'A' NBI: 25271			
0010	509(B)0320	CLASS A CONCRETE	15.500	CY
0020	510(C)1450	SLOPE WALL (5")	305.000	SY
0030	511(A)2210	REINFORCING STEEL	520.000	LB
0040	513(B)4300	CLASS B BRIDGE DECK REPAIR	40.000	SY
0050	518(C)0400	RAPID CURE JOINT SEALANT	440.000	LF
0060	523(C)3400	DECK AREA SEALED (FLOODCOATS)	1,680.000	SY
0002	BRIDGE 'B' NBI: 25276			
0070	509(B)0320	CLASS A CONCRETE	15.500	CY
0080	510(C)1450	SLOPE WALL (5")	305.000	SY
0090	511(A)2210	REINFORCING STEEL	520.000	LB
0100	513(B)4300	CLASS B BRIDGE DECK REPAIR	30.000	SY
0110	518(C)0400	RAPID CURE JOINT SEALANT	315.000	LF
0120	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	100.000	LF
0130	520(C)1400	EPOXY RESIN, ABOVE WATER	2.000	GAL
0140	521(A)2200	PNEUMATICALLY PLACED MORTAR	20.000	SY
0150	523(C)3400	DECK AREA SEALED (FLOODCOATS)	2,000.000	SY
0003	BRIDGE 'C' NBI: 25277			
0160	513(B)4300	CLASS B BRIDGE DECK REPAIR	20.000	SY
0170	518(C)0400	RAPID CURE JOINT SEALANT	146.000	LF
0180	523(C)3400	DECK AREA SEALED (FLOODCOATS)	825.000	SY
0190	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	2.000	EA
0004	BRIDGE 'D' NBI: 25204			
0200	501(G)1800	CLSM BACKFILL	5.000	CY
0210	509(B)0320	CLASS A CONCRETE	27.800	CY
0220	510(C)1450	SLOPE WALL (5")	361.000	SY
0230	511(A)2210	REINFORCING STEEL	680.000	LB
0240	513(B)4300	CLASS B BRIDGE DECK REPAIR	30.000	SY
0250	518(C)0400	RAPID CURE JOINT SEALANT	234.000	LF
0260	523(C)3400	DECK AREA SEALED (FLOODCOATS)	1,321.000	SY
0270	540 8136	(PL)REPAIR BRIDGE ITEM (TYPE B)	1.000	EA

Proposal:240201 **Let Date:**November 21, 2024 **Call Order:**520
J/P Num:38466(04) **Proj. Num:**STP-220F(098)3B
Counties:CUSTER
Description:JOINT SEAL/REPAIR
SH-34: OVER WASHITA RIVER AND O'FLOWS,
AND QUARTER MASTER CREEK, AT MULTIPLE LOCATIONS IN DISTRICT V.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0005	TRAFFIC CONTROL			
0280	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	150.000	SD
0290	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	28,000.000	LF
0300	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	2,700.000	EA
0310	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	15,500.000	LF
0320	871(B)2300	CONST.ZONE IMPACT ATTEN.	300.000	SD
0330	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,700.000	LF
0340	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	3,400.000	LF
0350	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,050.000	SD
0360	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	420.000	SD
0370	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,730.000	SD
0380	880(E)6607	WARNING LIGHTS(TYPE B)	1,890.000	SD
0390	880(E)6616	WARNING LIGHTS(TYPE D)	3,360.000	SD
0400	880(F)6700	DRUMS	1,050.000	SD
0410	880(G)6805	CHANNELIZER CONES	2,310.000	SD
0420	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	328.000	SD
0006	TRAFFIC SIGNING AND STRIPING			
0430	856(A)8204	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	15,500.000	LF
0007	CONSTRUCTION			
0440	641 2100	MOBILIZATION	1.000	LSUM