Proposal:240231 **Let Date:**October 10, 2024 **Call Order:**320
J/P Num:33898(04) **Proj. Num:**STP-220D(093)CI
Counties:CUSTER
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW 102): OVER BARNITZ CREEK,
2.4 MILES WEST OF US-183 NEAR CLINTON.
PROJECT LENGTH = 0.189 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(H)2900	EARTHWORK	1.000	LSUM
0030	221(B)2300	TEMPORARY SILT FENCE	1,260.000	LF
0040	221(E)2600	TEMPORARY SILT DIKE	100.000	LF
0050	230(A)7200	SOLID SLAB SODDING	5,100.000	SY
0060	233(A)0200	VEGETATIVE MULCHING	1.060	AC
0070	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	568.000	TON
0080	509(D)0500	CLASS C CONCRETE	10.000	CY
0090	611(G)7942	INLET GPI TYPE 1 (DES. 4)	1.000	EA
0100	611(H)0470	ADD'L DEPTH IN INLET GPI TYPE 1	3.650	VF
0110	613(B)5532	42" CORR. GALV. STEEL PIPE	38.000	LF
0120	619(B)6392	REMOVAL OF EXISTING STRUCTURES	1.000	EA
0002	BRIDGE			
0130	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
0140	501(F)1700	GRANULAR BACKFILL	82.000	CY
0150	503(A)4220	PRESTRESSED CONCRETE BEAMS (TYPE II)	517.000	LF
0160	504(D)5410	CONCRETE RAIL (TR3)	328.200	LF
0170	506(A)7200	STRUCTURAL STEEL	1,140.010	LB
0180	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000	EA
0190	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	12.000	EA
0200	509(A)0210	CLASS AA CONCRETE	114.400	CY
0210	509(B)0320	CLASS A CONCRETE	210.000	CY
0220	511(A)2210	REINFORCING STEEL	56,460.000	LB
0230	514(A)5210	PILES, FURNISHED (HP 10X42)	480.000	LF
0240	514(A)5220	PILES, FURNISHED (HP 12X53)	1,200.000	LF
0250	514(A)5230	PILES, FURNISHED (HP 12X74)	3,264.000	LF
0260	514(B)5310	PILES, DRIVEN (HP 10X42)	480.000	LF
0270	514(B)5320	PILES, DRIVEN (HP 12X53)	1,200.000	LF
0280	514(B)5330	PILES, DRIVEN (HP 12X74)	3,264.000	LF
0290	514(F)5700	PILE LOAD TEST (DYNAMIC)	2.000	EA
0300	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0310	518(B)0300	SEALED EXPANSION JOINTS	35.500	LF
0320	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	3,560.000	TON
0330	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	64.000	LF
0340	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	36.000	LF
0350	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0360	623(A)1210	BEAM GUARDRAIL W-BEAM SINGLE	43.750	LF
0370	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	1.000	EA
0380	623(F)1748	GUARDRAIL ANCHOR UNIT (TYPE II)	3.000	EA
0003	TRAFFIC			
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
0400	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
0410	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0420	880(E)6600	WARNING LIGHTS(TYPE A)	2,640.000	SD

Proposal: 240231 **Let Date:** October 10, 2024 **Call Order:** 320
J/P Num: 33898(04) **Proj. Num:** STP-220D(093)CI
Counties: CUSTER
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW 102): OVER BARNITZ CREEK,
2.4 MILES WEST OF US-183 NEAR CLINTON.
PROJECT LENGTH = 0.189 MILES

Line #		Item Description	Quantity	Unit
0004	STAKING			
0430	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0440	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0450	641 2110	MOBILIZATION	1.000	LSUM