Proposal:240236 **Let Date:**January 16, 2025 **Call Order:**245
J/P Num:33860(05) **Proj. Num:**STP-252F(109)PM
Counties:OKLAHOMA
Description:TRAFFIC SIGNING
I-35: FROM THE I-44 INTERCHANGE,
EXTEND NORTH IN OKLAHOMA CITY.
PROJECT LENGTH = 4.785 MILES

Line #		Item Description	Quantity	Unit
0001	TRAFFIC SIGNING			
0010	509(D)0500	CLASS C CONCRETE	20.490	CY
0020	511(A)2200	REINFORCING STEEL	843.000	LB
0030	516(A)8240	DRILLED SHAFTS 60" DIAMETER	108.000	LF
0040	804(A)2200	STRUCTURAL CONCRETE	24.220	CY
0050	804(B)2300	REINFORCING STEEL	4,516.000	LB
0060	805(A)3236	(PL)REMOVAL OF OVERHEAD SIGN STRUCTURE	4.000	EA
0070	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	100.000	EA
0080	850(A)1200	SHEET ALUMINUM SIGNS	1,116.810	SF
0090	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	1,840.000	SF
0100	850(B)1320	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	7,378.000	SF
0110	851(A)2200	4"@13 GALV.STL.WD.FLANGE BM.POST	501.500	LF
0120	851(A)2205	6"@15 GALV.STL.WD.FLANGE BM.POST	400.000	LF
0130	851(A)2220	8"@31 GALV.STL.WD.FLANGE BM.POST	55.000	LF
0140	851(C)2420	2 1/4" SQUARE TUBE POST	1,576.000	LF
0150	852(D)3536	OVHD.SN.STR., MONOTUBE TYPE B 100'	1.000	EA
0160	852(E)3600	OVHD.SN.STR., MONOTUBE TYPE C	1.000	EA
0170	870(A)1100	SAND FILLED IMPACT ATTEN.MODULE	57.000	EA
0002	TRAFFIC CONTROL			
0180	880(A)6220	ARROW DISPLAY(TYPE C)	1,800.000	SD
0190	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	21,600.000	SD
0200	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,000.000	SD
0210	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	19,800.000	SD
0220	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,400.000	SD
0230	880(E)6607	WARNING LIGHTS(TYPE B)	12,600.000	SD
0240	880(F)6700	DRUMS	34,200.000	SD
0250	880(G)6805	CHANNELIZER CONES	36,000.000	SD
0260	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	900.000	SD
0003	STAKING			
0270	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0280	641 2110	MOBILIZATION	1.000	LSUM