Proposal:240243 **Let Date:**October 17, 2024 **Call Order:**405
J/P Num:32382(04) **Proj. Num:**STP-225C(126)CI
Counties:GARVIN
Description:GRADE, DRAIN, SURFACE, BRIDGE AND APPROACHES
COUNTY ROAD (CITY LAKE ROAD): FROM THE SH-19 JUNCTION,
EXTEND NORTH NEAR PAULS VALLEY.
PROJECT LENGTH = 2.566 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	40,352.000	CY
0030	202(C)2400	ROCK EXCAVATION	2,000.000	CY
0040	202(D)2500	UNCLASSIFIED BORROW	200.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	8,525.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	798.000	LF
0080	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	20.000	CY
0090	221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	21.000	CY
0100	230(A)7200	SOLID SLAB SODDING	123,630.000	SY
0110	233(A)0200	VEGETATIVE MULCHING	25.550	AC
0120	242 4101	STABILIZED CONSTRUCTION EXIT	1.000	EA
0130	303(A)1200	AGGREGATE BASE TYPE A	4,784.000	CY
0140	307(E)3600	CEMENTITIOUS STABILIZED SUBGRADE	24,957.000	SY
0150	325 0100	SEPARATOR FABRIC	24,957.000	SY
0160	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	7,484.000	TON
0170	407(B)7300	TACK COAT	2,696.000	GAL
0180	408 8100	PRIME COAT	14,533.000	GAL
0190	409(A)9200	FABRIC REINFORCEMENT	33,404.000	SY
0200	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	6,785.000	TON
0210	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	7,879.000	TON
0220	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	400.000	TON
0230	412 3100	COLD MILLING PAVEMENT	2,934.000	SY
0240	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	110.000	CY
0250	509(A)0200	CLASS AA CONCRETE	50.100	CY
0260	509(D)0500	CLASS C CONCRETE	592.400	CY
0270	511(A)2200	REINFORCING STEEL	5,369.000	LB
0280	601(B)1220	TYPE I-A PLAIN RIPRAP	349.000	TON
0290	601(C)1300	TYPE I-A FILTER BLANKET	101.000	TON
0300	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	337.000	SY
0310	611(G)9016	INLET CDI RCP DES. 5	1.000	EA
0320	611(H)0696	ADD'L DEPTH IN INLET CDI RCP DES. 5	1.400	VF
0330	613(A)5216	24" R.C.PIPE CLASS III	8.000	LF
0340	613(A)5228	42" R.C.PIPE CLASS III	64.000	LF
0350	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	36.000	LF
0360	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	44.000	LF
0370	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	348.000	LF
0380	613(EE)5961	12" CORRUGATED POLYPROPYLENE PIPE	400.000	LF
0390	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	1,824.000	LF
0400	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	466.000	LF
0410	613(EE)5977	30" CORRUGATED POLYPROPYLENE PIPE	121.000	LF
0420	613(EE)5981	36" CORRUGATED POLYPROPYLENE PIPE	54.000	LF
0430	613(L)6620	28" X 18" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0440	613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0450	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0460	613(L)6732	42" PREFAB. CULVERT END SEC., ROUND	1.000	EA

Proposal:240243 **Let Date:**October 17, 2024 **Call Order:**405
J/P Num:32382(04) **Proj. Num:**STP-225C(126)CI
Counties:GARVIN
Description:GRADE, DRAIN, SURFACE, BRIDGE AND APPROACHES
COUNTY ROAD (CITY LAKE ROAD): FROM THE SH-19 JUNCTION,
EXTEND NORTH NEAR PAULS VALLEY.
PROJECT LENGTH = 2.566 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	613(M)6960	TYPE A4 CULVERT END TREATMENT	78.000	EA
0480	613(M)6964	TYPE B4 CULVERT END TREATMENT	18.000	EA
0490	613(M)6968	TYPE C4 CULVERT END TREATMENT	2.000	EA
0500	613(M)6972	TYPE D4 CULVERT END TREATMENT	1.000	EA
0510	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0520	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	7,585.000	SY
0530	619(C)6600	SAWING PAVEMENT	23,183.000	LF
0540	624(A)3200	FENCE-STYLE WWF	576.000	LF
0550	624(B)3360	GATES-STYLE WWF (4.5'HIGH X 16'LONG)	3.000	EA
0560	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	3,754.000	LF
0570	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	6,510.000	LF
0580	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	342.000	LF
0590	624(E)3620	FENCE-STYLE CLF (6'HIGH, CLASS A)	672.000	LF
0600	624(F)3712	GATES-STYLE CLF (4'HIGH X 12'LONG)	2.000	EA
0610	624(F)3721	GATES-STYLE CLF (4'HIGH X 16'LONG)	2.000	EA
0620	624(F)3766	GATES-STYLE CLF (6'HIGH X 12'LONG)	2.000	EA
0630	624(F)3772	GATES-STYLE CLF (6'HIGH X 16'LONG)	1.000	EA
0640	629(A)7200	MAILBOX INSTALLATION-SINGLE	29.000	EA
0650	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	6.000	EA
0660	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	35.000	EA
0670	629(E)7600	MAILBOX	44.000	EA
0002	BRIDGE			
0680	202(A)2210	UNCLASSIFIED EXCAVATION	725.000	CY
0690	202(C)2400	ROCK EXCAVATION	100.000	CY
0700	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	776.000	CY
0710	509(A)0210	CLASS AA CONCRETE	340.500	CY
0720	511(A)2210	REINFORCING STEEL	49,008.000	LB
0730	601(B)1230	TYPE I-A PLAIN RIPRAP	250.000	TON
0740	601(C)1310	TYPE I-A FILTER BLANKET	230.000	TON
0750	619(B)6488	REMOVAL OF EXISTING RIPRAP	1.000	LSUM

Proposal:240243 **Let Date:**October 17, 2024 **Call Order:**405
J/P Num:32382(04) **Proj. Num:**STP-225C(126)CI
Counties:GARVIN
Description:GRADE, DRAIN, SURFACE, BRIDGE AND APPROACHES
COUNTY ROAD (CITY LAKE ROAD): FROM THE SH-19 JUNCTION,
EXTEND NORTH NEAR PAULS VALLEY.
PROJECT LENGTH = 2.566 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC			
0760	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	20.000	EA
0770	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	6.000	EA
0780	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	360.000	SD
0790	850(A)1200	SHEET ALUMINUM SIGNS	196.000	SF
0800	851(C)2430	2 1/2" SQUARE TUBE POST	564.000	LF
0810	853 5115	DELINEATORS(TYPE 2, CODE 1)	3.000	EA
0820	856(A)8200	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	53,920.000	LF
0830	856(A)8216	TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	87.000	LF
0840	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	38,152.000	SD
0850	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,704.000	SD
0860	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,252.000	SD
0870	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,810.000	SD
0880	880(E)6600	WARNING LIGHTS(TYPE A)	4,080.000	SD
0890	880(G)6805	CHANNELIZER CONES	5,800.000	SD
0900	880(I)7000	FLAGGER	720.000	SD
0910	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	300.000	SD
0004	STAKING			
0920	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0930	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0940	641 2100	MOBILIZATION	1.000	LSUM